

Attachments

Debris Basin Drawings

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EA\Project Data\Design\Structures\UT-1024-1801_Design Base NEW BELOW.dwg - BASIN 1 - 10/05/2018 01:36pm .lisa



PRELIMINARY
NOT FOR CONSTRUCTION

REV	DATE	BY	DESCRIPTION

REVISIONS

SCALE
 HORIZONTAL
 1" = 150'
 VERTICAL
 N/A

WARNING
 0 1/2 1
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE




2162 West Grove Parkway
 Suite 400
 Pleasant Grove, UT 84062
 (801) 763-5100

SANTAQUIN DEBRIS BASINS
BASIN 1 - BELOW GRADE

DESIGNED	DATE	PROJECT NO.
###	###	PG-1024-1801
DRAWN	DATE	SHEET NO.
###	###	# OF #
CHECKED	DATE	DRAWING NO.
###	###	P-01

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EA\Project Data\Design\Structures\UT-1024-1801_Design Base NEW BELOW.dwg - BASIN 3A - 10/05/2018 01:37 pm. llsj



PRELIMINARY

NOT FOR CONSTRUCTION

REV	DATE	BY	DESCRIPTION

REVISIONS

SCALE

HORIZONTAL	1" = 60'
VERTICAL	N/A

WARNING

0
0
1/2
1

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE




2162 West Grove Parkway
 Suite 400
 Pleasant Grove, UT 84062
 (801) 763-5100

SANTAQUIN DEBRIS BASINS

BASIN 3A - BELOW GRADE (WATERSHEDS 2 & 3 COMBINED)

DESIGNED	DATE	PROJECT NO.
###	###	PG-1024-1801
DRAWN	DATE	SHEET NO.
###	###	# OF #
CHECKED	DATE	DRAWING NO.
###	###	P-05



C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EA\Project Data\Design\Structures\UT-1024-1801_Design Base NEW ABOVE.dwg - BASIN 4E - 10/05/2018 01:33pm. llsj

PRELIMINARY

NOT FOR CONSTRUCTION

REV	DATE	BY	DESCRIPTION

REVISIONS

SCALE

HORIZONTAL
1" = 100'

VERTICAL
N/A

WARNING

0 1/2 1

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

HORROCKS


ENGINEERS

2162 West Grove Parkway
Suite 400
Pleasant Grove, UT 84062
(801) 763-5100

SANTAQUIN DEBRIS BASINS

BASIN 4E - ABOVE GRADE (WATERSHED ONLY)

DESIGNED	DATE	PROJECT NO.
####	####	PG-1024-1801
DRAWN	DATE	SHEET NO.
####	####	5 OF 12
CHECKED	DATE	DRAWING NO.
####	####	P-05



C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EA\Project Data\Design\Structures\UT-1024-1801_Design Base NEW BELOW.dwg - BASIN 5 - 10/05/2018 01:39pm .lisa.j

PRELIMINARY

NOT FOR CONSTRUCTION

REV	DATE	BY	DESCRIPTION

REVISIONS

SCALE

HORIZONTAL
1" = 150'

VERTICAL
N/A

WARNING

0 1/2 1

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

HORROCKS


ENGINEERS

2162 West Grove Parkway
Suite 400
Pleasant Grove, UT 84062
(801) 763-5100

SANTAQUIN DEBRIS BASINS

BASIN 5 - BELOW GRADE

DESIGNED	DATE	PROJECT NO.
###	###	PG-1024-1801
DRAWN	DATE	SHEET NO.
###	###	# OF #
CHECKED	DATE	DRAWING NO.
###	###	P-12



C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EA\Project Data\Design\Structures\UT-1024-1801_Design Base NEW ABOVE.dwg - BASIN 6A - 10/05/2018 01:34pm. llsj

PRELIMINARY	
NOT FOR CONSTRUCTION	
REV	DATE
REVISIONS	

SCALE
HORIZONTAL
1" = 100'
VERTICAL
N/A

WARNING

0 1/2 1

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

HORROCKS

ENGINEERS

2162 West Grove Parkway
 Suite 400
 Pleasant Grove, UT 84062
 (801) 763-5100

SANTAQUIN DEBRIS BASINS

BASIN 6A - ABOVE GRADE

DESIGNED	DATE	PROJECT NO.
####	####	PG-1024-1801
DRAWN	DATE	SHEET NO.
####	####	# OF #
CHECKED	DATE	DRAWING NO.
####	####	P-07

Appendices

- Appendix A: Reservoir Routing and Basin Design Summary
- Appendix B: Approach B Drawdown Calculations
- Appendix C: Spillway
- Appendix D: Pre and Post Velocity and Depth Flood Maps
- Appendix E: Induced Flooding Maps
- Appendix F: Flow Comparison Maps
- Appendix G: Dam Breach Hydrographs, Dam Breach Maps
- Appendix H: Wave Runup Calculations

Appendix A: Reservoir Routing and Basin Design Summary

Santaquin Debris Basin SITES Results Summary

NOTE: All Runs Below are singular basin systems unless otherwise stated. Results from multi-basin systems will be identified in the Site Title.

Prepared by: Mickey Navidomskis

Date Started: 5/23/2018

Most Recent Update: 7/26/2018

Site	1 Above Grade																
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition	
Reservoir Bottom Elevation (ft)	5395	5395	5395	5395	5395	5395	5395	5395	5395	5395	5395	5395	5395	NA	5395	5395	
Original Dam Crest (ft)	5410	5410	5410	5410	5410	5410	5410	5410	5410	5410	5410	5410	5410	NA	5410	5410	
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5398.5	5398.5	5398.5	5398.5	5398.5	5398.5	5398.5	5398.5	5398.5	5398.5	5398.5	5398.5	5398.5	NA	5398.5	5398.5	
Principal Spillway Elevation Weir (ft)	5406.64	5407.07	5407	5407	5407	5407	5407	5407	5407	5407	5407	5407	5407	NA	5407	5407	
Auxillary Spillway Elevation (ft)	5406.65	5407.08	5408.5	5408.5	5408.5	5408.5	5408.5	5408.5	5408.5	5408.5	5408.5	5408.5	5408.5	NA	5408.5	5408.5	
Volume at Principal Spillway (acre-ft)	*	*	17.2	17.2	17.2	17.2	17.2	17.2	17.2	17.2	17.2	17.2	17.2	NA	17.2	17.2	
Volume at Auxillary Spillway (acre-ft)	*	*	20.35	20.35	20.35	20.35	20.35	20.35	20.35	20.35	20.35	20.35	20.35	NA	20.35	20.35	
Volume at Low Stage Orifice Crest (acre-ft)	3.43	3.43	3.43	3.43	3.43	3.43	3.43	3.43	3.43	3.43	3.43	3.43	3.43	NA	3.43	3.43	
Principal Spillway Weir Length (ft)	14	14	14	14	14	14	14	14	14	14	14	14	14	NA	14	14	
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50	
Principal Spillway Outlet Pipe Diameter (in)	42	42	42	42	42	42	42	42	42	42	42	42	42	NA	42	42	
Scaling Factor	1.316	1.316	1.316	1.316	1.316	1.316	1.316	1.316	1.316	1.316	1.316	1.316	1.316	NA	1.316	1.316	
PSH Peak Inflow (cfs)	61.44	67.51	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Peak Outflow (cfs)	13.71	15.88	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Max Water Surface Elevation (ft)	5406.64	5407.07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
FBH/Storm Peak Inflow (cfs)	548	548	548	507	183.5	11.9	41.8	79.6	146.2	217.1	300.6	403.8	559.7	NA	418.5	174	
FBH/Storm Peak Outflow (cfs)	465.2	445.9	515.1	502.6	183.4	3.4	6.6	9.1	12	18	60.5	146.4	334.8	NA	149	12.8	
FBH/Storm Peak Principal Spillway Outflow (cfs)	109.2	87.9	135.1	203.6	145.4	3.4	6.6	9.1	12	18	60.5	121.4	196.8	NA	125	12.8	
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	356	358	380	299	38	0	0	0	0	0	0	25	138	NA	24	0	
FBH/Storm Initial Water Surface Elevation (ft)	5398.52	5398.52	5407	5407	5407	5398.5	5398.5	5398.5	5398.5	5398.5	5398.5	5398.5	5398.5	NA	5398.5	5398.5	
FBH/Storm Max Water Surface Elevation (ft)	5408.5	5409.04	5410.56	5410.29	5409.08	5399.80	5401.01	5402.51	5405.10	5407.16	5408.03	5408.82	5409.59	NA	5408.86	5405.95	
Height of Water Above Auxillary Spillway (ft)	1.85	1.96	2.06	1.79	0.58	-8.7	-7.49	-5.99	-3.4	-1.34	-0.47	0.32	1.09	NA	0.36	-2.55	
Final Dam Crest (ft)	5409.65	5410.08	5411.5	5411.5	5411.5	5411.5	5411.5	5411.5	5411.5	5411.5	5411.5	5411.5	5411.5	NA	5411.5	5411.5	
Site	1 Below Grade																
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition	
Reservoir Bottom Elevation (ft)	5363.1	5363.1	5363.1	5363.1	5363.1	5363.1	5363.1	5363.1	5363.1	5363.1	5363.1	5363.1	5363.1	NA	5363.1	5363.1	
Original Dam Crest (ft)	5378	5378	5378	5378	5378	5378	5378	5378	5378	5378	5378	5378	5378	NA	5378	5378	
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5366.5	5366.5	5366.5	5366.5	5366.5	5366.5	5366.5	5366.5	5366.5	5366.5	5366.5	5366.5	5366.5	NA	5366.5	5366.5	
Principal Spillway Elevation Weir (ft)	5371.84	5375.12	5375	5375	5375	5375	5375	5375	5375	5375	5375	5375	5375	NA	5375	5375	
Auxillary Spillway Elevation (ft)	5371.85	5375.13	5376.6	5376.6	5376.6	5376.6	5376.6	5376.6	5376.6	5376.6	5376.6	5376.6	5376.6	NA	5376.6	5376.6	
Volume at Principal Spillway (acre-ft)	*	*	17.2	17.2	17.2	17.2	17.2	17.2	17.2	17.2	17.2	17.2	17.2	NA	17.2	17.2	
Volume at Auxillary Spillway (acre-ft)	20.47	20.47	20.47	20.47	20.47	20.47	20.47	20.47	20.47	20.47	20.47	20.47	20.47	NA	20.47	20.47	
Volume at Low Stage Orifice Crest (acre-ft)	3.71	3.71	3.71	3.71	3.71	3.71	3.71	3.71	3.71	3.71	3.71	3.71	3.71	NA	3.71	3.71	
Principal Spillway Weir Length (ft)	12	12	12	12	12	12	12	12	12	12	12	12	12	NA	12	12	
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50	
Principal Spillway Outlet Pipe Diameter (in)	30	30	30	30	30	30	30	30	30	30	30	30	30	NA	42	30	
Scaling Factor	1.226	1.226	1.226	1.226	1.226	1.226	1.226	1.226	1.226	1.226	1.226	1.226	1.226	NA	1.226	1.226	
PSH Peak Inflow (cfs)	50.33	50.72	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Peak Outflow (cfs)	11	12	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Max Water Surface Elevation (ft)	5371.84	5372.86	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
FBH/Storm Peak Inflow (cfs)	221.1	221.1	221.1	110.5	42.7	11.9	41.8	79.6	144.7	217.1	300.6	403.8	559.7	NA	418.5	174	
FBH/Storm Peak Outflow (cfs)	131.3	101.1	166.4	103	41.5	3.5	6.7	9.6	12.1	29.4	84.8	183.1	317.6	NA	149.6	12.9	
FBH/Storm Peak Principal Spillway Outflow (cfs)	36.3	47.1	112.4	99	41.5	3.5	6.7	9.6	12.1	29.4	84.8	90.1	91.6	NA	122.6	12.9	
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	95	54	54	4	0	0	0	0	0	0	0	93	226	NA	27	0	
FBH/Storm Initial Water Surface Elevation (ft)	5366.52	5366.52	5375	5375	5375	5366.5	5366.5	5366.5	5366.5	5366.5	5366.5	5366.5	5366.5	NA	5377.02	5366.5	
FBH/Storm Max Water Surface Elevation (ft)	5372.81	5375.8	5377.32	5376.72	5375.79	5367.81	5369.04	5370.88	5373.21	5375.54	5376.52	5377.54	5378.11	NA	5372.69	5374.07	
Height of Water Above Auxillary Spillway (ft)	0.96	0.67	0.72	0.12	-0.81	-8.79	-7.56	-5.72	-3.39	-1.06	-0.08	0.94	1.51	NA	-3.91	-2.53	
Final Dam Crest (ft)	5374.85	5378.13	5379.6	5379.6	5379.6	5379.6	5379.6	5379.6	5379.6	5379.6	5379.6	5379.6	5379.6	NA	5379.6	5379.6	

Site	2 Above Grade																
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition	
Reservoir Bottom Elevation (ft)	5305	5305	5305	5305	5305	5305	5305	5305	5305	5305	5305	5305	5305	NA	5305	5305	
Original Dam Crest (ft)	5320	5320	5320	5320	5320	5320	5320	5320	5320	5320	5320	5320	5320	NA	5320	5320	
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5309	5309	5309	5309	5309	5309	5309	5309	5309	5309	5309	5309	5309	NA	5309	5309	
Principal Spillway Elevation Weir (ft)	5310.31	5310.95	5316	5316	5316	5316	5316	5316	5316	5316	5316	5316	5316	NA	5316	5316	
Auxillary Spillway Elevation (ft)	5310.32	5310.96	5317	5317	5317	5317	5317	5317	5317	5317	5317	5317	5317	NA	5317	5317	
Volume at Principal Spillway (acre-ft)	*	*	1.5	1.5	1.5	1.5	1.5	1.5	1.5	1.5	1.5	1.5	1.5	NA	1.5	1.5	
Volume at Auxillary Spillway (acre-ft)	*	*	1.774	1.774	1.774	1.774	1.774	1.774	1.774	1.774	1.774	1.774	1.774	NA	1.774	1.774	
Volume at Low Stage Orifice Crest (acre-ft)	0.26	0.26	0.26	0.26	0.26	0.26	0.26	0.26	0.26	0.26	0.26	0.26	0.26	NA	0.26	0.26	
Principal Spillway Weir Length (ft)	12	12	12	12	12	12	12	12	12	12	12	12	12	NA	12	12	
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50	
Principal Spillway Outlet Pipe Diameter (in)	30	30	30	30	30	30	30	30	30	30	30	30	30	NA	30	30	
Scaling Factor	1.0313	1.0313	1.0313	1.0313	1.0313	1.0313	1.0313	1.0313	1.0313	1.0313	1.0313	1.0313	1.0313	NA	1.0313	1.0313	
PSH Peak Inflow (cfs)	5.65	7.58	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Peak Outflow (cfs)	5.12	6.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Max Water Surface Elevation (ft)	5310.31	5310.95	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
FBH/Storm Peak Inflow (cfs)	76.5	76.5	76.5	55.1	19.8	0.6	3.8	8.6	18.2	27.9	40.3	55.2	80.4	NA	60.7	19	
FBH/Storm Peak Outflow (cfs)	76.3	76	76.4	55.1	19.7	0.5	2.1	4.3	7.9	10	11.9	28.6	70.3	NA	20.1	7.5	
FBH/Storm Peak Principal Spillway Outflow (cfs)	15.3	16	59.4	52.1	19.7	0.5	2.1	4.3	7.9	10	11.9	28.6	57.3	NA	20.1	7.5	
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	61	60	17	3	0	0	0	0	0	0	0	0	13	NA	0	0	
FBH/Storm Initial Water Surface Elevation (ft)	5309.02	5309.02	5316	5316	5316	5309	5309	5309	5309	5309	5309	5309	5309	NA	5309	5309	
FBH/Storm Max Water Surface Elevation (ft)	5310.72	5311.34	5317.15	5317.03	5316.32	5309.19	5309.74	5310.57	5312.08	5313.63	5315.48	5316.55	5317.11	NA	5316.34	5311.75	
Height of Water Above Auxillary Spillway (ft)	0.4	0.38	0.15	0.03	-0.68	-7.81	-7.26	-6.43	-4.92	-3.37	-1.52	-0.45	0.11	NA	-0.66	-5.25	
Final Dam Crest (ft)	5313.32	5313.96	5320	5320	5320	5320	5320	5320	5320	5320	5320	5320	5320	NA	5320	5320	
Site	2 Below Grade																
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition	
Reservoir Bottom Elevation (ft)	5269.32	5269.32	5269.32	5269.32	5269.32	5269.32	5269.32	5269.32	5269.32	5269.32	5269.32	5269.32	5269.32	NA	5269.32	5269.32	
Original Dam Crest (ft)	5284	5284	5284	5284	5284	5284	5284	5284	5284	5284	5284	5284	5284	NA	5284	5284	
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5273	5273	5273	5273	5273	5273	5273	5273	5273	5273	5273	5273	5273	NA	5273	5273	
Principal Spillway Elevation Weir (ft)	5273.29	5274.99	5280	5280	5280	5280	5280	5280	5280	5280	5280	5280	5280	NA	5280	5280	
Auxillary Spillway Elevation (ft)	5273.3	5275	5281	5281	5281	5281	5281	5281	5281	5281	5281	5281	5281	NA	5281	5281	
Volume at Principal Spillway (acre-ft)	*	*	1.385	1.385	1.385	1.385	1.385	1.385	1.385	1.385	1.385	1.385	1.385	NA	1.385	1.385	
Volume at Auxillary Spillway (acre-ft)	*	*	1.62	1.62	1.62	1.62	1.62	1.62	1.62	1.62	1.62	1.62	1.62	NA	1.62	1.62	
Volume at Low Stage Orifice Crest (acre-ft)	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28	NA	0.28	0.28	
Principal Spillway Weir Length (ft)	12	12	12	12	12	12	12	12	12	12	12	12	12	NA	12	12	
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50	
Principal Spillway Outlet Pipe Diameter (in)	30	30	30	30	30	30	30	30	30	30	30	30	30	NA	30	30	
Scaling Factor	0.716	0.716	0.716	0.716	0.716	0.716	0.716	0.716	0.716	0.716	0.716	0.716	0.716	NA	0.716	0.716	
PSH Peak Inflow (cfs)	2.93	5.7	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Peak Outflow (cfs)	2.87	5.18	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Max Water Surface Elevation (ft)	5273.29	5274.34	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
FBH/Storm Peak Inflow (cfs)	26.4	26.4	26.4	11	4.3	0.6	3.8	8.6	18.2	27.9	40.3	55.2	80.4	NA	60.7	19	
FBH/Storm Peak Outflow (cfs)	26	26.2	18.8	12.5	12.5	0.5	2.1	4.5	8.3	10.3	12.4	32.2	70.2	NA	32.5	7.7	
FBH/Storm Peak Principal Spillway Outflow (cfs)	8	10.2	18.8	12.5	12.5	0.5	2.1	4.5	8.3	10.3	12.4	32.2	62.2	NA	32.5	7.7	
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	18	16	0	0	0	0	0	0	0	0	0	0	8	NA	0	0	
FBH/Storm Initial Water Surface Elevation (ft)	5273.02	5273.02	5280	5280	5280	5273	5273	5273	5273	5273	5273	5273	5273	NA	5273	5273	
FBH/Storm Max Water Surface Elevation (ft)	5273.84	5275.25	5280.28	5280	5280	5273.19	5273.75	5274.61	5276.35	5277.90	5279.90	5280.64	5281.20	NA	5280.64	5275.87	
Height of Water Above Auxillary Spillway (ft)	0.54	0.25	-0.72	-1	-1	-7.81	-7.25	-6.39	-4.65	-3.1	-1.1	-0.36	0.2	NA	-0.36	-5.13	
Final Dam Crest (ft)	5276.3	5278	5284	5284	5284	5284	5284	5284	5284	5284	5284	5284	5284	NA	5284	5284	

Site	3 Above Grade																
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition	
Reservoir Bottom Elevation (ft)	5255	5255	5255	5255	5255	5255	5255	5255	5255	5255	5255	5255	5255	NA	5255	5255	
Original Dam Crest (ft)	5270	5270	5270	5270	5270	5270	5270	5270	5270	5270	5270	5270	5270	NA	5270	5270	
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5259	5259	5259	5259	5259	5259	5259	5259	5259	5259	5259	5259	5259	NA	5259	5259	
Principal Spillway Elevation Weir (ft)	5260.23	5260.5	5266	5266	5266	5266	5266	5266	5266	5266	5266	5266	5266	NA	5266	5266	
Auxillary Spillway Elevation (ft)	5260.24	5260.51	5267	5267	5267	5267	5267	5267	5267	5267	5267	5267	5267	NA	5267	5267	
Volume at Principal Spillway (acre-ft)	*	*	1.1	1.1	1.1	1.1	1.1	1.1	1.1	1.1	1.1	1.1	1.1	NA	1.1	1.1	
Volume at Auxillary Spillway (acre-ft)	*	*	1.31	1.31	1.31	1.31	1.31	1.31	1.31	1.31	1.31	1.31	1.31	NA	1.31	1.31	
Volume at Low Stage Orifice Crest (acre-ft)	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	NA	0.19	0.19	
Principal Spillway Weir Length (ft)	12	12	12	12	12	12	12	12	12	12	12	12	12	NA	12	12	
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50	
Principal Spillway Outlet Pipe Diameter (in)	30	30	30	30	30	30	30	30	30	30	30	30	30	NA	30	30	
Scaling Factor	0.859	0.859	0.859	0.859	0.859	0.859	0.859	0.859	0.859	0.859	0.859	0.859	0.859	NA	0.859	0.859	
PSH Peak Inflow (cfs)	5.07	5.85	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Peak Outflow (cfs)	4.79	5.39	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Max Water Surface Elevation (ft)	5260.23	5260.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
FBH/Storm Peak Inflow (cfs)	65.5	65.5	65.5	44.6	15.7	0.8	4.2	8.7	17.1	25.7	36.4	49.4	71.1	NA	51.8	21	
FBH/Storm Peak Outflow (cfs)	65.8	0	64.4	44.4	15.6	0.6	2.5	4.9	8.2	10.4	12.2	32.2	68.8	NA	24.7	8.9	
FBH/Storm Peak Principal Spillway Outflow (cfs)	23.8	0	59.4	44.4	15.6	0.6	2.5	4.9	8.2	10.4	12.2	32.2	61.8	NA	24.7	8.9	
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	42	0	5	0	0	0	0	0	0	0	0	0	7	NA	0	0	
FBH/Storm Initial Water Surface Elevation (ft)	5259.02	5259.02	5266	5266	5266	5259	5259	5259	5259	5259	5259	5259	5259	NA	5259	5259	
FBH/Storm Max Water Surface Elevation (ft)	5260.84	0	5267.15	5266.88	5266.14	5259.21	5259.92	5260.79	5262.34	5263.95	5265.74	5266.64	5267.19	NA	5266.45	5262.83	
Height of Water Above Auxillary Spillway (ft)	0.6	-5260.51	0.15	-0.12	-0.86	-7.79	-7.08	-6.21	-4.66	-3.05	-1.26	-0.36	0.19	NA	-0.55	-4.17	
Final Dam Crest (ft)	5263.24	5263.51	5270	5270	5270	5270	5270	5270	5270	5270	5270	5270	5270	NA	5270	5270	
Site	3 Below Grade																
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition	
Reservoir Bottom Elevation (ft)	5225	5225	5225	5225	5225	5225	5225	5225	5225	5225	5225	5225	5225	NA	5225	5225	
Original Dam Crest (ft)	5240	5240	5240	5240	5240	5240	5240	5240	5240	5240	5240	5240	5240	NA	5240	5240	
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5229	5229	5229	5229	5229	5229	5229	5229	5229	5229	5229	5229	5229	NA	5229	5229	
Principal Spillway Elevation Weir (ft)	5229.55	5230.52	5237	5237	5237	5237	5237	5237	5237	5237	5237	5237	5237	NA	5237	5237	
Auxillary Spillway Elevation (ft)	5229.56	5230.53	5238	5238	5238	5238	5238	5238	5238	5238	5238	5238	5238	NA	5238	5238	
Volume at Principal Spillway (acre-ft)	*	*	1.1	1.1	1.1	1.1	1.1	1.1	1.1	1.1	1.1	1.1	1.1	NA	1.1	1.1	
Volume at Auxillary Spillway (acre-ft)	*	*	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25	NA	1.25	1.25	
Volume at Low Stage Orifice Crest (acre-ft)	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	NA	0.23	0.23	
Principal Spillway Weir Length (ft)	12	12	12	12	12	12	12	12	12	12	12	12	12	NA	12	12	
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50	
Principal Spillway Outlet Pipe Diameter (in)	30	30	30	30	30	30	30	30	30	30	30	30	30	NA	30	30	
Scaling Factor	0.2404	0.2404	0.2404	0.2404	0.2404	0.2404	0.2404	0.2404	0.2404	0.2404	0.2404	0.2404	0.2404	NA	0.2404	0.2404	
PSH Peak Inflow (cfs)	2.7	4.38	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Peak Outflow (cfs)	2.7	4.34	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Max Water Surface Elevation (ft)	5229.55	5230.01	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
FBH/Storm Peak Inflow (cfs)	23.1	23.1	23.1	6.2	3.5	0.8	4.2	8.7	17.1	25.7	36.4	49.4	71.1	NA	51.8	21	
FBH/Storm Peak Outflow (cfs)	23.1	0	13.3	13.3	13.3	0.5	2.4	2.4	9.1	11.6	21.8	46.5	80.8	NA	26.8	9.3	
FBH/Storm Peak Principal Spillway Outflow (cfs)	7.1	0	13.3	13.3	13.3	0.5	2.4	2.4	9.1	11.6	21.8	46.5	69.8	NA	26.8	9.3	
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	16	0	0	0	0	0	0	0	0	0	0	0	11	NA	0	0	
FBH/Storm Initial Water Surface Elevation (ft)	5229.02	5229.02	5237	5237	5237	5229	5229	5229	5229	5229	5229	5229	5229	NA	5229	5229	
FBH/Storm Max Water Surface Elevation (ft)	5229.77	5229.02	5237	5232.05	5237	5229.19	5229.89	5229.89	5232.98	5235.19	5237.36	5237.90	5238.30	NA	5237.48	5233.17	
Height of Water Above Auxillary Spillway (ft)	0.21	-1.51	-1	-5.95	-1	-8.81	-8.11	-8.11	-5.02	-2.81	-0.64	-0.1	0.3	NA	-0.52	-4.83	
Final Dam Crest (ft)	5232.56	5233.53	5241	5241	5241	5241	5241	5241	5241	5241	5241	5241	5241	NA	5241	5241	

Site	3A Below Grade (combined watersheds 2 & 3)																
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition	
Reservoir Bottom Elevation (ft)	5220	5220	5220	5220	5220	5220	5220	5220	5220	5220	5220	5220	5220	NA	5220	5220	
Original Dam Crest (ft)	5235	5235	5235	5235	5235	5235	5235	5235	5235	5235	5235	5235	5235	NA	5235	5235	
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5225	5225	5225	5225	5225	5225	5225	5225	5225	5225	5225	5225	5225	NA	5225	5225	
Principal Spillway Elevation Weir (ft)	5226.19	5226.69	5233	5233	5233	5233	5233	5233	5233	5233	5233	5233	5233	NA	5233	5233	
Auxillary Spillway Elevation (ft)	5226.2	5226.7	5234	5234	5234	5234	5234	5234	5234	5234	5234	5234	5234	NA	5234	5234	
Volume at Principal Spillway (acre-ft)	*	*	2.6	2.6	2.6	2.6	2.6	2.6	2.6	2.6	2.6	2.6	2.6	NA	2.6	2.6	
Volume at Auxillary Spillway (acre-ft)	*	*	2.98	2.98	2.98	2.98	2.98	2.98	2.98	2.98	2.98	2.98	2.98	NA	2.98	2.98	
Volume at Low Stage Orifice Crest (acre-ft)	0.55	0.55	0.55	0.55	0.55	0.55	0.55	0.55	0.55	0.55	0.55	0.55	0.55	NA	0.55	0.55	
Principal Spillway Weir Length (ft)	12	12	12	12	12	12	12	12	12	12	12	12	12	NA	12	12	
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50	
Principal Spillway Outlet Pipe Diameter (in)	30	30	30	30	30	30	30	30	30	30	30	30	30	NA	30	30	
Scaling Factor	0.8802	0.8802	0.8802	0.8802	0.8802	0.8802	0.8802	0.8802	0.8802	0.8802	0.8802	0.8802	0.8802	NA	0.8802	0.8802	
PSH Peak Inflow (cfs)	5.64	7.57	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Peak Outflow (cfs)	4.86	5.92	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Max Water Surface Elevation (ft)	5226.19	5226.69	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
FBH/Storm Peak Inflow (cfs)	72.4	72.4	49.4	20.2	7.8	1.4	7.4	17.3	35.3	52.3	75.4	104.6	151.5	NA	112.4	39	
FBH/Storm Peak Outflow (cfs)	72.2	72.6	16.3	13.4	13.4	1	3.2	6.5	9.9	12.2	27.7	67.4	144.5	NA	53.3	9.9	
FBH/Storm Peak Principal Spillway Outflow (cfs)	25.2	25.6	16.3	13.4	13.4	1	3.2	6.5	9.9	12.2	27.7	61.4	94.5	NA	52.3	9.9	
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	47	47	0	0	0	0	0	0	0	0	0	6	50	NA	1	0	
FBH/Storm Initial Water Surface Elevation (ft)	5225.05	5225.02	5233	5233	5233	5225	5225	5225	5225	5225	5225	5225	5225	NA	5225	5225	
FBH/Storm Max Water Surface Elevation (ft)	5226.83	5227.33	5233.13	5233	5233	5225.29	5226.24	5227.42	5229.68	5231.78	5233.51	5234.17	5234.69	NA	5234.02	5229.62	
Height of Water Above Auxillary Spillway (ft)	0.63	0.63	-0.87	-1	-1	-8.71	-7.76	-6.58	-4.32	-2.22	-0.49	0.17	0.69	NA	0.02	-4.38	
Final Dam Crest (ft)	5229.2	5229.7	5237	5237	5237	5237	5237	5237	5237	5237	5237	5237	5237	NA	5237	5237	
Site	4E Above Grade (Watershed 4 only) NOTICE: different auxillary crest elevation from 4E Multi-Basin																
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition	
Reservoir Bottom Elevation (ft)	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	NA	5040	5040	
Original Dam Crest (ft)	5055	5055	5055	5055	5055	5055	5055	5055	5055	5055	5055	5055	5055	NA	5055	5055	
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5043	5043	5043	5043	5043	5043	5043	5043	5043	5043	5043	5043	5043	NA	5043	5043	
Principal Spillway Elevation Weir (ft)	5051.59	5052.25	5052	5052	5052	5052	5052	5052	5052	5052	5052	5052	5052	NA	5052	5052	
Auxillary Spillway Elevation (ft)	5051.6	5052.26	5053	5053	5053	5053	5053	5053	5053	5053	5053	5053	5053	NA	5053	5053	
Volume at Principal Spillway (acre-ft)	*	*	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	NA	17.09	17.09	
Volume at Auxillary Spillway (acre-ft)	*	*	18.99	18.99	18.99	18.99	18.99	18.99	18.99	18.99	18.99	18.99	18.99	NA	18.99	18.99	
Volume at Low Stage Orifice Crest (acre-ft)	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	NA	3.34	3.34	
Principal Spillway Weir Length (ft)	20	20	20	20	20	20	20	20	20	20	20	20	20	NA	20	20	
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50	
Principal Spillway Outlet Pipe Diameter (in)	42	42	42	42	42	42	42	42	42	42	42	42	42	NA	42	42	
Scaling Factor	1	1	1	1	1	1	1	1	1	1	1	1	1	NA	1	1	
PSH Peak Inflow (cfs)	61.27	73.83	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Peak Outflow (cfs)	14.2	28.5	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Max Water Surface Elevation (ft)	5051.59	5052.25	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
FBH/Storm Peak Inflow (cfs)	582.7	582.7	582.7	544.7	199.4	8.8	35.9	71.2	139.1	207.8	291.6	395.8	563.8	NA	442.5	157	
FBH/Storm Peak Outflow (cfs)	523.7	507.3	558.3	541.1	199.3	3.3	6.7	9.5	12.3	30.7	71.8	236.7	452.7	NA	217.2	13	
FBH/Storm Peak Principal Spillway Outflow (cfs)	179.7	200.3	230.3	230.1	148.3	3.3	6.7	9.5	12.3	30.7	71.8	166.7	228.7	NA	157.2	13	
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	344	307	328	311	51	0	0	0	0	0	0	70	224	NA	60	0	
FBH/Storm Initial Water Surface Elevation (ft)	5043.02	5043.02	5052	5052	5052	5043	5043	5043	5043	5043	5043	5043	5043	NA	5043	5043	
FBH/Storm Max Water Surface Elevation (ft)	5053.51	5054.07	5054.9	5054.85	5053.66	5044.26	5045.59	5047.30	5049.86	5052.40	5052.94	5053.81	5054.54	NA	5053.73	5050.7	
Height of Water Above Auxillary Spillway (ft)	1.91	1.81	1.9	1.85	0.66	-8.74	-7.41	-5.7	-3.14	-0.6	-0.06	0.81	1.54	NA	0.73	-2.3	
Final Dam Crest (ft)	5054.6	5055.26	5056	5056	5056	5056	5056	5056	5056	5056	5056	5056	5056	NA	5056	5056	

Site	Basin 4E Above Grade Multi-Basin (includes Watershed 4 and inputs from Basin 1below, 2below, and 3 below)															
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition
Reservoir Bottom Elevation (ft)	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	NA	5040	5040
Original Dam Crest (ft)	5055	5055	5055	5055	5055	5055	5055	5055	5055	5055	5055	5055	5055	NA	5055	5055
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5043	5043	5043	5043	5043	5043	5043	5043	5043	5043	5043	5043	5043	NA	5043	5043
Principal Spillway Elevation Weir (ft)	5052.74	5053.12	5052	5052	5052	5052	5052	5052	5052	5052	5052	5052	5052	NA	5052	5052
Auxillary Spillway Elevation (ft)	5052.75	5053.13	5054	5054	5054	5054	5054	5054	5054	5054	5054	5054	5054	NA	5054	5054
Volume at Principal Spillway (acre-ft)	*	*	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	NA	17.09	17.09
Volume at Auxillary Spillway (acre-ft)	*	*	20.97	20.97	20.97	20.97	20.97	20.97	20.97	20.97	20.97	20.97	20.97	NA	20.97	20.97
Volume at Low Stage Orifice Crest (acre-ft)	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	NA	3.34	3.34
Principal Spillway Weir Length (ft)	20	20	20	20	20	20	20	20	20	20	20	20	20	NA	20	20
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50
Principal Spillway Outlet Pipe Diameter (in)	42	42	42	42	42	42	42	42	42	42	42	42	42	NA	42	42
Scaling Factor	1	1	1	1	1	1	1	1	1	1	1	1	1	NA	1	1
PSH Peak Inflow (cfs)	73.49	97.24	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Peak Outflow (cfs)	55.11	92.28	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Max Water Surface Elevation (ft)	5052.74	5053.12	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
FBH/Storm Peak Inflow (cfs)	609.4	609.6	754.2	654.3	247.8	11.9	41.8	82.6	162.7	217.3	326.4	493.5	889.1	NA	504.8	183
FBH/Storm Peak Outflow (cfs)	520.6	504.1	729.9	649	246	6	10	13	27.9	84.2	189.5	438.9	825	NA	338.2	34.2
FBH/Storm Peak Principal Spillway Outflow (cfs)	228.6	230.1	236.9	236	228	6	10	13	27.9	84.2	189.5	232.9	238	NA	230.9	34.2
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	292	274	493	413	18	0	0	0	0	0	0	206	587	NA	107.3	0
FBH/Storm Initial Water Surface Elevation (ft)	5043.02	5043.02	5052	5052	5052	5043	5043	5043	5043	5043	5043	5043	5043	NA	5043	5043
FBH/Storm Max Water Surface Elevation (ft)	5054.52	5054.85	5056.35	5056.14	5054.39	5045.34	5047.75	5050.67	5052.27	5053.05	5053.99	5054.46	5056.59	NA	5055.03	5052.39
Height of Water Above Auxillary Spillway (ft)	1.77	1.72	2.35	2.14	0.39	-8.66	-6.25	-3.33	-1.73	-0.95	-0.01	-4548.54	2.59	NA	1.03	-1.61
Final Dam Crest (ft)	5055.75	5056.13	5057	5057	5057	5057	5057	5057	5057	5057	5057	5057	5057	NA	5057	5057
Site	4D Below Grade (Watershed 4 inputs)															
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition
Reservoir Bottom Elevation (ft)	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	NA	5025	5025
Original Dam Crest (ft)	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	NA	5040	5040
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5029	5029	5029	5029	5029	5029	5029	5029	5029	5029	5029	5029	5029	NA	5029	5029
Principal Spillway Elevation Weir (ft)	5033.61	5037.39	5037	5037	5037	5037	5037	5037	5037	5037	5037	5037	5037	NA	5037	5037
Auxillary Spillway Elevation (ft)	5033.62	5037.4	5038.5	5038.5	5038.5	5038.5	5038.5	5038.5	5038.5	5038.5	5038.5	5038.5	5038.5	NA	5038.5	5038.5
Volume at Principal Spillway (acre-ft)	*	*	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	NA	17.09	17.09
Volume at Auxillary Spillway (acre-ft)	*	*	19.98	19.98	19.98	19.98	19.98	19.98	19.98	19.98	19.98	19.98	19.98	NA	19.98	19.98
Volume at Low Stage Orifice Crest (acre-ft)	4.59	4.59	4.59	4.59	4.59	4.59	4.59	4.59	4.59	4.59	4.59	4.59	4.59	NA	4.59	4.59
Principal Spillway Weir Length (ft)	20	20	20	20	20	20	20	20	20	20	20	20	20	NA	20	20
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50
Principal Spillway Outlet Pipe Diameter (in)	42	42	42	30	42	42	42	42	42	42	42	42	42	NA	30	42
Scaling Factor	1	1	1	1	1	1	1	1	1	1	1	1	1	NA	1	1
PSH Peak Inflow (cfs)	33.37	55.39	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Peak Outflow (cfs)	10.24	12.72	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Max Water Surface Elevation (ft)	5033.61	5036.09	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
FBH/Storm Peak Inflow (cfs)	215.6	215.6	215.6	111.6	44.5	8.8	35.9	71.2	139.1	207.8	291.6	395.8	563.8	NA	442.5	157
FBH/Storm Peak Outflow (cfs)	160.9	102.6	185.2	107.6	43.9	3.3	6.7	9.3	12	42.6	115.4	244	450.5	NA	202.5	12.8
FBH/Storm Peak Principal Spillway Outflow (cfs)	65.9	65.6	171.2	107.6	43.9	3.3	6.7	9.3	12	42.6	115.4	115	252.5	NA	115.5	12.8
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	95	37	14	0	0	0	0	0	0	0	0	129	198	NA	87	0
FBH/Storm Initial Water Surface Elevation (ft)	5029.02	5029.02	5037	5037	5029	5029	5029	5029	5029	5029	5029	5029	5029	NA	5029	5029
FBH/Storm Max Water Surface Elevation (ft)	6034.54	5037.88	5038.85	5038.31	5037.6	5030.20	5031.47	5033.14	5035.61	5037.59	5038.36	5039.14	5039.93	NA	5039.42	5036.43
Height of Water Above Auxillary Spillway (ft)	1000.92	0.48	0.35	-0.19	-0.9	-8.3	-7.03	-5.36	-2.89	-0.91	-0.14	0.64	1.43	NA	0.92	-2.07
Final Dam Crest (ft)	5036.62	5040.4	5041.5	5041.5	5041.5	5041.5	5041.5	5041.5	5041.5	5041.5	5041.5	5041.5	5041.5	NA	5041.5	5041.5

Site	Basin 4D Below Grade Multi-Basin (includes Watershed 4 and inputs from Basin 1below, 2below, and 3 below)															
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition
Reservoir Bottom Elevation (ft)	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	NA	5025	5025
Original Dam Crest (ft)	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	NA	5040	5040
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5029	5029	5029	5029	5029	5029	5029	5029	5029	5029	5029	5029	5029	NA	5029	5029
Principal Spillway Elevation Weir (ft)	5037.2	5038.13	5037	5037	5037	5037	5037	5037	5037	5037	5037	5037	5037	NA	5037	5037
Auxillary Spillway Elevation (ft)	5037.21	5038.14	5039	5039	5039	5039	5039	5039	5039	5039	5039	5039	5039	NA	5039	5039
Volume at Principal Spillway (acre-ft)	*	*	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	17.09	NA	17.09	17.09
Volume at Auxillary Spillway (acre-ft)	*	*	20.96	20.96	20.96	20.96	20.96	20.96	20.96	20.96	20.96	20.96	20.96	NA	20.96	20.96
Volume at Low Stage Orifice Crest (acre-ft)	4.59	4.59	4.59	4.59	4.59	4.59	4.59	4.59	4.59	4.59	4.59	4.59	4.59	NA	4.59	4.59
Principal Spillway Weir Length (ft)	20	20	20	20	20	20	20	20	20	20	20	20	20	NA	20	20
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50
Principal Spillway Outlet Pipe Diameter (in)	42	42	42	42	42	42	42	42	42	42	42	42	42	NA	30	42
Scaling Factor	1	1	1	1	1	1	1	1	1	1	1	1	1	NA	1	1
PSH Peak Inflow (cfs)	48.52	97.23	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Peak Outflow (cfs)	25.41	92.41	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Max Water Surface Elevation (ft)	5037.2	5038.13	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
FBH/Storm Peak Inflow (cfs)	244	244	379.5	226.9	93.1	9.8	42.8	149.1	162.8	238.6	335.1	486.3	875	NA	504.8	182.9
FBH/Storm Peak Outflow (cfs)	193.6	192.4	350.7	215.6	91.9	6.1	10.1	23	32.3	91.3	183.2	374.2	820.2	NA	349.7	38.4
FBH/Storm Peak Principal Spillway Outflow (cfs)	91.6	153.4	252.7	116.6	91.9	6.1	10.1	23	32.3	91.3	183.2	253.2	259.2	NA	232	38.4
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	102	39	98	99	0	0	0	0	0	0	0	121	561	NA	117.7	0
FBH/Storm Initial Water Surface Elevation (ft)	5029.02	5029.02	5037	5037	5029	5029	5029	5029	5029	5029	5029	5029	5029	NA	5029	5029
FBH/Storm Max Water Surface Elevation (ft)	5038.16	5038.71	5039.98	5039.98	5038.14	5031.24	5033.76	5037.19	5037.37	5038.14	5038.94	5040.10	5041.53	NA	5040.52	5037.49
Height of Water Above Auxillary Spillway (ft)	0.95	0.57	0.98	0.98	-0.86	-7.76	-5.24	-1.81	-1.63	-0.86	-0.06	1.1	2.53	NA	1.52	-1.51
Final Dam Crest (ft)	5040.21	5041.14	5042	5042	5042	5042	5042	5042	5042	5042	5042	5042	5042	NA	5042	5042
Site	Basin 4A-4B Above Grade Multi-Basin (includes Watershed 4 and inputs from Basin 1below, 2below, and 3 below)															
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition
Reservoir Bottom Elevation (ft)	5015.58	5015.58	5015.58	5015.58	5015.58	5015.58	5015.58	5015.58	5015.58	5015.58	5015.58	5015.58	5015.58	NA	5015.58	5015.58
Original Dam Crest (ft)	5030	5030	5030	5030	5030	5030	5030	5030	5030	5030	5030	5030	5030	NA	5030	5030
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5019	5019	5019	5019	5019	5019	5019	5019	5019	5019	5019	5019	5019	NA	5019	5019
Principal Spillway Elevation Weir (ft)	*	*	5027	5027	5027	5027	5027	5027	5027	5027	5027	5027	5027	NA	5027	5027
Auxillary Spillway Elevation (ft)	*	*	5029.6	5029.6	5029.6	5029.6	5029.6	5029.6	5029.6	5029.6	5029.6	5029.6	5029.6	NA	5029.6	5029.6
Volume at Principal Spillway (acre-ft)	*	*	15.353	15.353	15.353	15.353	15.353	15.353	15.353	15.353	15.353	15.353	15.353	NA	15.353	15.353
Volume at Auxillary Spillway (acre-ft)	*	*	20.2	20.2	20.2	20.2	20.2	20.2	20.2	20.2	20.2	20.2	20.2	NA	20.2	20.2
Volume at Low Stage Orifice Crest (acre-ft)	3.55	3.55	3.55	3.55	3.55	3.55	3.55	3.55	3.55	3.55	3.55	3.55	3.55	NA	3.55	3.55
Principal Spillway Weir Length (ft)	16	16	16	16	16	16	16	16	16	16	16	16	16	NA	16	16
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50
Principal Spillway Outlet Pipe Diameter (in)	42	42	42	42	42	42	42	42	42	42	42	42	42	NA	42	42
Scaling Factor	1.447	1.447	1.447	1.447	1.447	1.447	1.447	1.447	1.447	1.447	1.447	1.447	1.447	NA	1.447	1.447
PSH Peak Inflow (cfs)	*	*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Peak Outflow (cfs)	*	*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Max Water Surface Elevation (ft)	*	*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
FBH/Storm Peak Inflow (cfs)	*	*	719.6	*	*	*	*	*	*	*	335.35	*	*	NA	504.7	*
FBH/Storm Peak Outflow (cfs)	*	*	719.1	*	*	*	*	*	*	*	214.5	*	*	NA	345.6	*
FBH/Storm Peak Principal Spillway Outflow (cfs)	*	*	303.1	*	*	*	*	*	*	*	214.5	*	*	NA	292.9	*
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	*	*	416	*	*	*	*	*	*	*	0	*	*	NA	52.7	*
FBH/Storm Initial Water Surface Elevation (ft)	*	*	5027	5027	5027	5019	5019	5019	5019	5019	5019	5019	5019	NA	5019	5019
FBH/Storm Max Water Surface Elevation (ft)	*	*	5031.57	*	*	*	*	*	*	*	5029.52	*	*	NA	5030.31	*
Height of Water Above Auxillary Spillway (ft)	*	*	1.97	*	*	*	*	*	*	*	-0.08	*	*	NA	0.71	*
Final Dam Crest (ft)	*	*	5032.6	5032.6	5032.6	5032.6	5032.6	5032.6	5032.6	5032.6	5032.6	5032.6	5032.6	NA	5032.6	5032.6
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition
Reservoir Bottom Elevation (ft)	4991	4991	4991	4991	4991	4991	4991	4991	4991	4991	4991	4991	4991	NA	4991	4991
Original Dam Crest (ft)	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	NA	5000	5000
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	4993	4993	4993	4993	4993	4993	4993	4993	4993	4993	4993	4993	4993	NA	4993	4993
Principal Spillway Elevation Weir (ft)	4997.97	4998.21	4997	4997	4997	4997	4997	4997	4997	4997	4997	4997	4997	NA	4997	4997

4A	Auxillary Spillway Elevation (ft)	4997.98	4998.22	4999.2	4999.2	4999.2	4999.2	4999.2	4999.2	4999.2	4999.2	4999.2	4999.2	4999.2	NA	4999.2	4999.2
	Volume at Principal Spillway (acre-ft)	*	*	1.747	1.747	1.747	1.747	1.747	1.747	1.747	1.747	1.747	1.747	1.747	NA	1.747	1.747
	Volume at Auxilliary Spillway (acre-ft)	*	*	2.7	2.7	2.7	2.7	2.7	2.7	2.7	2.7	2.7	2.7	2.7	NA	2.7	2.7
	Volume at Low Stage Orifice Crest (acre-ft)	0.44	0.44	0.44	0.44	0.44	0.44	0.44	0.44	0.44	0.44	0.44	0.44	0.44	NA	0.44	0.44
	Principal Spillway Weir Length (ft)	20	20	20	20	20	20	20	20	20	20	20	20	20	NA	20	20
	Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50
	Principal Spillway Outlet Pipe Diameter (in)	48	48	48	48	48	48	48	48	48	48	48	48	48	NA	48	48
	Scaling Factor	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	1.2	NA	1.2	1.2
	PSH Peak Inflow (cfs)	66	88.77	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	PSH Peak Outflow (cfs)	65.66	88.39	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	PSH Max Water Surface Elevation (ft)	4997.97	4998.21	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	FBH/Storm Peak Inflow (cfs)	486.8	520.4	719.2	647.6	246.9	6.1	9.9	25	47.9	97	214.5	440.2	810.7	NA	346.6	41.1
	FBH/Storm Peak Outflow (cfs)	485.9	518.5	717.9	647.1	246.7	5.9	9.9	24.9	47.6	95.2	213.8	439.2	805.8	NA	345.4	40.9
	FBH/Storm Peak Principal Spillway Outflow (cfs)	243.9	252.5	258.9	258.1	240.7	5.9	9.9	24.9	47.6	95.2	213.8	255.2	259.8	NA	253.4	40.9
	FBH/Storm Peak Auxillary Spillway Outflow (cfs)	242	266	459	389	6	0	0	0	0	0	0	184	546	NA	92	0
	FBH/Storm Initial Water Surface Elevation (ft)	4993.02	4993.02	4997	4997	4997	4993	4993	4993	4993	4993	4993	4993	4993	NA	4993	4993
	FBH/Storm Max Water Surface Elevation (ft)	4999.58	4999.93	5001.46	5001.27	4999.39	4994.82	4997.01	4997.29	4997.71	4998.22	4999.2	5000.57	5001.7	NA	5000.15	4997.58
Height of Water Above Auxillary Spillway (ft)	1.6	1.71	2.26	2.07	0.19	-4.38	-2.19	-1.91	-1.49	-0.98	0	1.37	2.5	NA	0.95	-1.62	
Final Dam Crest (ft)	5000.98	5001.22	5002.2	5002.2	5002.2	5002.2	5002.2	5002.2	5002.2	5002.2	5002.2	5002.2	5002.2	NA	5002.2	5002.2	

Site **Basin 4A-4B Below Grade Multi-Basin** (includes Watershed 4 and inputs from Basin 1below, 2below, and 3 below) **NOTE: 60ft wide auxilliary spillway**

4B	Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCIII 24hr 100yr	ARCIII 6hr	10yr Burn Condition	
	Reservoir Bottom Elevation (ft)	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	NA	5000	5000
	Original Dam Crest (ft)	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015	NA	5015	5015
	Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5003	5003	5003	5003	5003	5003	5003	5003	5003	5003	5003	5003	5003	5003	NA	5003	5003
	Principal Spillway Elevation Weir (ft)	*	*	5012	5012	5012	5012	5012	5012	5012	5012	5012	5012	5012	5012	NA	5012	5012
	Auxillary Spillway Elevation (ft)	*	*	5014.4	5014.4	5014.4	5014.4	5014.4	5014.4	5014.4	5014.4	5014.4	5014.4	5014.4	5014.4	NA	5014.4	5014.4
	Volume at Principal Spillway (acre-ft)	*	*	15.268	15.268	15.268	15.268	15.268	15.268	15.268	15.268	15.268	15.268	15.268	15.268	NA	15.268	15.268
	Volume at Auxilliary Spillway (acre-ft)	*	*	19.58	19.58	19.58	19.58	19.58	19.58	19.58	19.58	19.58	19.58	19.58	19.58	NA	19.58	19.58
	Volume at Low Stage Orifice Crest (acre-ft)	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	NA	2.89	2.89
	Principal Spillway Weir Length (ft)	18	18	18	18	18	18	18	18	18	18	18	18	18	18	NA	18	18
	Auxillary Spillway Width (ft)	60	60	60	60	60	60	60	60	60	60	60	60	60	60	NA	60	60
	Principal Spillway Outlet Pipe Diameter (in)	42	42	42	42	42	42	42	42	42	42	42	42	42	42	NA	42	42
	Scaling Factor	1.273	1.273	1.273	1.273	1.273	1.273	1.273	1.273	1.273	1.273	1.273	1.273	1.273	1.273	NA	1.273	1.273
	PSH Peak Inflow (cfs)	*	*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	PSH Peak Outflow (cfs)	*	*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	PSH Max Water Surface Elevation (ft)	*	*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	FBH/Storm Peak Inflow (cfs)	*	*	379.5	*	*	*	*	*	*	*	238.59	335.4	*	*	NA	*	*
FBH/Storm Peak Outflow (cfs)	*	*	348.7	*	*	*	*	*	*	*	92.9	210.9	*	*	NA	*	*	
FBH/Storm Peak Principal Spillway Outflow (cfs)	*	*	243.5	*	*	*	*	*	*	*	92.9	210.9	*	*	NA	*	*	
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	*	*	105.2	*	*	*	*	*	*	*	0	0	*	*	NA	*	*	
FBH/Storm Initial Water Surface Elevation (ft)	*	*	5003	*	*	*	*	*	*	*	5003	5003	*	*	NA	*	*	
FBH/Storm Max Water Surface Elevation (ft)	*	*	5014.89	*	*	*	*	*	*	*	5013.22	5014.30	*	*	NA	*	*	
Height of Water Above Auxillary Spillway (ft)	*	*	0.49	*	*	*	*	*	*	*	-1.18	-0.1	*	*	NA	*	*	
Final Dam Crest (ft)	*	*	5017.4	5017.4	5017.4	5017.4	5017.4	5017.4	5017.4	5017.4	5017.4	5017.4	5017.4	5017.4	NA	5017.4	5017.4	

	Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCIII 24hr 100yr	ARCIII 6hr	10yr Burn Condition	
	Reservoir Bottom Elevation (ft)	4981	4981	4981	4981	4981	4981	4981	4981	4981	4981	4981	4981	4981	4981	NA	4981	4981
	Original Dam Crest (ft)	4991	4991	4991	4991	4991	4991	4991	4991	4991	4991	4991	4991	4991	4991	NA	4991	4991
	Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	4983	4983	4983	4983	4983	4983	4983	4983	4983	4983	4983	4983	4983	4983	NA	4983	4983
	Principal Spillway Elevation Weir (ft)	4988.91	4989.24	4988	4988	4988	4988	4988	4988	4988	4988	4988	4988	4988	4988	NA	4988	4988
	Auxillary Spillway Elevation (ft)	4988.92	4989.25	4990.4	4990.4	4990.4	4990.4	4990.4	4990.4	4990.4	4990.4	4990.4	4990.4	4990.4	4990.4	NA	4990.4	4990.4
	Volume at Principal Spillway (acre-ft)	*	*	1.732	1.732	1.732	1.732	1.732	1.732	1.732	1.732	1.732	1.732	1.732	1.732	NA	1.732	1.732
	Volume at Auxilliary Spillway (acre-ft)	*	*	2.66	2.66	2.66	2.66	2.66	2.66	2.66	2.66	2.66	2.66	2.66	2.66	NA	2.66	2.66
	Volume at Low Stage Orifice Crest (acre-ft)	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	NA	0.36	0.36
	Principal Spillway Weir Length (ft)	18	18	18	18	18	18	18	18	18	18	18	18	18	18	NA	18	18
	Auxillary Spillway Width (ft)	60	60	60	60	60	60	60	60	60	60	60	60	60	60	NA	60	60

4A	Principal Spillway Outlet Pipe Diameter (in)	42	42	42	42	42	42	42	42	42	42	42	42	42	42	NA	42	42
	Scaling Factor	1	1	1	1	1	1	1	1	1	1	1	1	1	1	NA	1	1
	PSH Peak Inflow (cfs)	62.1	92.55	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	PSH Peak Outflow (cfs)	61.8	92.25	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	PSH Max Water Surface Elevation (ft)	4988.91	4989.24	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	FBH/Storm Peak Inflow (cfs)	527.3	192.8	348.7	162.8	92	6.25	10.5	13.4	32.8	92.9	211	407	790.7	NA	NA	346	39.3
	FBH/Storm Peak Outflow (cfs)	526.5	14978	348.3	161.8	91.9	6.2	10.3	13.4	32.7	92.5	208.2	404.8	790.7	NA	NA	345.8	39.2
	FBH/Storm Peak Principal Spillway Outflow (cfs)	209.5	14935	214.3	161.8	91.9	6.2	10.3	13.4	32.7	92.5	208.2	214.8	220	NA	NA	213.8	39.2
	FBH/Storm Peak Auxillary Spillway Outflow (cfs)	317	43	134	0	0	0	0	0	0	0	0	190	570.7	NA	NA	132	0
	FBH/Storm Initial Water Surface Elevation (ft)	4983.02	4983.02	4988	4988	4988	4983	4983	4983	4983	4983	4983	4983	4983	NA	NA	4983	4983
	FBH/Storm Max Water Surface Elevation (ft)	4990.61	4989.82	4991.56	4989.92	4989.26	4984.9	4987.82	4988.07	4988.45	4989.26	4990.35	4991.66	4992.72	NA	NA	4991.47	4988.57
	Height of Water Above Auxillary Spillway (ft)	1.69	0.57	1.16	-0.48	-1.14	-5.5	-2.58	-2.33	-1.95	-1.14	-0.05	1.26	2.32	NA	NA	1.07	-1.83
	Final Dam Crest (ft)	4991.92	4992.25	4993.4	4993.4	4993.4	4993.4	4993.4	4993.4	4993.4	4993.4	4993.4	4993.4	4993.4	NA	NA	4993.4	4993.4

Site **Basin 4A-4B Below Grade (watershed 4 inputs only) NOTE: 60ft wide auxilliary spillway**

4B	Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition	
	Reservoir Bottom Elevation (ft)	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	NA	5000	5000	
	Original Dam Crest (ft)	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015	NA	5015	5015	
	Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5003	5003	5003	5003	5003	5003	5003	5003	5003	5003	5003	5003	5003	NA	5003	5003	
	Principal Spillway Elevation Weir (ft)	*	*	5012	5012	5012	5012	5012	5012	5012	5012	5012	5012	5012	NA	5012	5012	
	Auxillary Spillway Elevation (ft)	*	*	5013.5	5013.5	5013.5	5013.5	5013.5	5013.5	5013.5	5013.5	5013.5	5013.5	5013.5	NA	5013.5	5013.5	
	Volume at Principal Spillway (acre-ft)	*	*	15.268	15.268	15.268	15.268	15.268	15.268	15.268	15.268	15.268	15.268	15.268	NA	15.268	15.268	
	Volume at Auxillary Spillway (acre-ft)	*	*	17.91	17.91	17.91	17.91	17.91	17.91	17.91	17.91	17.91	17.91	17.91	NA	17.91	17.91	
	Volume at Low Stage Orifice Crest (acre-ft)	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	NA	2.89	2.89	
	Principal Spillway Weir Length (ft)	18	18	18	18	18	18	18	18	18	18	18	18	18	NA	18	18	
	Auxillary Spillway Width (ft)	60	60	60	60	60	60	60	60	60	60	60	60	60	NA	60	60	
	Principal Spillway Outlet Pipe Diameter (in)	42	42	42	42	42	42	42	42	42	42	42	42	42	NA	42	42	
	Scaling Factor	1.273	1.273	1.273	1.273	1.273	1.273	1.273	1.273	1.273	1.273	1.273	1.273	1.273	NA	1.273	1.273	
	PSH Peak Inflow (cfs)	*	*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	PSH Peak Outflow (cfs)	*	*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	PSH Max Water Surface Elevation (ft)	*	*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	FBH/Storm Peak Inflow (cfs)	*	*	215.6	*	*	8.8	35.9	71.2	139.1	207.8	291.6	395.8	563.8	NA	442.5	183.3	
	FBH/Storm Peak Outflow (cfs)	*	*	190.7	*	*	*	*	*	*	*	115.7	*	*	NA	241.8	*	
FBH/Storm Peak Principal Spillway Outflow (cfs)	*	*	165	*	*	*	*	*	*	*	115.7	*	*	NA	189.9	*		
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	*	*	25.7	*	*	*	*	*	*	*	0	*	*	NA	51.9	*		
FBH/Storm Initial Water Surface Elevation (ft)	*	*	5012	5012	5012	5003	5003	5003	5003	5003	5003	5003	5003	NA	5003	5003		
FBH/Storm Max Water Surface Elevation (ft)	*	*	5013.93	*	*	*	*	*	*	*	5013.48	*	*	NA	5014.13	*		
Height of Water Above Auxillary Spillway (ft)	*	*	0.43	*	*	*	*	*	*	*	-0.02	*	*	NA	0.63	*		
Final Dam Crest (ft)	*	*	5016.5	5016.5	5016.5	5016.5	5016.5	5016.5	5016.5	5016.5	5016.5	5016.5	5016.5	NA	5016.5	5016.5		

4A	Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition
	Reservoir Bottom Elevation (ft)	4981	4981	4981	4981	4981	4981	4981	4981	4981	4981	4981	4981	4981	NA	4981	4981
	Original Dam Crest (ft)	4991	4991	4991	4991	4991	4991	4991	4991	4991	4991	4991	4991	4991	NA	4991	4991
	Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	4983	4983	4983	4983	4983	4983	4983	4983	4983	4983	4983	4983	4983	NA	4983	4983
	Principal Spillway Elevation Weir (ft)	4987.64	4988.42	4988	4988	4988	4988	4988	4988	4988	4988	4988	4988	4988	NA	4988	4988
	Auxillary Spillway Elevation (ft)	4987.65	4988.43	4989.5	4989.5	4989.5	4989.5	4989.5	4989.5	4989.5	4989.5	4989.5	4989.5	4989.5	NA	4989.5	4989.5
	Volume at Principal Spillway (acre-ft)	*	*	1.732	1.732	1.732	1.732	1.732	1.732	1.732	1.732	1.732	1.732	1.732	NA	1.732	1.732
	Volume at Auxillary Spillway (acre-ft)	*	*	2.29	2.29	2.29	2.29	2.29	2.29	2.29	2.29	2.29	2.29	2.29	NA	2.29	2.29
	Volume at Low Stage Orifice Crest (acre-ft)	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	NA	0.36	0.36
	Principal Spillway Weir Length (ft)	18	18	18	18	18	18	18	18	18	18	18	18	18	NA	18	18
	Auxillary Spillway Width (ft)	60	60	60	60	60	60	60	60	60	60	60	60	60	NA	60	60
	Principal Spillway Outlet Pipe Diameter (in)	42	42	42	42	42	42	42	42	42	42	42	42	42	NA	42	42
	Scaling Factor	1	1	1	1	1	1	1	1	1	1	1	1	1	NA	1	1
	PSH Peak Inflow (cfs)	10.65	31.89	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Peak Outflow (cfs)	10.16	31.74	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Max Water Surface Elevation (ft)	4987.64	4988.42	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
FBH/Storm Peak Inflow (cfs)	96.1	57.7	162.6	107.5	43.8	3.4	7.1	9.9	12.7	40	115.7	253.6	470.5	NA	241.8	13.7	

FBH/Storm Peak Outflow (cfs)	96.2	95.7	189.6	107.5	43.8	6.4	6.8	9.3	12.7	42.3	115.2	253.6	470.5	NA	241.4	13.6
FBH/Storm Peak Principal Spillway Outflow (cfs)	36.2	57.7	162.6	107.5	43.8	6.4	6.8	9.3	12.7	42.3	115.2	192.6	211.5	NA	187.4	13.6
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	60	38	27	0	0	0	0	0	0	0	0	61	259	NA	54	0
FBH/Storm Initial Water Surface Elevation (ft)	4983.02	4983.02	4988	4988	4988	4983	4983	4983	4983	4983	4983	4983	4983	NA	4983	4983
FBH/Storm Max Water Surface Elevation (ft)	4988.24	4988.88	4989.94	4989.43	4988.68	4984.07	4985.34	4987.05	4988.05	4988.66	4989.51	4990.18	4991.01	NA	4990.14	4988.08
Height of Water Above Auxillary Spillway (ft)	0.59	0.45	0.44	-0.07	-0.82	-5.43	-4.16	-2.45	-1.45	-0.84	0.01	0.68	1.51	NA	0.64	-1.42
Final Dam Crest (ft)	4990.65	4991.43	4992.5	4992.5	4992.5	4992.5	4992.5	4992.5	4992.5	4992.5	4992.5	4992.5	4992.5	NA	4992.5	4992.5
Site	5 Above Grade															
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCIII 24hr 100yr	ARCIII 6hr	10yr Burn Condition
Reservoir Bottom Elevation (ft)	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000
Original Dam Crest (ft)	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015	5015
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5
Principal Spillway Elevation Weir (ft)	5011.16	5011.98	5011	5011	5011	5011	5011	5011	5011	5011	5011	5011	5011	5011	5011	5011
Auxillary Spillway Elevation (ft)	5011.17	5011.99	5012.5	5012.5	5012.5	5012.5	5012.5	5012.5	5012.5	5012.5	5012.5	5012.5	5012.5	5012.5	5012.5	5012.5
Volume at Principal Spillway (acre-ft)	*	*	12.21	12.21	12.21	12.21	12.21	12.21	12.21	12.21	12.21	12.21	12.21	12.21	12.21	12.21
Volume at Auxillary Spillway (acre-ft)	*	*	14.64	14.64	14.64	14.64	14.64	14.64	14.64	14.64	14.64	14.64	14.64	14.64	14.64	14.64
Volume at Low Stage Orifice Crest (acre-ft)	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89	2.89
Principal Spillway Weir Length (ft)	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50
Principal Spillway Outlet Pipe Diameter (in)	42	42	42	42	42	42	42	42	42	42	42	42	42	42	42	42
Scaling Factor	1.154	1.154	1.154	1.154	1.154	1.154	1.154	1.154	1.154	1.154	1.154	1.154	1.154	1.154	1.154	1.154
PSH Peak Inflow (cfs)	44	75.44	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Peak Outflow (cfs)	13.6	55.8	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Max Water Surface Elevation (ft)	5011.16	5011.98	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
FBH/Storm Peak Inflow (cfs)	476.6	476.6	475.3	510.4	196	3.1	15.6	38.6	88.4	142.1	209.5	295.7	438.2	501.8	355.9	102.6
FBH/Storm Peak Outflow (cfs)	460.2	430.9	462.8	509.3	195.6	2.3	5	8.2	11.7	29.7	82.2	189.9	385.3	442.8	77.2	11.9
FBH/Storm Peak Principal Spillway Outflow (cfs)	111.2	170.9	218.8	231.3	135.6	2.3	5	8.2	11.7	29.7	82.2	132.9	196.3	213.8	11.2	11.9
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	349	260	244	278	60	0	0	0	0	0	0	57	189	229	66	0
FBH/Storm Initial Water Surface Elevation (ft)	5003.52	5003.52	5011	5011	5011	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5	5003.5
FBH/Storm Max Water Surface Elevation (ft)	5013.05	5013.6	5014.1	5014.23	5013.19	5004.32	5005.31	5006.74	5009.71	5011.57	5012.49	5013.16	5013.87	5014.05	5012.50	5010
Height of Water Above Auxillary Spillway (ft)	1.88	1.61	1.6	1.73	0.69	-8.18	-7.19	-5.76	-2.79	-0.93	-0.01	0.66	1.37	1.55	0	-2.5
Final Dam Crest (ft)	5014.17	5014.99	5015.5	5015.5	5015.5	5015.5	5015.5	5015.5	5015.5	5015.5	5015.5	5015.5	5015.5	5015.5	5015.5	5015.5
Site	5 Below Grade															
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCIII 24hr 100yr	ARCIII 6hr	10yr Burn Condition
Reservoir Bottom Elevation (ft)	4974	4974	4974	4974	4974	4974	4974	4974	4974	4974	4974	4974	4974	NA	4974	4974
Original Dam Crest (ft)	4988	4988	4988	4988	4988	4988	4988	4988	4988	4988	4988	4988	4988	NA	4988	4988
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	4977.52	4977.52	4977.5	4977.5	4977.5	4977.5	4977.5	4977.5	4977.5	4977.5	4977.5	4977.5	4977.5	NA	4977.5	4977.5
Principal Spillway Elevation Weir (ft)	4980.41	4986.81	4986	4986	4986	4986	4986	4986	4986	4986	4986	4986	4986	NA	4986	4986
Auxillary Spillway Elevation (ft)	4980.42	4986.82	4987.3	4987.3	4987.3	4987.3	4987.3	4987.3	4987.3	4987.3	4987.3	4987.3	4987.3	NA	4987.3	4987.3
Volume at Principal Spillway (acre-ft)	*	*	13.8	13.8	13.8	13.8	13.8	13.8	13.8	13.8	13.8	13.8	13.8	NA	13.8	13.8
Volume at Auxillary Spillway (acre-ft)	*	*	15.88	15.88	15.88	15.88	15.88	15.88	15.88	15.88	15.88	15.88	15.88	NA	15.88	15.88
Volume at Low Stage Orifice Crest (acre-ft)	3.09	3.09	3.09	3.09	3.09	3.09	3.09	3.09	3.09	3.09	3.09	3.09	3.09	NA	3.09	3.09
Principal Spillway Weir Length (ft)	12	12	12	12	12	12	12	12	12	12	12	12	12	NA	12	12
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50
Principal Spillway Outlet Pipe Diameter (in)	42	42	42	42	42	42	42	42	42	42	42	42	42	NA	42	42
Scaling Factor	0.8655	0.8655	0.8655	0.8655	0.8655	0.8655	0.8655	0.8655	0.8655	0.8655	0.8655	0.8655	0.8655	NA	0.8655	0.8655
PSH Peak Inflow (cfs)	13.03	56.56	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Peak Outflow (cfs)	7.92	13.85	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Max Water Surface Elevation (ft)	4980.41	4985.79	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
FBH/Storm Peak Inflow (cfs)	123.2	123.2	157.5	91.3	21.6	3.1	15.6	38.6	88.4	142.1	209.5	295.7	438.2	NA	355.9	102.6
FBH/Storm Peak Outflow (cfs)	141.9	81.6	135.8	88.1	38	0	4.9	8.2	11.7	19.9	68.3	171	374.2	NA	194.7	12
FBH/Storm Peak Principal Spillway Outflow (cfs)	43.9	58.6	105.8	79.1	38	2.3	4.9	8.2	11.7	19.9	68.3	119	180.2	NA	126.7	12
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	98	23	30	9	0	0	0	0	0	0	0	52	194	NA	68	0
FBH/Storm Initial Water Surface Elevation (ft)	4977.52	4977.52	4986	4986	4986	4977.5	4977.5	4977.5	4977.5	4977.5	4977.5	4977.5	4977.5	NA	4977.5	4977.5
FBH/Storm Max Water Surface Elevation (ft)	4981.37	4987.12	4987.81	4987.44	4986.72	4978.35	4979.35	4980.73	4983.75	4986.24	4987.27	4987.98	4988.69	NA	4988.08	4984.04

Height of Water Above Auxillary Spillway (ft)	0.95	0.3	0.51	0.14	-0.58	-8.95	-7.95	-6.57	-3.55	-1.06	-0.03	0.68	1.39	NA	0.78	-3.26
Final Dam Crest (ft)	4983.42	4989.82	4990.3	4990.3	4990.3	4990.3	4990.3	4990.3	4990.3	4990.3	4990.3	4990.3	4990.3	NA	4990.3	4990.3
Site	6A Above Grade															
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition
Reservoir Bottom Elevation (ft)	5010	5010	5010	5010	5010	5010	5010	5010	5010	5010	5010	5010	5010	NA	5010	5010
Original Dam Crest (ft)	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	NA	5025	5025
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5014	5014	5014	5014	5014	5014	5014	5014	5014	5014	5014	5014	5014	NA	5014	5014
Principal Spillway Elevation Weir (ft)	5020.18	5020.79	5021	5021	5021	5021	5021	5021	5021	5021	5021	5021	5021	NA	5021	5021
Auxillary Spillway Elevation (ft)	5020.19	5020.8	5022.5	5022.5	5022.5	5022.5	5022.5	5022.5	5022.5	5022.5	5022.5	5022.5	5022.5	NA	5022.5	5022.5
Volume at Principal Spillway (acre-ft)	*	*	11.04	11.04	11.04	11.04	11.04	11.04	11.04	11.04	11.04	11.04	11.04	NA	11.04	11.04
Volume at Auxillary Spillway (acre-ft)	*	*	13.43	13.43	13.43	13.43	13.43	13.43	13.43	13.43	13.43	13.43	13.43	NA	13.43	13.43
Volume at Low Stage Orifice Crest (acre-ft)	2.59	2.59	2.59	2.59	2.59	2.59	2.59	2.59	2.59	2.59	2.59	2.59	2.59	NA	2.59	2.59
Principal Spillway Weir Length (ft)	12	12	12	12	12	12	12	12	12	12	12	12	12	NA	12	12
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50
Principal Spillway Outlet Pipe Diameter (in)	30	30	30	30	30	30	30	30	30	30	30	30	30	NA	30	30
Scaling Factor	1.248	1.248	1.248	1.248	1.248	1.248	1.248	1.248	1.248	1.248	1.248	1.248	1.248	NA	1.248	1.248
PSH Peak Inflow (cfs)	44.74	49.52	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Peak Outflow (cfs)	11.8	12.57	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Max Water Surface Elevation (ft)	5020.18	5020.79	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
FBH/Storm Peak Inflow (cfs)	494.6	487.7	494.6	373.5	132.5	9.5	35.3	67.9	127.8	188.8	262.5	352.6	502.1	NA	367	154
FBH/Storm Peak Outflow (cfs)	464.8	438.6	467.8	370.4	131.6	2.7	5.7	8.7	11.6	19.4	57.4	127.8	288.9	NA	143.5	11.3
FBH/Storm Peak Principal Spillway Outflow (cfs)	114.8	101.6	170.8	170.4	112.6	2.7	5.7	8.7	11.6	19.4	57.4	110.8	169.9	NA	117.5	11.3
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	350	337	297	200	19	0	0	0	0	0	0	17	119	NA	26	0
FBH/Storm Initial Water Surface Elevation (ft)	5014.02	5014.02	5021	5021	5021	5014	5014	5014	5014	5014	5014	5014	5014	NA	5014	5014
FBH/Storm Max Water Surface Elevation (ft)	5022.74	5022.73	5024.29	5023.95	5022.91	5014.97	5016.03	5017.65	5020.19	5021.31	5022.11	5022.89	5023.60	NA	5022.98	5019.85
Height of Water Above Auxillary Spillway (ft)	2.55	1.93	1.79	1.45	0.41	-7.53	-6.47	-4.85	-2.31	-1.19	-0.39	0.39	1.1	NA	0.48	-2.65
Final Dam Crest (ft)	5023.19	5023.8	5025.5	5025.5	5025.5	5025.5	5025.5	5025.5	5025.5	5025.5	5025.5	5025.5	5025.5	NA	5025.5	5025.5
Site	6A Below Grade															
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition
Reservoir Bottom Elevation (ft)	4955	4955	4955	4955	4955	4955	4955	4955	4955	4955	4955	4955	4955	NA	4955	4955
Original Dam Crest (ft)	4970	4970	4970	4970	4970	4970	4970	4970	4970	4970	4970	4970	4970	NA	4970	4970
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	4959	4959	4959	4959	4959	4959	4959	4959	4959	4959	4959	4959	4959	NA	4959	4959
Principal Spillway Elevation Weir (ft)	4968.19	4968.19	4967	4967	4967	4967	4967	4967	4967	4967	4967	4967	4967	NA	4967	4967
Auxillary Spillway Elevation (ft)	4968.2	4968.2	4968.2	4968.2	4968.2	4968.2	4968.2	4968.2	4968.2	4968.2	4968.2	4968.2	4968.2	NA	4968.2	4968.2
Volume at Principal Spillway (acre-ft)	*	*	12.6	12.6	12.6	12.6	12.6	12.6	12.6	12.6	12.6	12.6	12.6	NA	12.6	12.6
Volume at Auxillary Spillway (acre-ft)	*	*	14.6	14.6	14.6	14.6	14.6	14.6	14.6	14.6	14.6	14.6	14.6	NA	14.6	14.6
Volume at Low Stage Orifice Crest (acre-ft)	2.8	2.8	2.8	2.8	2.8	2.8	2.8	2.8	2.8	2.8	2.8	2.8	2.8	NA	2.8	2.8
Principal Spillway Weir Length (ft)	12	12	12	12	12	12	12	12	12	12	12	12	12	NA	12	12
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50
Principal Spillway Outlet Pipe Diameter (in)	30	30	30	30	30	30	30	30	30	30	30	30	30	NA	30	30
Scaling Factor	1.433	1.433	1.433	1.433	1.433	1.433	1.433	1.433	1.433	1.433	1.433	1.433	1.433	NA	1.433	1.433
PSH Peak Inflow (cfs)	24.55	37.16	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Peak Outflow (cfs)	8.8	10.64	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PSH Max Water Surface Elevation (ft)	4968.19	4963.99	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
FBH/Storm Peak Inflow (cfs)	80.4	80.4	251.7	80.4	30.5	9.5	35.3	67.9	127.8	188.8	262.5	352.6	502.1	NA	367	154
FBH/Storm Peak Outflow (cfs)	76.1	35.1	194.1	74.2	26.3	2.7	6.1	8.8	11.7	20.2	63.7	140.1	308.5	NA	107.1	11.4
FBH/Storm Peak Principal Spillway Outflow (cfs)	36.1	22.1	94.1	71.2	26.3	2.7	6.1	8.8	11.7	20.2	63.7	93.1	95.5	NA	92.1	11.4
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	40	13	100	3	0	0	0	0	0	0	0	47	213	NA	15	0
FBH/Storm Initial Water Surface Elevation (ft)	4959	4959	4967	4967	4967	4959	4959	4959	4959	4959	4959	4959	4959	NA	4959	4959
FBH/Storm Max Water Surface Elevation (ft)	4963.26	4966.28	4969.51	4968.32	4967.47	4960.01	4961.26	4962.74	4965.30	4967.28	4968.21	4969.10	4970.10	NA	4968.70	4964.96
Height of Water Above Auxillary Spillway (ft)	-4.94	-1.92	1.31	0.12	-0.73	-8.19	-6.94	-5.46	-2.9	-0.92	0.01	0.9	1.9	NA	0.5	-3.24
Final Dam Crest (ft)	4971.2	4971.2	4971.2	4971.2	4971.2	4971.2	4971.2	4971.2	4971.2	4971.2	4971.2	4971.2	4971.2	NA	4971.2	4971.2

Site	6B Above Grade																
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition	
Reservoir Bottom Elevation (ft)	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	5025	NA	5025	5025	
Original Dam Crest (ft)	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	5040	NA	5040	5040	
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	5028.5	5028.5	5028.5	5028.5	5028.5	5028.5	5028.5	5028.5	5028.5	5028.5	5028.5	5028.5	5028.5	NA	5028.5	5028.5	
Principal Spillway Elevation Weir (ft)	5034.94	5035.59	5037	5037	5037	5037	5037	5037	5037	5037	5037	5037	5037	NA	5037	5037	
Auxillary Spillway Elevation (ft)	5034.95	5035.6	5038.5	5038.5	5038.5	5038.5	5038.5	5038.5	5038.5	5038.5	5038.5	5038.5	5038.5	NA	5038.5	5038.5	
Volume at Principal Spillway (acre-ft)	*	*	12.6	12.6	12.6	12.6	12.6	12.6	12.6	12.6	12.6	12.6	12.6	NA	12.6	12.6	
Volume at Auxillary Spillway (acre-ft)	*	*	14.99	14.99	14.99	14.99	14.99	14.99	14.99	14.99	14.99	14.99	14.99	NA	14.99	14.99	
Volume at Low Stage Orifice Crest (acre-ft)	2.59	2.59	2.59	2.59	2.59	2.59	2.59	2.59	2.59	2.59	2.59	2.59	2.59	NA	2.59	2.59	
Principal Spillway Weir Length (ft)	12	12	12	12	12	12	12	12	12	12	12	12	12	NA	12	12	
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50	
Principal Spillway Outlet Pipe Diameter (in)	30	30	30	30	30	30	30	30	30	30	30	30	30	NA	30	30	
Scaling Factor	1.215	1.215	1.215	1.215	1.215	1.215	1.215	1.215	1.215	1.215	1.215	1.215	1.215	NA	1.215	1.215	
PSH Peak Inflow (cfs)	44.7	49.54	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Peak Outflow (cfs)	12	12.69	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Max Water Surface Elevation (ft)	5034.94	5035.59	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
FBH/Storm Peak Inflow (cfs)	494.6	494.6	494.6	373.5	132.3	9.5	35.3	67.9	127.8	188.8	262.5	352.6	502.1	NA	367	154	
FBH/Storm Peak Outflow (cfs)	463.8	454.2	470.5	371.9	132.4	2.7	6.1	8.9	12	18.6	63.2	143.6	325.5	NA	11.6	11.6	
FBH/Storm Peak Principal Spillway Outflow (cfs)	99.8	101.2	107.5	106.9	104.4	2.7	6.1	8.9	12	18.6	63.2	104.6	106.5	NA	99.3	11.6	
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	364	353	363	265	28	0	0	0	0	0	0	39	219	NA	7	0	
FBH/Storm Initial Water Surface Elevation (ft)	5028.52	5028.52	5037	5037	5037	5028.5	5028.5	5028.5	5028.5	5028.5	5028.5	5028.5	5028.5	NA	5028.5	5028.5	
FBH/Storm Max Water Surface Elevation (ft)	5036.97	5097.58	5040.46	5040.16	5039.01	5029.52	5030.82	5032.35	5035.04	5037.21	5038.18	5039.10	5040.01	NA	5038.72	5034.66	
Height of Water Above Auxillary Spillway (ft)	2.02	61.98	1.96	1.66	0.51	-8.98	-7.68	-6.15	-3.46	-1.29	-0.32	0.6	1.51	NA	0.22	-3.84	
Final Dam Crest (ft)	5037.95	5038.6	5041.5	5041.5	5041.5	5041.5	5041.5	5041.5	5041.5	5041.5	5041.5	5041.5	5041.5	NA	5041.5	5041.5	
Site	6B Below Grade																
Storm Scenario	6hrBase	Snowmelt	6hr SEF	24hr SEF	72hr SEF	2yr	5yr	10yr	25yr	50yr	100yr	200yr	500yr	Type 2 ARCI 24hr 100yr	ARCI 6hr	10yr Burn Condition	
Reservoir Bottom Elevation (ft)	4985	4985	4985	4985	4985	4985	4985	4985	4985	4985	4985	4985	4985	NA	4985	4985	
Original Dam Crest (ft)	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	5000	NA	5000	5000	
Low Stage Orifice Crest (ft) (2' x 0.5' Orifice)	4988.5	4988.5	4988.5	4988.5	4988.5	4988.5	4988.5	4988.5	4988.5	4988.5	4988.5	4988.5	4988.5	NA	4988.5	4988.5	
Principal Spillway Elevation Weir (ft)	4992.04	4995.57	4997	4997	4997	4997	4997	4997	4997	4997	4997	4997	4997	NA	4997	4997	
Auxillary Spillway Elevation (ft)	4992.05	4995.58	4998.2	4998.2	4998.2	4998.2	4998.2	4998.2	4998.2	4998.2	4998.2	4998.2	4998.2	NA	4998.2	4998.2	
Volume at Principal Spillway (acre-ft)	*	*	12.6	12.6	12.6	12.6	12.6	12.6	12.6	12.6	12.6	12.6	12.6	NA	12.6	12.6	
Volume at Auxillary Spillway (acre-ft)	*	*	14.52	14.52	14.52	14.52	14.52	14.52	14.52	14.52	14.52	14.52	14.52	NA	14.52	14.52	
Volume at Low Stage Orifice Crest (acre-ft)	2.54	2.54	2.54	2.54	2.54	2.54	2.54	2.54	2.54	2.54	2.54	2.54	2.54	NA	2.54	2.54	
Principal Spillway Weir Length (ft)	12	12	12	12	12	12	12	12	12	12	12	12	12	NA	12	12	
Auxillary Spillway Width (ft)	50	50	50	50	50	50	50	50	50	50	50	50	50	NA	50	50	
Principal Spillway Outlet Pipe Diameter (in)	30	30	30	30	30	30	30	30	30	30	30	30	30	NA	30	30	
Scaling Factor	1.1667	1.1667	1.1667	1.1667	1.1667	1.1667	1.1667	1.1667	1.1667	1.1667	1.1667	1.1667	1.1667	NA	1.1667	1.1667	
PSH Peak Inflow (cfs)	24.54	37.17	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Peak Outflow (cfs)	8.94	10.75	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
PSH Max Water Surface Elevation (ft)	4992.04	4993.62	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
FBH/Storm Peak Inflow (cfs)	182.9	182.9	182.9	80.4	30.5	3.2	19.1	50.6	119.4	193.6	286.7	404.9	601.8	NA	367	154	
FBH/Storm Peak Outflow (cfs)	146	78.2	146	75.8	24.5	2.7	6.1	8.9	12	18.5	61.8	159.2	342	NA	113.7	11.6	
FBH/Storm Peak Principal Spillway Outflow (cfs)	46	32.2	104	71.8	24.5	2.7	6.1	8.9	12	18.5	61.8	104.2	106	NA	92.7	11.6	
FBH/Storm Peak Auxillary Spillway Outflow (cfs)	100	46	42	4	0	0	0	0	0	0	0	55	236	NA	21	0	
FBH/Storm Initial Water Surface Elevation (ft)	4988.52	4988.52	4997	4997	4997	4988.5	4988.5	4988.5	4988.5	4988.5	4988.5	4988.5	4988.5	NA	4988.5	4988.5	
FBH/Storm Max Water Surface Elevation (ft)	4993.02	4996.22	4998.82	4998.33	4997.42	4989.53	4990.83	4992.36	4995.03	4997.19	4998.17	4998.92	4999.77	NA	4998.63	4994.66	
Height of Water Above Auxillary Spillway (ft)	0.97	0.64	0.62	0.13	-0.78	-8.67	-7.37	-5.84	-3.17	-1.01	-0.03	0.72	1.57	NA	0.43	-3.54	
Final Dam Crest (ft)	4995.05	4998.58	5001.2	5001.2	5001.2	5001.2	5001.2	5001.2	5001.2	5001.2	5001.2	5001.2	5001.2	NA	5001.2	5001.2	

Basin 1					
Time (hr)	Q (cfs)	Incremental Volume (ft3)	Incremental Volume (ac-ft)	Cumulative Volume (ft3)	Cumulative Volume (ac-ft)
11.8	0	0		0	0.00
11.9	1.5	270	0.006	270	0.01
12	9.6	1,998	0.046	2,268	0.05
12.1	42.4	9,360	0.215	11,628	0.27
12.2	116.5	28,602	0.657	40,230	0.92
12.3	214.5	59,580	1.368	99,810	2.29
12.4	278.1	88,668	2.036	188,478	4.33
12.47	291.6	71,782	1.648	260,260	5.97
12.5	289.6	31,385	0.720	291,645	6.70
12.6	262.1	99,306	2.280	390,951	8.97
12.7	218.2	86,454	1.985	477,405	10.96
12.8	180.7	71,802	1.648	549,207	12.61
12.9	150.4	59,598	1.368	608,805	13.98
13	126.1	49,770	1.143	658,575	15.12
13.1	106.9	41,940	0.963	700,515	16.08
13.2	91.6	35,730	0.820	736,245	16.90
13.3	79.1	30,726	0.705	766,971	17.61
13.4	69	26,658	0.612	793,629	18.22
13.5	60.5	23,310	0.535	816,939	18.75
13.6	53.5	20,520	0.471	837,459	19.23
13.7	47.6	18,198	0.418	855,657	19.64
13.8	42.3	16,182	0.371	871,839	20.01
13.9	38	14,454	0.332	886,293	20.35
14	34.6	13,068	0.300	899,361	20.65
14.1	32.1	12,006	0.276	911,367	20.92
14.2	30.2	11,214	0.257	922,581	21.18
14.3	28.6	10,584	0.243	933,165	21.42
14.4	27.2	10,044	0.231	943,209	21.65
14.5	26	9,576	0.220	952,785	21.87
14.6	24.8	9,144	0.210	961,929	22.08
14.7	23.7	8,730	0.200	970,659	22.28
14.8	22.6	8,334	0.191	978,993	22.47
14.9	21.5	7,938	0.182	986,931	22.66
15	20.5	7,560	0.174	994,491	22.83
15.1	19.4	7,182	0.165	1,001,673	23.00
15.2	18.3	6,786	0.156	1,008,459	23.15
15.3	17.4	6,426	0.148	1,014,885	23.30
15.4	16.5	6,102	0.140	1,020,987	23.44
15.5	15.8	5,814	0.133	1,026,801	23.57
15.6	15.2	5,580	0.128	1,032,381	23.70
15.7	14.8	5,400	0.124	1,037,781	23.82
15.8	14.4	5,256	0.121	1,043,037	23.94
15.9	14.1	5,130	0.118	1,048,167	24.06
16	13.8	5,022	0.115	1,053,189	24.18
16.1	13.5	4,914	0.113	1,058,103	24.29
16.2	13.3	4,824	0.111	1,062,927	24.40
16.3	13	4,734	0.109	1,067,661	24.51
16.4	12.7	4,626	0.106	1,072,287	24.62
16.5	12.5	4,536	0.104	1,076,823	24.72
16.6	12.2	4,446	0.102	1,081,269	24.82
16.7	12	4,356	0.100	1,085,625	24.92
16.8	11.7	4,266	0.098	1,089,891	25.02
16.9	11.5	4,176	0.096	1,094,067	25.12
17	11.2	4,086	0.094	1,098,153	25.21
17.1	11	3,996	0.092	1,102,149	25.30
17.2	10.7	3,906	0.090	1,106,055	25.39
17.3	10.5	3,816	0.088	1,109,871	25.48
17.4	10.2	3,726	0.086	1,113,597	25.56
17.5	9.9	3,618	0.083	1,117,215	25.65
17.6	9.7	3,528	0.081	1,120,743	25.73
17.7	9.4	3,438	0.079	1,124,181	25.81
17.8	9.2	3,348	0.077	1,127,529	25.88
17.9	8.9	3,258	0.075	1,130,787	25.96
18	8.6	3,150	0.072	1,133,937	26.03
18.1	8.4	3,060	0.070	1,136,997	26.10
18.2	8.1	2,970	0.068	1,139,967	26.17
18.3	7.9	2,880	0.066	1,142,847	26.24
18.4	7.7	2,808	0.064	1,145,655	26.30
18.5	7.5	2,736	0.063	1,148,391	26.36
18.6	7.3	2,664	0.061	1,151,055	26.42
18.7	7.2	2,610	0.060	1,153,665	26.48

18.8	7.1	2,574	0.059	1,156,239	26.54
18.9	7.1	2,556	0.059	1,158,795	26.60
19	7	2,538	0.058	1,161,333	26.66
19.1	6.9	2,502	0.057	1,163,835	26.72
19.2	6.8	2,466	0.057	1,166,301	26.77
19.3	6.8	2,448	0.056	1,168,749	26.83
19.4	6.7	2,430	0.056	1,171,179	26.89
19.5	6.6	2,394	0.055	1,173,573	26.94
19.6	6.6	2,376	0.055	1,175,949	27.00
19.7	6.5	2,358	0.054	1,178,307	27.05
19.8	6.4	2,322	0.053	1,180,629	27.10
19.9	6.4	2,304	0.053	1,182,933	27.16
20	6.3	2,286	0.052	1,185,219	27.21
20.1	6.2	2,250	0.052	1,187,469	27.26
20.2	6.2	2,232	0.051	1,189,701	27.31
20.3	6.1	2,214	0.051	1,191,915	27.36
20.4	6.1	2,196	0.050	1,194,111	27.41
20.5	6	2,178	0.050	1,196,289	27.46
20.6	5.9	2,142	0.049	1,198,431	27.51
20.7	5.9	2,124	0.049	1,200,555	27.56
20.8	5.8	2,106	0.048	1,202,661	27.61
20.9	5.7	2,070	0.048	1,204,731	27.66
21	5.7	2,052	0.047	1,206,783	27.70
21.1	5.6	2,034	0.047	1,208,817	27.75
21.2	5.5	1,998	0.046	1,210,815	27.80
21.3	5.5	1,980	0.045	1,212,795	27.84
21.4	5.4	1,962	0.045	1,214,757	27.89
21.5	5.3	1,926	0.044	1,216,683	27.93
21.6	5.3	1,908	0.044	1,218,591	27.98
21.7	5.2	1,890	0.043	1,220,481	28.02
21.8	5.1	1,854	0.043	1,222,335	28.06
21.9	5.1	1,836	0.042	1,224,171	28.10
22	5	1,818	0.042	1,225,989	28.14
22.1	4.9	1,782	0.041	1,227,771	28.19
22.2	4.9	1,764	0.040	1,229,535	28.23
22.3	4.8	1,746	0.040	1,231,281	28.27
22.4	4.7	1,710	0.039	1,232,991	28.31
22.5	4.7	1,692	0.039	1,234,683	28.34
22.6	4.6	1,674	0.038	1,236,357	28.38
22.7	4.5	1,638	0.038	1,237,995	28.42
22.8	4.5	1,620	0.037	1,239,615	28.46
22.9	4.4	1,602	0.037	1,241,217	28.49
23	4.3	1,566	0.036	1,242,783	28.53
23.1	4.3	1,548	0.036	1,244,331	28.57
23.2	4.2	1,530	0.035	1,245,861	28.60
23.3	4.1	1,494	0.034	1,247,355	28.64
23.4	4	1,458	0.033	1,248,813	28.67
23.5	4	1,440	0.033	1,250,253	28.70
23.6	3.9	1,422	0.033	1,251,675	28.73
23.7	3.8	1,386	0.032	1,253,061	28.77
23.8	3.8	1,368	0.031	1,254,429	28.80
23.9	3.7	1,350	0.031	1,255,779	28.83
24	3.6	1,314	0.030	1,257,093	28.86
24.1	3.5	1,278	0.029	1,258,371	28.89
24.2	3.2	1,206	0.028	1,259,577	28.92
24.3	2.6	1,044	0.024	1,260,621	28.94
24.4	1.9	810	0.019	1,261,431	28.96
24.5	1.3	576	0.013	1,262,007	28.97
24.6	0.8	378	0.009	1,262,385	28.98
24.7	0.5	234	0.005	1,262,619	28.99

Basin 2,3					
Time (hr)	Q (cfs)	Incremental Volume (ft3)	Incremental Volume (ac-ft)	Cumulative Volume (ft3)	Cumulative Volume (ac-ft)
0	0	0		0	0.00
11.9	0.7	14,994	0.344	14,994	0.34
12	7.1	1,404	0.032	16,398	0.38
12.1	31.4	6,930	0.159	23,328	0.54
12.2	71.7	18,558	0.426	41,886	0.96
12.23	76.7	8,014	0.184	49,900	1.15
12.3	69.8	18,459	0.424	68,359	1.57
12.4	49.1	21,402	0.491	89,761	2.06
12.5	35	15,138	0.348	104,899	2.41
12.6	26.9	11,142	0.256	116,041	2.66
12.7	21	8,622	0.198	124,663	2.86
12.8	16.9	6,822	0.157	131,485	3.02
12.9	14.5	5,652	0.130	137,137	3.15
13	12.8	4,914	0.113	142,051	3.26
13.1	11.2	4,320	0.099	146,371	3.36
13.2	9.9	3,798	0.087	150,169	3.45
13.3	8.7	3,348	0.077	153,517	3.52
13.4	8	3,006	0.069	156,523	3.59
13.5	7.1	2,718	0.062	159,241	3.66
13.6	6.4	2,430	0.056	161,671	3.71
13.7	5.8	2,196	0.050	163,867	3.76
13.8	5.3	1,998	0.046	165,865	3.81
13.9	5	1,854	0.043	167,719	3.85
14	4.8	1,764	0.040	169,483	3.89
14.1	4.7	1,710	0.039	171,193	3.93
14.2	4.5	1,656	0.038	172,849	3.97
14.3	4.3	1,584	0.036	174,433	4.00
14.4	4.1	1,512	0.035	175,945	4.04
14.5	3.9	1,440	0.033	177,385	4.07
14.6	3.8	1,386	0.032	178,771	4.10
14.7	3.6	1,332	0.031	180,103	4.13
14.8	3.4	1,260	0.029	181,363	4.16
14.9	3.2	1,188	0.027	182,551	4.19
15	3	1,116	0.026	183,667	4.22
15.1	2.9	1,062	0.024	184,729	4.24
15.2	2.7	1,008	0.023	185,737	4.26
15.3	2.6	954	0.022	186,691	4.29
15.4	2.5	918	0.021	187,609	4.31
15.5	2.5	900	0.021	188,509	4.33
15.6	2.5	900	0.021	189,409	4.35
15.7	2.4	882	0.020	190,291	4.37
15.8	2.3	846	0.019	191,137	4.39
15.9	2.3	828	0.019	191,965	4.41
16	2.3	828	0.019	192,793	4.43
16.1	2.2	810	0.019	193,603	4.44
16.2	2.2	792	0.018	194,395	4.46
16.3	2.1	774	0.018	195,169	4.48
16.4	2.1	756	0.017	195,925	4.50
16.5	2.1	756	0.017	196,681	4.52
16.6	2	738	0.017	197,419	4.53
16.7	2	720	0.017	198,139	4.55
16.8	1.9	702	0.016	198,841	4.56
16.9	1.9	684	0.016	199,525	4.58
17	1.8	666	0.015	200,191	4.60
17.1	1.8	648	0.015	200,839	4.61
17.2	1.8	648	0.015	201,487	4.63
17.3	1.7	630	0.014	202,117	4.64
17.4	1.6	594	0.014	202,711	4.65
17.5	1.6	576	0.013	203,287	4.67
17.6	1.6	576	0.013	203,863	4.68
17.7	1.6	576	0.013	204,439	4.69
17.8	1.4	540	0.012	204,979	4.71
17.9	1.4	504	0.012	205,483	4.72
18	1.4	504	0.012	205,987	4.73
18.1	1.4	504	0.012	206,491	4.74
18.2	1.3	486	0.011	206,977	4.75
18.3	1.3	468	0.011	207,445	4.76
18.4	1.2	450	0.010	207,895	4.77
18.5	1.2	432	0.010	208,327	4.78
18.6	1.2	432	0.010	208,759	4.79
18.7	1.2	432	0.010	209,191	4.80
18.8	1.2	432	0.010	209,623	4.81

18.9	1.2	432	0.010	210,055	4.82
19	1.2	432	0.010	210,487	4.83
19.1	1.2	432	0.010	210,919	4.84
19.2	1.2	432	0.010	211,351	4.85
19.3	1.2	432	0.010	211,783	4.86
19.4	0.6	324	0.007	212,107	4.87
19.4	4.3	0	0.000	212,107	4.87
19.5	4.3	1,548	0.036	213,655	4.90
19.6	4.2	1,530	0.035	215,185	4.94
19.7	4.2	1,512	0.035	216,697	4.97
19.8	4.1	1,494	0.034	218,191	5.01
19.9	4.1	1,476	0.034	219,667	5.04
20	4	1,458	0.033	221,125	5.08
20.1	4	1,440	0.033	222,565	5.11
20.2	3.9	1,422	0.033	223,987	5.14
20.3	3.9	1,404	0.032	225,391	5.17
20.4	3.9	1,404	0.032	226,795	5.21
20.5	3.8	1,386	0.032	228,181	5.24
20.6	3.8	1,368	0.031	229,549	5.27
20.7	3.7	1,350	0.031	230,899	5.30
20.8	3.7	1,332	0.031	232,231	5.33
20.9	3.6	1,314	0.030	233,545	5.36
21	3.6	1,296	0.030	234,841	5.39
21.1	3.5	1,278	0.029	236,119	5.42
21.2	3.5	1,260	0.029	237,379	5.45
21.3	3.5	1,260	0.029	238,639	5.48
21.4	3.4	1,242	0.029	239,881	5.51
21.5	3.4	1,224	0.028	241,105	5.54
21.6	3.3	1,206	0.028	242,311	5.56
21.7	3.3	1,188	0.027	243,499	5.59
21.8	3.2	1,170	0.027	244,669	5.62
21.9	3.2	1,152	0.026	245,821	5.64
22	3.1	1,134	0.026	246,955	5.67
22.1	3.1	1,116	0.026	248,071	5.69
22.2	3.1	1,116	0.026	249,187	5.72
22.3	3	1,098	0.025	250,285	5.75
22.4	3	1,080	0.025	251,365	5.77
22.5	2.9	1,062	0.024	252,427	5.79
22.6	2.9	1,044	0.024	253,471	5.82
22.7	2.8	1,026	0.024	254,497	5.84
22.8	2.8	1,008	0.023	255,505	5.87
22.9	2.7	990	0.023	256,495	5.89
23	2.7	972	0.022	257,467	5.91
23.1	2.6	954	0.022	258,421	5.93
23.2	2.6	936	0.021	259,357	5.95
23.3	2.6	936	0.021	260,293	5.98
23.4	2.5	918	0.021	261,211	6.00
23.5	2.5	900	0.021	262,111	6.02
23.6	2.4	882	0.020	262,993	6.04
23.7	2.4	864	0.020	263,857	6.06
23.8	2.3	846	0.019	264,703	6.08
23.9	2.3	828	0.019	265,531	6.10
24	2.2	810	0.019	266,341	6.11
24.1	2.1	774	0.018	267,115	6.13
24.2	1.6	666	0.015	267,781	6.15
24.3	1	468	0.011	268,249	6.16
24.4	0.5	270	0.006	268,519	6.16
24.5	0	90	0.002	268,609	6.17

Basin 4					
Time (hr)	Q (cfs)	Incremental Volume (ft3)	Incremental Volume (ac-ft)	Cumulative Volume (ft3)	Cumulative Volume (ac-ft)
0	0	0		0	0.00
11.8	0	0	0.000	0	0.00
11.9	1.5	270	0.006	270	0.01
12	9.6	1,998	0.046	2,268	0.05
12.1	42.4	9,360	0.215	11,628	0.27
12.2	116.5	28,602	0.657	40,230	0.92
12.3	214.5	59,580	1.368	99,810	2.29
12.4	278.1	88,668	2.036	188,478	4.33
12.47	291.6	71,782	1.648	260,260	5.97
12.5	289.6	31,385	0.720	291,645	6.70
12.6	262.1	99,306	2.280	390,951	8.97
12.7	218.2	86,454	1.985	477,405	10.96
12.8	180.7	71,802	1.648	549,207	12.61
12.9	150.4	59,598	1.368	608,805	13.98
13	126.1	49,770	1.143	658,575	15.12
13.1	106.9	41,940	0.963	700,515	16.08
13.2	91.6	35,730	0.820	736,245	16.90
13.3	79.1	30,726	0.705	766,971	17.61
13.4	69	26,658	0.612	793,629	18.22
13.5	60.5	23,310	0.535	816,939	18.75
13.6	53.5	20,520	0.471	837,459	19.23
13.7	47.6	18,198	0.418	855,657	19.64
13.8	42.3	16,182	0.371	871,839	20.01
13.9	38	14,454	0.332	886,293	20.35
14	34.6	13,068	0.300	899,361	20.65
14.1	32.1	12,006	0.276	911,367	20.92
14.2	30.2	11,214	0.257	922,581	21.18
14.3	28.6	10,584	0.243	933,165	21.42
14.4	27.2	10,044	0.231	943,209	21.65
14.5	26	9,576	0.220	952,785	21.87
14.6	24.8	9,144	0.210	961,929	22.08
14.7	23.7	8,730	0.200	970,659	22.28
14.8	22.6	8,334	0.191	978,993	22.47
14.9	21.5	7,938	0.182	986,931	22.66
15	20.5	7,560	0.174	994,491	22.83
15.1	19.4	7,182	0.165	1,001,673	23.00
15.2	18.3	6,786	0.156	1,008,459	23.15
15.3	17.4	6,426	0.148	1,014,885	23.30
15.4	16.5	6,102	0.140	1,020,987	23.44
15.5	15.8	5,814	0.133	1,026,801	23.57
15.6	15.2	5,580	0.128	1,032,381	23.70
15.7	14.8	5,400	0.124	1,037,781	23.82
15.8	14.4	5,256	0.121	1,043,037	23.94
15.9	14.1	5,130	0.118	1,048,167	24.06
16	13.8	5,022	0.115	1,053,189	24.18
16.1	13.5	4,914	0.113	1,058,103	24.29
16.2	13.3	4,824	0.111	1,062,927	24.40
16.3	13	4,734	0.109	1,067,661	24.51
16.4	12.7	4,626	0.106	1,072,287	24.62
16.5	12.5	4,536	0.104	1,076,823	24.72
16.6	12.2	4,446	0.102	1,081,269	24.82
16.7	12	4,356	0.100	1,085,625	24.92
16.8	11.7	4,266	0.098	1,089,891	25.02
16.9	11.5	4,176	0.096	1,094,067	25.12
17	11.2	4,086	0.094	1,098,153	25.21
17.1	11	3,996	0.092	1,102,149	25.30
17.2	10.7	3,906	0.090	1,106,055	25.39
17.3	10.5	3,816	0.088	1,109,871	25.48
17.4	10.2	3,726	0.086	1,113,597	25.56
17.5	9.9	3,618	0.083	1,117,215	25.65
17.6	9.7	3,528	0.081	1,120,743	25.73
17.7	9.4	3,438	0.079	1,124,181	25.81
17.8	9.2	3,348	0.077	1,127,529	25.88
17.9	8.9	3,258	0.075	1,130,787	25.96
18	8.6	3,150	0.072	1,133,937	26.03
18.1	8.4	3,060	0.070	1,136,997	26.10
18.2	8.1	2,970	0.068	1,139,967	26.17
18.3	7.9	2,880	0.066	1,142,847	26.24
18.4	7.7	2,808	0.064	1,145,655	26.30
18.5	7.5	2,736	0.063	1,148,391	26.36
18.6	7.3	2,664	0.061	1,151,055	26.42
18.7	7.2	2,610	0.060	1,153,665	26.48

18.8	7.1	2,574	0.059	1,156,239	26.54
18.9	7.1	2,556	0.059	1,158,795	26.60
19	7	2,538	0.058	1,161,333	26.66
19.1	6.9	2,502	0.057	1,163,835	26.72
19.2	6.8	2,466	0.057	1,166,301	26.77
19.3	6.8	2,448	0.056	1,168,749	26.83
19.4	6.7	2,430	0.056	1,171,179	26.89
19.5	6.6	2,394	0.055	1,173,573	26.94
19.6	6.6	2,376	0.055	1,175,949	27.00
19.7	6.5	2,358	0.054	1,178,307	27.05
19.8	6.4	2,322	0.053	1,180,629	27.10
19.9	6.4	2,304	0.053	1,182,933	27.16
20	6.3	2,286	0.052	1,185,219	27.21
20.1	6.2	2,250	0.052	1,187,469	27.26
20.2	6.2	2,232	0.051	1,189,701	27.31
20.3	6.1	2,214	0.051	1,191,915	27.36
20.4	6.1	2,196	0.050	1,194,111	27.41
20.5	6	2,178	0.050	1,196,289	27.46
20.6	5.9	2,142	0.049	1,198,431	27.51
20.7	5.9	2,124	0.049	1,200,555	27.56
20.8	5.8	2,106	0.048	1,202,661	27.61
20.9	5.7	2,070	0.048	1,204,731	27.66
21	5.7	2,052	0.047	1,206,783	27.70
21.1	5.6	2,034	0.047	1,208,817	27.75
21.2	5.5	1,998	0.046	1,210,815	27.80
21.3	5.5	1,980	0.045	1,212,795	27.84
21.4	5.4	1,962	0.045	1,214,757	27.89
21.5	5.3	1,926	0.044	1,216,683	27.93
21.6	5.3	1,908	0.044	1,218,591	27.98
21.7	5.2	1,890	0.043	1,220,481	28.02
21.8	5.1	1,854	0.043	1,222,335	28.06
21.9	5.1	1,836	0.042	1,224,171	28.10
22	5	1,818	0.042	1,225,989	28.14
22.1	4.9	1,782	0.041	1,227,771	28.19
22.2	4.9	1,764	0.040	1,229,535	28.23
22.3	4.8	1,746	0.040	1,231,281	28.27
22.4	4.7	1,710	0.039	1,232,991	28.31
22.5	4.7	1,692	0.039	1,234,683	28.34
22.6	4.6	1,674	0.038	1,236,357	28.38
22.7	4.5	1,638	0.038	1,237,995	28.42
22.8	4.5	1,620	0.037	1,239,615	28.46
22.9	4.4	1,602	0.037	1,241,217	28.49
23	4.3	1,566	0.036	1,242,783	28.53
23.1	4.3	1,548	0.036	1,244,331	28.57
23.2	4.2	1,530	0.035	1,245,861	28.60
23.3	4.1	1,494	0.034	1,247,355	28.64
23.4	4	1,458	0.033	1,248,813	28.67
23.5	4	1,440	0.033	1,250,253	28.70
23.6	3.9	1,422	0.033	1,251,675	28.73
23.7	3.8	1,386	0.032	1,253,061	28.77
23.8	3.8	1,368	0.031	1,254,429	28.80
23.9	3.7	1,350	0.031	1,255,779	28.83
24	3.6	1,314	0.030	1,257,093	28.86
24.1	3.5	1,278	0.029	1,258,371	28.89
24.2	3.2	1,206	0.028	1,259,577	28.92
24.3	2.6	1,044	0.024	1,260,621	28.94
24.4	1.9	810	0.019	1,261,431	28.96
24.5	1.3	576	0.013	1,262,007	28.97
24.6	0.8	378	0.009	1,262,385	28.98
24.7	0.5	234	0.005	1,262,619	28.99

Basin 5					
Time (hr)	Q (cfs)	Incremental Volume (ft3)	Incremental Volume (ac-ft)	Cumulative Volume (ft3)	Cumulative Volume (ac-ft)
0	0	0		0	0.00
11.9	0	0	0.000	0	0.00
12	2.2	396	0.009	396	0.01
12.1	17.4	3,528	0.081	3,924	0.09
12.2	58.6	13,680	0.314	17,604	0.40
12.3	123.3	32,742	0.752	50,346	1.16
12.4	179.5	54,504	1.251	104,850	2.41
12.5	206.8	69,534	1.596	174,384	4.00
12.55	209.5	37,467	0.860	211,851	4.86
12.6	205.6	37,359	0.858	249,210	5.72
12.7	184.2	70,164	1.611	319,374	7.33
12.8	157.1	61,434	1.410	380,808	8.74
12.9	134	52,398	1.203	433,206	9.95
13	114.7	44,766	1.028	477,972	10.97
13.1	98.6	38,394	0.881	516,366	11.85
13.2	85.3	33,102	0.760	549,468	12.61
13.3	74.3	28,728	0.660	578,196	13.27
13.4	65	25,074	0.576	603,270	13.85
13.5	57.3	22,014	0.505	625,284	14.35
13.6	50.7	19,440	0.446	644,724	14.80
13.7	45.1	17,244	0.396	661,968	15.20
13.8	40.3	15,372	0.353	677,340	15.55
13.9	36.3	13,788	0.317	691,128	15.87
14	32.9	12,456	0.286	703,584	16.15
14.1	30.2	11,358	0.261	714,942	16.41
14.2	28.1	10,494	0.241	725,436	16.65
14.3	26.4	9,810	0.225	735,246	16.88
14.4	25.1	9,270	0.213	744,516	17.09
14.5	23.9	8,820	0.202	753,336	17.29
14.6	22.8	8,406	0.193	761,742	17.49
14.7	21.7	8,010	0.184	769,752	17.67
14.8	20.7	7,632	0.175	777,384	17.85
14.9	19.8	7,290	0.167	784,674	18.01
15	18.8	6,948	0.160	791,622	18.17
15.1	17.8	6,588	0.151	798,210	18.32
15.2	16.9	6,246	0.143	804,456	18.47
15.3	16	5,922	0.136	810,378	18.60
15.4	15.2	5,616	0.129	815,994	18.73
15.5	14.5	5,346	0.123	821,340	18.86
15.6	14	5,130	0.118	826,470	18.97
15.7	13.5	4,950	0.114	831,420	19.09
15.8	13.2	4,806	0.110	836,226	19.20
15.9	12.8	4,680	0.107	840,906	19.30
16	12.6	4,572	0.105	845,478	19.41
16.1	12.3	4,482	0.103	849,960	19.51
16.2	12	4,374	0.100	854,334	19.61
16.3	11.8	4,284	0.098	858,618	19.71
16.4	11.6	4,212	0.097	862,830	19.81
16.5	11.3	4,122	0.095	866,952	19.90
16.6	11.1	4,032	0.093	870,984	20.00
16.7	10.9	3,960	0.091	874,944	20.09
16.8	10.7	3,888	0.089	878,832	20.18
16.9	10.4	3,798	0.087	882,630	20.26
17	10.2	3,708	0.085	886,338	20.35
17.1	10	3,636	0.083	889,974	20.43
17.2	9.8	3,564	0.082	893,538	20.51
17.3	9.5	3,474	0.080	897,012	20.59
17.4	9.3	3,384	0.078	900,396	20.67
17.5	9.1	3,312	0.076	903,708	20.75
17.6	8.8	3,222	0.074	906,930	20.82
17.7	8.6	3,132	0.072	910,062	20.89
17.8	8.4	3,060	0.070	913,122	20.96
17.9	8.1	2,970	0.068	916,092	21.03
18	7.9	2,880	0.066	918,972	21.10
18.1	7.7	2,808	0.064	921,780	21.16
18.2	7.4	2,718	0.062	924,498	21.22
18.3	7.2	2,628	0.060	927,126	21.28
18.4	7	2,556	0.059	929,682	21.34
18.5	6.8	2,484	0.057	932,166	21.40
18.6	6.7	2,430	0.056	934,596	21.46
18.7	6.6	2,394	0.055	936,990	21.51
18.8	6.5	2,358	0.054	939,348	21.56



18.9	6.4	2,322	0.053	941,670	21.62
19	6.3	2,286	0.052	943,956	21.67
19.1	6.3	2,268	0.052	946,224	21.72
19.2	6.2	2,250	0.052	948,474	21.77
19.3	6.2	2,232	0.051	950,706	21.83
19.4	6.1	2,214	0.051	952,920	21.88
19.5	6	2,178	0.050	955,098	21.93
19.6	6	2,160	0.050	957,258	21.98
19.7	5.9	2,142	0.049	959,400	22.02
19.8	5.8	2,106	0.048	961,506	22.07
19.9	5.8	2,088	0.048	963,594	22.12
20	5.7	2,070	0.048	965,664	22.17
20.1	5.7	2,052	0.047	967,716	22.22
20.2	5.6	2,034	0.047	969,750	22.26
20.3	5.6	2,016	0.046	971,766	22.31
20.4	5.5	1,998	0.046	973,764	22.35
20.5	5.4	1,962	0.045	975,726	22.40
20.6	5.4	1,944	0.045	977,670	22.44
20.7	5.3	1,926	0.044	979,596	22.49
20.8	5.3	1,908	0.044	981,504	22.53
20.9	5.2	1,890	0.043	983,394	22.58
21	5.2	1,872	0.043	985,266	22.62
21.1	5.1	1,854	0.043	987,120	22.66
21.2	5	1,818	0.042	988,938	22.70
21.3	5	1,800	0.041	990,738	22.74
21.4	4.9	1,782	0.041	992,520	22.79
21.5	4.9	1,764	0.040	994,284	22.83
21.6	4.8	1,746	0.040	996,030	22.87
21.7	4.7	1,710	0.039	997,740	22.90
21.8	4.7	1,692	0.039	999,432	22.94
21.9	4.6	1,674	0.038	1,001,106	22.98
22	4.6	1,656	0.038	1,002,762	23.02
22.1	4.5	1,638	0.038	1,004,400	23.06
22.2	4.4	1,602	0.037	1,006,002	23.09
22.3	4.4	1,584	0.036	1,007,586	23.13
22.4	4.3	1,566	0.036	1,009,152	23.17
22.5	4.3	1,548	0.036	1,010,700	23.20
22.6	4.2	1,530	0.035	1,012,230	23.24
22.7	4.1	1,494	0.034	1,013,724	23.27
22.8	4.1	1,476	0.034	1,015,200	23.31
22.9	4	1,458	0.033	1,016,658	23.34
23	4	1,440	0.033	1,018,098	23.37
23.1	3.9	1,422	0.033	1,019,520	23.40
23.2	3.8	1,386	0.032	1,020,906	23.44
23.3	3.8	1,368	0.031	1,022,274	23.47
23.4	3.7	1,350	0.031	1,023,624	23.50
23.5	3.6	1,314	0.030	1,024,938	23.53
23.6	3.6	1,296	0.030	1,026,234	23.56
23.7	3.5	1,278	0.029	1,027,512	23.59
23.8	3.5	1,260	0.029	1,028,772	23.62
23.9	3.4	1,242	0.029	1,030,014	23.65
24	3.3	1,206	0.028	1,031,220	23.67
24.1	3.2	1,170	0.027	1,032,390	23.70
24.2	3	1,116	0.026	1,033,506	23.73
24.3	2.6	1,008	0.023	1,034,514	23.75
24.4	2	828	0.019	1,035,342	23.77
24.5	1.5	630	0.014	1,035,972	23.78

Basin 6					
Time (hr)	Q (cfs)	Incremental Volume (ft3)	Incremental Volume (ac-ft)	Cumulative Volume (ft3)	Cumulative Volume (ac-ft)
0	0	0		0	0.00
11.8	0.074	1,572	0.036	1,572	0.04
11.9	3.8	697	0.016	2,269	0.05
12	18.7	4,050	0.093	6,319	0.15
12.1	73.2	16,542	0.380	22,861	0.52
12.2	184.8	46,440	1.066	69,301	1.59
12.3	258.8	79,848	1.833	149,149	3.42
12.34	262.5	37,534	0.862	186,683	4.29
12.4	244.1	54,713	1.256	241,395	5.54
12.5	189	77,958	1.790	319,353	7.33
12.6	146	60,300	1.384	379,653	8.72
12.7	114.2	46,836	1.075	426,489	9.79
12.8	90.6	36,864	0.846	463,353	10.64
12.9	73.8	29,592	0.679	492,945	11.32
13	62.4	24,516	0.563	517,461	11.88
13.1	53.7	20,898	0.480	538,359	12.36
13.2	46.4	18,018	0.414	556,377	12.77
13.3	40.2	15,588	0.358	571,965	13.13
13.4	35.6	13,644	0.313	585,609	13.44
13.5	31.8	12,132	0.279	597,741	13.72
13.6	28.5	10,854	0.249	608,595	13.97
13.7	25.5	9,720	0.223	618,315	14.19
13.8	23.1	8,748	0.201	627,063	14.40
13.9	21.3	7,992	0.183	635,055	14.58
14	20.1	7,452	0.171	642,507	14.75
14.1	19.1	7,056	0.162	649,563	14.91
14.2	18.3	6,732	0.155	656,295	15.07
14.3	17.5	6,444	0.148	662,739	15.21
14.4	16.8	6,174	0.142	668,913	15.36
14.5	16.1	5,922	0.136	674,835	15.49
14.6	15.4	5,670	0.130	680,505	15.62
14.7	14.6	5,400	0.124	685,905	15.75
14.8	13.9	5,130	0.118	691,035	15.86
14.9	13.2	4,878	0.112	695,913	15.98
15	12.5	4,626	0.106	700,539	16.08
15.1	11.8	4,374	0.100	704,913	16.18
15.2	11.1	4,122	0.095	709,035	16.28
15.3	10.5	3,888	0.089	712,923	16.37
15.4	10.1	3,708	0.085	716,631	16.45
15.5	9.8	3,582	0.082	720,213	16.53
15.6	9.5	3,474	0.080	723,687	16.61
15.7	9.3	3,384	0.078	727,071	16.69
15.8	9.2	3,330	0.076	730,401	16.77
15.9	9	3,276	0.075	733,677	16.84
16	8.8	3,204	0.074	736,881	16.92
16.1	8.6	3,132	0.072	740,013	16.99
16.2	8.5	3,078	0.071	743,091	17.06
16.3	8.3	3,024	0.069	746,115	17.13
16.4	8.1	2,952	0.068	749,067	17.20
16.5	8	2,898	0.067	751,965	17.26
16.6	7.8	2,844	0.065	754,809	17.33
16.7	7.6	2,772	0.064	757,581	17.39
16.8	7.5	2,718	0.062	760,299	17.45
16.9	7.3	2,664	0.061	762,963	17.52
17	7.1	2,592	0.060	765,555	17.57
17.1	6.9	2,520	0.058	768,075	17.63
17.2	6.8	2,466	0.057	770,541	17.69
17.3	6.6	2,412	0.055	772,953	17.74
17.4	6.4	2,340	0.054	775,293	17.80
17.5	6.3	2,286	0.052	777,579	17.85
17.6	6.1	2,232	0.051	779,811	17.90
17.7	5.9	2,160	0.050	781,971	17.95
17.8	5.7	2,088	0.048	784,059	18.00
17.9	5.6	2,034	0.047	786,093	18.05
18	5.4	1,980	0.045	788,073	18.09
18.1	5.2	1,908	0.044	789,981	18.14
18.2	5	1,836	0.042	791,817	18.18
18.3	4.9	1,782	0.041	793,599	18.22
18.4	4.8	1,746	0.040	795,345	18.26
18.5	4.7	1,710	0.039	797,055	18.30
18.6	4.7	1,692	0.039	798,747	18.34
18.7	4.6	1,674	0.038	800,421	18.38

18.8	4.5	1,638	0.038	802,059	18.41
18.9	4.5	1,620	0.037	803,679	18.45
19	4.5	1,620	0.037	805,299	18.49
19.1	4.4	1,602	0.037	806,901	18.52
19.2	4.4	1,584	0.036	808,485	18.56
19.3	4.3	1,566	0.036	810,051	18.60
19.4	4.3	1,548	0.036	811,599	18.63
19.5	4.3	1,548	0.036	813,147	18.67
19.6	4.2	1,530	0.035	814,677	18.70
19.7	4.2	1,512	0.035	816,189	18.74
19.8	4.1	1,494	0.034	817,683	18.77
19.9	4.1	1,476	0.034	819,159	18.81
20	4	1,458	0.033	820,617	18.84
20.1	4	1,440	0.033	822,057	18.87
20.2	3.9	1,422	0.033	823,479	18.90
20.3	3.9	1,404	0.032	824,883	18.94
20.4	3.9	1,404	0.032	826,287	18.97
20.5	3.8	1,386	0.032	827,673	19.00
20.6	3.8	1,368	0.031	829,041	19.03
20.7	3.7	1,350	0.031	830,391	19.06
20.8	3.7	1,332	0.031	831,723	19.09
20.9	3.6	1,314	0.030	833,037	19.12
21	3.6	1,296	0.030	834,333	19.15
21.1	3.5	1,278	0.029	835,611	19.18
21.2	3.5	1,260	0.029	836,871	19.21
21.3	3.5	1,260	0.029	838,131	19.24
21.4	3.4	1,242	0.029	839,373	19.27
21.5	3.4	1,224	0.028	840,597	19.30
21.6	3.3	1,206	0.028	841,803	19.33
21.7	3.3	1,188	0.027	842,991	19.35
21.8	3.2	1,170	0.027	844,161	19.38
21.9	3.2	1,152	0.026	845,313	19.41
22	3.1	1,134	0.026	846,447	19.43
22.1	3.1	1,116	0.026	847,563	19.46
22.2	3.1	1,116	0.026	848,679	19.48
22.3	3	1,098	0.025	849,777	19.51
22.4	3	1,080	0.025	850,857	19.53
22.5	2.9	1,062	0.024	851,919	19.56
22.6	2.9	1,044	0.024	852,963	19.58
22.7	2.8	1,026	0.024	853,989	19.60
22.8	2.8	1,008	0.023	854,997	19.63
22.9	2.7	990	0.023	855,987	19.65
23	2.7	972	0.022	856,959	19.67
23.1	2.6	954	0.022	857,913	19.69
23.2	2.6	936	0.021	858,849	19.72
23.3	2.6	936	0.021	859,785	19.74
23.4	2.5	918	0.021	860,703	19.76
23.5	2.5	900	0.021	861,603	19.78
23.6	2.4	882	0.020	862,485	19.80
23.7	2.4	864	0.020	863,349	19.82
23.8	2.3	846	0.019	864,195	19.84
23.9	2.3	828	0.019	865,023	19.86
24	2.2	810	0.019	865,833	19.88
24.1	2.1	774	0.018	866,607	19.89
24.2	1.6	666	0.015	867,273	19.91
24.3	1	468	0.011	867,741	19.92
24.4	0.5	270	0.006	868,011	19.93
24.5	0	90	0.002	868,101	19.93

Appendix B: Approach B Drawdown Calculations

Drawdown Reports (Approach B)



Summary Results for Reservoir "Basin2-3"


Project: Drawdown Simulation Run: Run 1
 Reservoir: Basin2-3



Start of Run: 01Jan2018, 00:00 Basin Model: Drawdown
 End of Run: 10Jan2018, 00:00 Meteorologic Model: Met 1
 Compute Time: 15Nov2018, 09:19:35 Control Specifications: Control 1



Volume Units: IN AC-FT



Computed Results

Peak Inflow:	0.0 (CFS)	Date/Time of Peak Inflow:	01Jan2018, 00:00
Peak Discharge:	1.3 (CFS)	Date/Time of Peak Discharge:	01Jan2018, 00:00
Inflow Volume:	n/a	Peak Storage:	4.2 (AC-FT)
Discharge Volume:	n/a	Peak Elevation:	5277.0 (FT)









Elevation-Volume Input Tables

Basin 1	
Elevation	Area (ft)
5354	61390
5356	69503
5358	77805
5360	86297
5362	94978
5364	103848
5366	112909
5367	117452
5368	134446
5370	151750

FB

Basin 2-3	
Elevation	Area (ft)
5264	4541
5266	7163
5268	9980
5270	12995
5272	16206
5274	19613
5276	23218
5277	25093
5278	35896
5280	40168

FB

Basin 4	
Elevation	Area (ft)
5040	61959
5042	68576
5044	75383
5046	82381
5048	89570
5050	96949
5052	104519
5053	108456
5054	
5056	

FB

Basin 5	
Elevation	Area (ft)
4944	45668
4946	52177
4948	58884
4950	65788
4952	72888
4954	80185
4956	87679
4957	91749
4958	100949

FB

Basin 6	
Elevation	Area (ft)
4984	37800
4986	44674
4988	51743
4990	59007
4992	66465
4994	74118
4996	81967
4997	85296
4998	99762
5000	107289

FB

Elevation	Area (ac)	Vol. (ac-ft)
5354	1.40932	0
5356	1.595569	3.0048898
5358	1.786157	6.3866162
5360	1.981107	10.15388
5362	2.180395	14.315381
5364	2.384022	18.879798
5366	2.592034	23.855854
5367	2.696327	26.500034
5368	3.086455	29.391426
5370	3.483701	35.961582

Elevation	Area (ac)	Vol. (ac-ft)
5264	0.104247	0
5266	0.16444	0.2686869
5268	0.229109	0.662236
5270	0.298324	1.1896694
5272	0.372039	1.8600321
5274	0.450253	2.6823232
5276	0.533012	3.6655877
5277	0.576056	4.2201217
5278	0.824059	4.9201791
5280	0.922213	6.6663682

Elevation	Area (ac)	Vol. (ac-ft)
5040	1.422383	0
5042	1.574288	2.9966713
5044	1.730556	6.3015152
5046	1.891208	9.9232782
5048	2.056244	13.87073
5050	2.225643	18.152617
5052	2.399426	22.777686
5053	2.489807	25.222303

Elevation	Area (ac)	Vol. (ac-ft)
4944	1.048393	0
4946	1.197819	2.24621212
4948	1.351791	4.79582185
4950	1.510285	7.65789715
4952	1.673278	10.8414601
4954	1.840794	14.3555326
4956	2.012833	18.2091598
4957	2.106267	20.2687098

Elevation	Area (ac)	Vol. (ac-ft)
4984	1	0
4986	1.025574	2.0255739
4988	1.187856	4.2390037
4990	1.354614	6.7814738
4992	1.525826	9.6619146
4994	1.701515	12.889256
4996	1.881703	16.472475
4997	1.958127	18.39239

Appendix C: Spillway

Auxiliary Spillway Design Precipitation Calculations

TR-60 Requirements
PMP depths modified per Jensen (USUL, USUS)

Pond 1 Class: High Option: Full Embankment (Above Grade)
6-Hour 24-hour 72-hour

PMP	5.04 inches	P100	3.1 inches	PMP	10.87 inches
		PMP	9.14 inches		
SDH	3.6044 inches	SDH	4.6704 inches	SDH	5.1202 inches
FBH	5.04 inches	FBH	9.14 inches	FBH	10.87 inches

Pond 2 Class: High Option: Full Embankment (Above Grade)
6-Hour 24-hour 72-hour

PMP	5.37 inches	P100	3.09 inches	PMP	10.96 inches
		PMP	9.22 inches		
SDH	3.6828 inches	SDH	4.6838 inches	SDH	5.1362 inches
FBH	5.37 inches	FBH	9.22 inches	FBH	10.96 inches

Pond 3 Class: High Option: Full Embankment (Above Grade)
6-Hour 24-hour 72-hour

PMP	5.39 inches	P100	3.03 inches	PMP	10.99 inches
		PMP	9.25 inches		
SDH	3.6436 inches	SDH	4.6472 inches	SDH	5.0996 inches
FBH	5.39 inches	FBH	9.25 inches	FBH	10.99 inches

Pond 4 Class: High Option: Full Embankment (Above Grade)
6-Hour 24-hour 72-hour

PMP	5.1 inches	P100	3.06 inches	PMP	10.88 inches
		PMP	9.15 inches		
SDH	3.5904 inches	SDH	4.6434 inches	SDH	5.0932 inches
FBH	5.1 inches	FBH	9.15 inches	FBH	10.88 inches

Pond 5 Class: High Option: Full Embankment (Above Grade)
6-Hour 24-hour 72-hour

PMP	5.1 inches	P100	3.06 inches	PMP	10.87 inches
		PMP	9.14 inches		
SDH	3.5904 inches	SDH	4.6408 inches	SDH	5.0906 inches
FBH	5.1 inches	FBH	9.14 inches	FBH	10.87 inches

Pond 6 Class: High Option: Full Embankment (Above Grade)
6-Hour 24-hour 72-hour

PMP	5.23 inches	P100	3.03 inches	PMP	10.83 inches
		PMP	9.11 inches		
SDH	3.602 inches	SDH	4.6108 inches	SDH	5.058 inches
FBH	5.23 inches	FBH	9.11 inches	FBH	10.83 inches

Table 2-5 Minimum auxiliary spillway hydrologic criteria

Class of Dam	Product of storage X effective height	Existing or planned up-stream dams	Precipitation data for ¹	
			Auxiliary spillway hydrograph	Freeboard hydrograph
Low ²	less than 30,000	none	P ₁₀₀	P ₁₀₀ + 0.12(PMP - P ₁₀₀)
	greater than 30,000		P ₁₀₀ + 0.06(PMP - P ₁₀₀)	P ₁₀₀ + 0.26(PMP - P ₁₀₀)
	all	any ³	P ₁₀₀ + 0.12(PMP - P ₁₀₀)	P ₁₀₀ + 0.40(PMP - P ₁₀₀)
Significant	all	none or any	P ₁₀₀ + 0.12(PMP - P ₁₀₀)	P ₁₀₀ + 0.40(PMP - P ₁₀₀)
High	all	none or any	P ₁₀₀ + 0.26(PMP - P ₁₀₀)	PMP

¹ P₁₀₀ = Precipitation for 100-year return period. PMP = Probable maximum precipitation

² Dams involving industrial or municipal water are to use minimum criteria equivalent to that of Significant Hazard Class.

³ Applies when the upstream dam is located so that its failure could endanger the lower dam

Auxiliary Spillway Design Precipitation Calculations

TR-60 Requirements
PMP depths modified per Jensen (USUL, USUS)

Pond 1 Class: Low Less than 30,000 Option: Below Grade
6-Hour 24-hour 72-hour

PMP	5.04 inches	P100 3.1 inches	PMP	10.87 inches
		PMP 9.14 inches		
SDH	3.1 inches	SDH 3.1 inches	SDH	3.1 inches
FBH	3.3328 inches	FBH 3.8248 inches	FBH	4.0324 inches

Pond 1 Principal 100yr 10day 5.96

Earth	Vegitated		
P50	P25	100yr 1 day	3.1
2.83	2.55 24hr		
5.41	4.16 10 day		

Pond 2 Class: Low Less than 30,000 Option: Below Grade
6-Hour 24-hour 72-hour

PMP	5.37 inches	P100 3.09 inches	PMP	10.96 inches
		PMP 9.22 inches		
SDH	3.09 inches	SDH 3.09 inches	SDH	3.09 inches
FBH	3.3636 inches	FBH 3.8256 inches	FBH	4.0344 inches

Pond 2 Principal 100yr 10day 5.82

Earth	Vegitated		
P50	P25	100yr 1 day	3.09
2.81	2.54 24hr		
5.28	4.75 10 day		

Pond 3 Class: Low Less than 30,000 Option: Below Grade
6-Hour 24-hour 72-hour

PMP	5.39 inches	P100 3.03 inches	PMP	10.99 inches
		PMP 9.25 inches		
SDH	3.03 inches	SDH 3.03 inches	SDH	3.03 inches
FBH	3.3132 inches	FBH 3.7764 inches	FBH	3.9852 inches

Pond 3 Principal 100yr 10day 5.57

Earth	Vegitated		
P50	P25	100yr 1 day	3.03
2.76	2.49 24hr		
5.06	4.56 10 day		

Pond 4 Class: Low Less than 30,000 Option: Below Grade
6-Hour 24-hour 72-hour

PMP	5.1 inches	P100 3.06 inches	PMP	10.88 inches
		PMP 9.15 inches		
SDH	3.06 inches	SDH 3.06 inches	SDH	3.06 inches
FBH	3.3048 inches	FBH 3.7908 inches	FBH	3.9984 inches

Pond 4 Principal 100yr 10day 5.81

Earth	Vegitated		
P50	P25	100yr 1 day	3.06
2.79	2.52 24hr		
5.27	4.74 10 day		

Pond 5 Class: Low Less than 30,000 Option: Below Grade
6-Hour 24-hour 72-hour

PMP	5.1 inches	P100 3.06 inches	PMP	10.87 inches
		PMP 9.14 inches		
SDH	3.06 inches	SDH 3.06 inches	SDH	3.06 inches
FBH	3.3048 inches	FBH 3.7896 inches	FBH	3.9972 inches

Pond 5 Principal 100yr 10day 5.81

Earth	Vegitated		
P50	P25	100yr 1 day	3.06
2.79	2.52 24hr		
5.27	4.74 10 day		

Pond 6 Class: Low Less than 30,000 Option: Below Grade
6-Hour 24-hour 72-hour

PMP	5.23 inches	P100 3.03 inches	PMP	10.83 inches
		PMP 9.11 inches		
SDH	3.03 inches	SDH 3.03 inches	SDH	3.03 inches
FBH	3.294 inches	FBH 3.7596 inches	FBH	3.966 inches

Pond 6 Principal 100yr 10day 5.78

Earth	Vegitated		
P50	P25	100yr 1 day	3.03
2.76	2.49 24hr		
5.24	4.72 10 day		

Table 2-5 Minimum auxiliary spillway hydrologic criteria

Class of Dam	Product of storage X effective height	Existing or planned upstream dams	Precipitation data for ¹	
			Auxiliary spillway hydrograph	Freeboard hydrograph
Low ²	less than 30,000	none	P ₁₀₀	P ₁₀₀ + 0.12(PMP - P ₁₀₀)
	greater than 30,000		P ₁₀₀ + 0.06(PMP - P ₁₀₀)	P ₁₀₀ + 0.26(PMP - P ₁₀₀)
	all	any ³	P ₁₀₀ + 0.12(PMP - P ₁₀₀)	P ₁₀₀ + 0.40(PMP - P ₁₀₀)
Significant	all	none or any	P ₁₀₀ + 0.12(PMP - P ₁₀₀)	P ₁₀₀ + 0.40(PMP - P ₁₀₀)
High	all	none or any	P ₁₀₀ + 0.26(PMP - P ₁₀₀)	PMP

¹ P₁₀₀ = Precipitation for 100-year return period. PMP = Probable maximum precipitation
² Dams involving industrial or municipal water are to use minimum criteria equivalent to that of Significant Hazard Class.
³ Applies when the upstream dam is located so that its failure could endanger the lower dam

Earth Dams and Reservoirs

Table 2-2 Minimum principal spillway hydrologic criteria

Class of dam	Purpose of dam	Product of storage X effective height	Existing or planned upstream dams	Precipitation data for maximum frequency of use of auxiliary spillway types: ^{1/}	
				Earth	Vegitated
Low	single irrigation only ^{2/}	less than 30,000	none	1/2 design life	1/2 design life
		greater than 30,000		3/4 design life	3/4 design life
	single or multiple ^{4/}	less than 30,000	none	P ₅₀	P ₂₅ ^{3/}
	greater than 30,000	1/2 (P ₅₀ + P ₁₀₀)		1/2 (P ₂₅ + P ₅₀)	
		all	any ^{5/}	P ₁₀₀	P ₅₀
Significant	single or multiple	all	none or any	P ₁₀₀	P ₅₀
High	single or multiple	all	none or any	P ₁₀₀	P ₁₀₀

¹ Precipitation amounts by return period in years. In some areas, direct runoff amounts determined by figure 2-1 and 2-2 or procedures in chapter 21, NEH-4 should be used in lieu of precipitation data.


² Applies to irrigation dams on ephemeral streams in areas where the annual rainfall is less the 25 inches.

³ The minimum criteria are to be increased from P₂₅ to P₁₀₀ for a ramp spillway.

⁴ Low Hazard Class dams involving industrial or municipal water are to be designed with a minimum criteria equivalent to that of Significant Hazard Class.

⁵ Applies when the upstream dam is located so that its failure could endanger the lower dam.

Appendix D: Pre and Post Velocity and Flood Depth Maps



2-Yr Existing Condition			
Depth (ft)	0.5-1	1-3	3+
Number of buildings	1	0	0
Length of road (ft)	0	0	0

Legend	
Flow Depth (ft)	
0.00 - 0.50	■
0.51 - 1.00	■
1.01 - 3.00	■
3.01 +	■
City Boundary	

1,500 750 0 1,500 Feet


Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horrors\Mxd\FLO-2D\Existing 2-yr.mxd, 8/29/2018 8:57:42 AM, abbk



2-Yr Existing Condition

DATE
8/29/2018
DRAWN



2-Yr Existing Condition		
Velocity x Depth (ft ² /s)	4-15	15+
Number of buildings	0	0
Length of road (ft)	0	0

Legend

Velocity x Depth*

- 0.00 - 4.00
- 4.01 - 15.00
- 15.01 +
- City Boundary

* Combinations of depth (in feet) and velocity (in fps) can be used as indicators of risk. Products of 4 or greater have been used as a limit for "people safety" and values of 15 or 20 for "structural safety".


Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horrors\Mxd\FLO-2D\Existing 2-yr.mxd, 8/29/2018 8:45:21 AM, abbk



2-Yr Existing Condition

DATE	8/29/2018
DRAWN	




5-Yr Existing Condition			
Depth (ft)	0.5-1	1-3	3+
Number of buildings	17	9	0
Length of road (ft)	818	33	0

Legend

Flow Depth (ft)

- 0.00 - 0.50
- 0.51 - 1.00
- 1.01 - 3.00
- 3.01 +
- City Boundary




Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horo\csk\Map\FLO-2D\Existing 5-yr.mxd, 8/29/2018 8:46:20 AM, abbk



5-Yr Existing Condition

DATE	8/29/2018
DRAWN	



5-Yr Existing Condition		
Velocity x Depth (ft ² /s)	4-15	15+
Number of buildings	5	0
Length of road (ft)	20	0

Legend	
Velocity x Depth*	
	0.00 - 4.00
	4.01 - 15.00
	15.01 +
	City Boundary

* Combinations of depth (in feet) and velocity (in fps) can be used as indicators of risk. Products of 4 or greater have been used as a limit for "people safety" and values of 15 or 20 for "structural safety".


Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin_Debriis_Basin_Plan_EAR\Project_Data\GIS\Horrors\Mxd\FLO-2D\Existing_5yr.mxd, 8/29/2018 8:34:34 AM, abbk



5-Yr Existing Condition

DATE	8/29/2018
DRAWN	



25-Yr Existing Condition

Depth (ft)	0.5-1	1-3	3+
Number of buildings	30	20	1
Length of road (ft)	3342	180	10

Legend

Flow Depth (ft)

- 0.00 - 0.50
- 0.51 - 1.00
- 1.01 - 3.00
- 3.01 +
- City Boundary

Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community


C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horrcock\Mxd\FLO-2D\Existing 25-yr.mxd, 8/29/2018 8:39:35 AM, abbk



25-Yr Existing Condition

DATE
8/29/2018

DRAWN



25-Yr Existing Condition

Velocity x Depth (ft ² /s)	4-15	15+
Number of buildings	14	2
Length of road (ft)	703.7	24

Legend

Velocity x Depth*

- 0.00 - 4.00
- 4.01 - 15.00
- 15.01 +
- City Boundary

* Combinations of depth (in feet) and velocity (in fps) can be used as indicators of risk. Products of 4 or greater have been used as a limit for "people safety" and values of 15 or 20 for "structural safety".


Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horrocks\Mxd\FLO-2D\Existing 25-yr.mxd, 8/29/2018 8:43:00 AM, abbk




25-Yr Existing Condition

DATE	8/29/2018
DRAWN	



50-Yr Existing Condition			
Depth (ft)	0.5-1	1-3	3+
Number of buildings	30	20	1
Length of road (ft)	4036	78	42

Legend	
Flow Depth (ft)	
0.00 - 0.50	■
0.51 - 1.00	■
1.01 - 3.00	■
3.01 +	■
City Boundary	




Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horrcock\Mxd\FLO-2D\Existing 50-yr.mxd, 8/29/2018 8:59:08 AM, abbk



50-Yr Existing Condition

DATE	8/29/2018
DRAWN	



50-Yr Existing Condition

Velocity x Depth (ft ² /s)	4-15	15+
Number of buildings	16	1
Length of road (ft)	1201	44

Legend

Velocity x Depth*

- 0.00 - 4.00
- 4.01 - 15.00
- 15.01 +
- City Boundary

* Combinations of depth (in feet) and velocity (in fps) can be used as indicators of risk. Products of 4 or greater have been used as a limit for "people safety" and values of 15 or 20 for "structural safety".


Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horrcock\Mxd\FLO-2D\Existing 50-yr.mxd, 8/29/2018 8:50:03 AM, abbk



50-Yr Existing Condition

DATE
8/29/2018
DRAWN



100-Yr Existing Condition			
Depth (ft)	0.5-1	1-3	3+
Number of buildings	52	25	2
Length of road (ft)	4892	361	20

Legend

Flow Depth (ft)

- 0.00 - 0.50
- 0.51 - 1.00
- 1.01 - 3.00
- 3.01 +
- City Boundary

1,500 750 0 1,500 Feet

Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community




100-Yr Existing Condition

DATE
8/29/2018

DRAWN


C:\2018\UT-1024-1801_Santaquin_Debriis_Basin_Plan_EAP\Project_Data\GIS\Horrcock\Mxd\FLO-2D\Existing_100-yr.mxd, 8/29/2018 8:55:40 AM, abik



100-Yr Existing Condition		
Velocity x Depth (ft ² /s)	4-15	15+
Number of buildings	16	1
Length of road (ft)	1722	74

Legend	
Velocity x Depth*	
■	0.00 - 4.00
■	4.01 - 15.00
■	15.01 +
	City Boundary

* Combinations of depth (in feet) and velocity (in fps) can be used as indicators of risk. Products of 4 or greater have been used as a limit for "people safety" and values of 15 or 20 for "structural safety".




Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horrcock\Mxd\FLO-2D\Existing 100-yr.mxd, 8/29/2018 8:53:50 AM, abik



100-Yr Existing Condition

DATE
8/29/2018
DRAWN



200-Yr Existing Condition			
Depth (ft)	0.5-1	1-3	3+
Number of buildings	62	34	2
Length of road (ft)	6657	158	40

Legend	
Flow Depth (ft)	
■	0.00 - 0.50
■	0.51 - 1.00
■	1.01 - 3.00
■	3.01 +
	City Boundary

Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community


C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horricks\Mxd\FLO-2D\Existing 200-yr.mxd, 8/29/2018 9:05:54 AM, abik



200-Yr Existing Condition

DATE
8/29/2018

DRAWN



200-Yr Existing Condition		
Velocity x Depth (ft ² /s)	4-15	15+
Number of buildings	61	0
Length of road (ft)	5759	0

Legend	
Velocity x Depth*	
0.00 - 4.00	
4.01 - 15.00	
15.01 +	
City Boundary	

* Combinations of depth (in feet) and velocity (in fps) can be used as indicators of risk. Products of 4 or greater have been used as a limit for "people safety" and values of 15 or 20 for "structural safety".


Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horrocks\Mxd\FLO-2D\Existing 200-yr.mxd, 8/29/2018 9:02:29 AM, abik



200-Yr Existing Condition

DATE
8/29/2018
DRAWN



500-Yr Existing Condition			
Depth (ft)	0.5-1	1-3	3+
Number of buildings	72	38	3
Length of road (ft)	7886	548	55

Legend

Flow Depth (ft)

- 0.00 - 0.50
- 0.51 - 1.00
- 1.01 - 3.00
- 3.01 +
- City Boundary

1,500 750 0 1,500 Feet


Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community



500-Yr Existing Condition

DATE	8/29/2018
DRAWN	

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horrcock\Mxd\FLO-2D\Existing 500-yr.mxd, 8/29/2018 9:11:29 AM, abik



500-Yr Existing Condition		
Velocity x Depth (ft ² /s)	4-15	15+
Number of buildings	32	0
Length of road (ft)	1567	0

Legend	
Velocity x Depth*	
0.00 - 4.00	
4.01 - 15.00	
15.01 +	
City Boundary	

* Combinations of depth (in feet) and velocity (in fps) can be used as indicators of risk. Products of 4 or greater have been used as a limit for "people safety" and values of 15 or 20 for "structural safety".

Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horrcock\Mxd\FLO-2D\Existing 500-yr.mxd, 8/29/2018 9:13:48 AM, abik



500-Yr Existing Condition

DATE	8/29/2018
DRAWN	




2, 5, 25, 50, 100-Yr Proposed Condition A			
Depth (ft)	0.5-1	1-3	3+
Number of buildings	0	0	0
Length of road (ft)	0	0	0

Legend

Flow Depth (ft)

- 0.00 - 0.50
- 0.51 - 1.00
- 1.01 - 3.00
- 3.01 +

- City Boundary
- Basin Locations
- Conduit Network



Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community


C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horo\ck\Wk\FLO-2D\post_100-yr.mxd, 9/14/2018 5:46:48 PM, abbk



2, 5, 25, 50 100-Yr Proposed Condition A

DATE
9/14/2018

DRAWN



2, 5, 25, 50, 100-Yr Proposed Condition A		
Velocity x Depth (ft ² /s)	4-15	15+
Number of buildings	0	0
Length of road (ft)	0	0

Legend

Velocity x Depth*

- 0.00 - 4.00
- 4.01 - 15.00
- 15.01 +
- City Boundary
- Basin Locations
- Conduit Network

* Combinations of depth (in feet) and velocity (in fps) can be used as indicators of risk. Products of 4 or greater have been used as a limit for "people safety" and values of 15 or 20 for "structural safety".


Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horrors\Mxd\FLO-2D\post 100-yr.mxd, 9/14/2018 5:48:05 PM, abk



2, 5, 25, 50 100-Yr Proposed Condition A

DATE	9/14/2018
DRAWN	



200-Yr Proposed Condition A			
Depth (ft)	0.5-1	1-3	3+
Number of buildings	9	4	0
Length of road (ft)	1047	20	10

Legend

Flow Depth (ft)

- 0.00 - 0.50
- 0.51 - 1.00
- 1.01 - 3.00
- 3.01 +

- City Boundary
- Basin Locations
- Conduit Network


Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horo\csl\Mxd\FLO-2D\post 200-yr.mxd, 9/14/2018 5:19:01 PM, abbk



200-Yr Proposed Condition A

DATE	9/14/2018
DRAWN	



200-Yr Proposed Condition A		
Velocity x Depth (ft ² /s)	4-15	15+
Number of buildings	2	0
Length of road (ft)	61	0

Legend

Velocity x Depth*

- 0.00 - 4.00
- 4.01 - 15.00
- 15.01 +
- City Boundary
- Basin Locations
- Conduit Network

* Combinations of depth (in feet) and velocity (in fps) can be used as indicators of risk. Products of 4 or greater have been used as a limit for "people safety" and values of 15 or 20 for "structural safety".

Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horo\csk\Mxd\FLO-2D\post 200-yr.mxd, 9/14/2018 5:21:02 PM, abk



200-Yr Proposed Condition A

DATE	9/14/2018
DRAWN	



500-Yr Proposed Condition A			
Depth (ft)	0.5-1	1-3	3+
Number of buildings	47	20	3
Length of road (ft)	5890	201	0

Legend

Flow Depth (ft)

- 0.00 - 0.50
- 0.51 - 1.00
- 1.01 - 3.00
- 3.01 +

- City Boundary
- Basin Locations
- Conduit Network

1,500 750 0 1,500 Feet

Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horo\csk\Mxd\FLO-2D\post 500-yr.mxd, 9/14/2018 5:54:11 PM, abkik



500-Yr Proposed Condition A

DATE	9/14/2018
DRAWN	




500-Yr Proposed Condition A		
Velocity x Depth (ft ² /s)	4-15	15+
Number of buildings	12	1
Length of road (ft)	2983	70

Legend

Velocity x Depth*

- 0.00 - 4.00
- 4.01 - 15.00
- 15.01 +
- City Boundary
- Basin Locations
- Conduit Network

* Combinations of depth (in feet) and velocity (in fps) can be used as indicators of risk. Products of 4 or greater have been used as a limit for "people safety" and values of 15 or 20 for "structural safety".



Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community




500-Yr Proposed Condition A

DATE
9/14/2018

DRAWN

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horo\csk\Mxd\FLO-2D\post 500-yr.mxd, 9/14/2018 5:52:43 PM, abbk



100-Yr Proposed Condition B			
Depth (ft)	0.5-1	1-3	3+
Number of buildings	16	6	0
Length of road (ft)	113	157	0

Legend

Flow Depth (ft)

- 0.00 - 0.50
- 0.51 - 1.00
- 1.01 - 3.00
- 3.01 +
- City Boundary
- Basin Locations


C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horo\ck\Wkd\FLO-2D\post-no overflow_100-yr.mxd, 8/29/2018 10:51:20 AM, abbk

Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community



100-Yr Proposed Condition B


DATE	8/29/2018
DRAWN	



100-Yr Proposed Condition B		
Velocity x Depth (ft ² /s)	4-15	15+
Number of buildings	0	0
Length of road (ft)	0	0

Legend	
Velocity x Depth*	
	0.00 - 4.00
	4.01 - 15.00
	15.01 +
	City Boundary
	Basin Locations

* Combinations of depth (in feet) and velocity (in fps) can be used as indicators of risk. Products of 4 or greater have been used as a limit for "people safety" and values of 15 or 20 for "structural safety".




Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horrocks\Wkd\FLO-2D\post-no overflow_100-yr.mxd, 8/29/2018 10:50:12 AM, abbk



100-Yr Proposed Condition B

DATE	8/29/2018
DRAWN	



200-Yr Proposed Condition B			
Depth (ft)	0.5-1	1-3	3+
Number of buildings	36	20	1
Length of road (ft)	2982	118	0

Legend

Flow Depth (ft)

- 0.00 - 0.50
- 0.51 - 1.00
- 1.01 - 3.00
- 3.01 +
- City Boundary
- Basin Locations

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horricks\Wkd\FLO-2D\post no outfall\200-yr.mxd, 8/29/2018 10:53:00 AM, abbk

Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community



200-Yr Proposed Condition B

DATE
8/29/2018

DRAWN



200-Yr Proposed Condition B		
Velocity x Depth (ft ² /s)	4-15	15+
Number of buildings	6	0
Length of road (ft)	1064	0

Legend	
Velocity x Depth*	
	0.00 - 4.00
	4.01 - 15.00
	15.01 +
	City Boundary
	Basin Locations

* Combinations of depth (in feet) and velocity (in fps) can be used as indicators of risk. Products of 4 or greater have been used as a limit for "people safety" and values of 15 or 20 for "structural safety".

1,500 750 0 1,500 Feet


Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horricks\Wkd\FLO-2D\post no outfall 200-yr.mxd, 8/29/2018 10:55:46 AM, abbk



200-Yr Proposed Condition B

DATE	8/29/2018
DRAWN	



500-Yr Proposed Condition B			
Depth (ft)	0.5-1	1-3	3+
Number of buildings	73	33	3
Length of road (ft)	6688	1703	0

Legend	
Flow Depth (ft)	
	0.00 - 0.50
	0.51 - 1.00
	1.01 - 3.00
	3.01 +
	City Boundary
	Basin Locations


C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horo\ck\Wkd\FLO-2D\post-no overflow\500-yr.mxd, 8/29/2018 10:18:16 AM, abbk

Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community



500-Yr Proposed Condition B

DATE
8/29/2018
DRAWN



500-Yr Proposed Condition B		
Velocity x Depth (ft ² /s)	4-15	15+
Number of buildings	22	2
Length of road (ft)	4345	1010

Legend	
Velocity x Depth*	
	0.00 - 4.00
	4.01 - 15.00
	15.01 +
	City Boundary
	Basin Locations

* Combinations of depth (in feet) and velocity (in fps) can be used as indicators of risk. Products of 4 or greater have been used as a limit for "people safety" and values of 15 or 20 for "structural safety".

Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horricks\Wdr\FLO-2D\post-no overflow\500-yr.mxd, 8/29/2018 10:17:11 AM, abbk



500-Yr Proposed Condition B

DATE
8/29/2018
DRAWN

Appendix E: Induced Flooding Maps

Induced flooding locations are indicated by yellow highlighted areas. The property in this area would be acquired as part of the project.



C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EA\Project Data\Design\Structures\UT-1024-1801_Design Base NEW BELOW.dwg - BASIN 1 - 10/05/2018 01:36pm .lisa

PRELIMINARY
NOT FOR CONSTRUCTION

REV	DATE	BY	DESCRIPTION

REVISIONS

SCALE
 HORIZONTAL
 1" = 150'
 VERTICAL
 N/A

WARNING
 0 1/2 1
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE




2162 West Grove Parkway
 Suite 400
 Pleasant Grove, UT 84062
 (801) 763-5100

SANTAQUIN DEBRIS BASINS
BASIN 1 - BELOW GRADE

DESIGNED	DATE	PROJECT NO.
###	###	PG-1024-1801
DRAWN	DATE	SHEET NO.
###	###	# OF #
CHECKED	DATE	DRAWING NO.
###	###	P-01

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EA\Project Data\Design\Structures\UT-1024-1801_Design Base NEW BELOW.dwg - BASIN 3A - 10/05/2018 01:37 pm. llsj



Induced flooding locations are indicated by yellow highlighted areas. The property in this area would be acquired as part of the project.

PRELIMINARY	
NOT FOR CONSTRUCTION	
REV	DATE
REVISIONS	

SCALE
HORIZONTAL
1" = 60'
VERTICAL
N/A


WARNING
 0 1/2 1
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE



2162 West Grove Parkway
 Suite 400
 Pleasant Grove, UT 84062
 (801) 763-5100

SANTAQUIN DEBRIS BASINS
BASIN 3A - BELOW GRADE (WATERSHEDS 2 & 3 COMBINED)

DESIGNED	DATE	PROJECT NO.
####	####	PG-1024-1801
DRAWN	DATE	SHEET NO.
####	####	# OF #
CHECKED	DATE	DRAWING NO.
####	####	P-05



Induced flooding locations are indicated by yellow highlighted areas. The property in this area would be acquired as part of the project.

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EA\Project Data\Design\Structures\UT-1024-1801_Design Base NEW ABOVE.dwg - BASIN 4E - 10/05/2018 01:33pm. llsj

PRELIMINARY
NOT FOR CONSTRUCTION

REV	DATE	BY	DESCRIPTION

REVISIONS

SCALE
 HORIZONTAL
 1" = 100'
 VERTICAL
 N/A


WARNING
 0 1/2 1
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE



2162 West Grove Parkway
 Suite 400
 Pleasant Grove, UT 84062
 (801) 763-5100

SANTAQUIN DEBRIS BASINS
BASIN 4E - ABOVE GRADE (WATERSHED ONLY)

DESIGNED	DATE	PROJECT NO.
###	###	PG-1024-1801
DRAWN	DATE	SHEET NO.
###	###	5 OF 12
CHECKED	DATE	DRAWING NO.
###	###	P-05



Induced flooding locations are indicated by yellow highlighted areas. The property in this area would be acquired as part of the project.

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EA\Project Data\Design\Structures\UT-1024-1801_Design Base NEW BELOW.dwg - BASIN 5 - 10/05/2018 01:39pm .lisa

PRELIMINARY
NOT FOR CONSTRUCTION

REV	DATE	BY	DESCRIPTION

REVISIONS

SCALE
 HORIZONTAL
 1" = 150'
 VERTICAL
 N/A


WARNING
 0 1/2 1
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE



2162 West Grove Parkway
 Suite 400
 Pleasant Grove, UT 84062
 (801) 763-5100

SANTAQUIN DEBRIS BASINS
BASIN 5 - BELOW GRADE

DESIGNED	DATE	PROJECT NO.
###	###	PG-1024-1801
DRAWN	DATE	SHEET NO.
###	###	# OF #
CHECKED	DATE	DRAWING NO.
###	###	P-12



Induced flooding locations are indicated by yellow highlighted areas. The property in this area would be acquired as part of the project.

C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EA\Project Data\Design\Structures\UT-1024-1801_Design Base NEW ABOVE.dwg - BASIN 6A - 10/05/2018 01:34pm. llsj

PRELIMINARY	
NOT FOR CONSTRUCTION	
REV	DATE
REVISIONS	

SCALE
HORIZONTAL
1" = 100'
VERTICAL
N/A

WARNING

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

HORROCKS
ENGINEERS


2162 West Grove Parkway
Suite 400
Pleasant Grove, UT 84062
(801) 763-5100

SANTAQUIN DEBRIS BASINS

BASIN 6A - ABOVE GRADE

DESIGNED	DATE	PROJECT NO.
####	####	PG-1024-1801
DRAWN	DATE	SHEET NO.
####	####	# OF #
CHECKED	DATE	DRAWING NO.
####	####	P-07

Appendix F: Flow Comparison Maps



Legend

- Flow Rate Comparison Lines
- Flood Extents

Section	2-Yr (cfs)		
	Existing	Proposed A	Proposed B
1	11.3	0	0
2	6.2	0	0
3	12.1	0	0
4	10	0	0
5	13.3	0	0
6	0	0	0

The existing condition flood extent is shown for reference.

AeroGRID, ICGN, and the GIS User Community


C:\2018\UT-1024-1801_Santaquin_Debris_Basin_Plan_EAP\Project_Data\GIS\Horricks\Mxd\FLO-2D\FLOW_Comparison_Map_2.mxd, 9/13/2018 7:25:54 PM, _JacobO



2-Yr Flow Rate Comparison

DATE
9/13/2018

DRAWN



Legend

- Flow Rate Comparison Lines
- Flood Extents

Section	5-Yr (cfs)		
	Existing	Proposed A	Proposed B
1	158	0	0
2	9.1	0	0
3	38.6	0	0
4	134.1	0	0
5	187.2	0	0
6	1.7	0	0

The existing condition flood extent is shown for reference.

AeroGRID, ICGN, and the GIS User Community


C:\2018\UT-1024-1801_Santaquin_Debris_Basin_Plan_EAP\Project_Data\GIS\Horricks\Mxd\FLO-2D\Flood_Comparison_Map_5.mxd, 9/13/2018 7:27:56 PM, _JacobO



5-Yr Flow Rate Comparison

DATE
9/13/2018

DRAWN



Legend

- Flow Rate Comparison Lines
- Flood Extents

Section	25-Yr (cfs)		
	Existing	Proposed A	Proposed B
1	315.2	0	0
2	71.8	0	0
3	118.7	0	0
4	277.4	0	0
5	373.7	0	0
6	20	0	0

The existing condition flood extent is shown for reference.

AeroGRID, ICN, and the GIS User Community


C:\2018\UT-1024-1801_Santaquin_Debriis Basin Plan EAP\Project Data\GIS\Horricks\Mxd\FLO-2D\FLOW Comparison Map 25.mxd, 9/13/2018 7:30:36 PM, JacobO



25-Yr Flow Rate Comparison

DATE
9/13/2018

DRAWN



Legend

- Flow Rate Comparison Lines
- Flood Extents

Section	50-Yr (cfs)		
	Existing	Proposed A	Proposed B
1	445.6	0	0
2	130.6	0	0
3	167.6	0	0
4	385.9	0	0
5	489.7	0	0
6	50	0	0

The existing condition flood extent is shown for reference.

AeroGRID, ICN, and the GIS User Community


C:\2018\UT-1024-1801_Santaquin_Debriis Basin Plan EAP\Project Data\GIS\Horricks\Mxd\FLO-2D\Flow Comparison Map 50.mxd, 9/13/2018 7:32:50 PM, JacobO



50-Yr Flow Rate Comparison

DATE
9/13/2018

DRAWN



Legend

- Flow Rate Comparison Lines
- Flood Extents

Section	100-Yr (cfs)		
	Existing	Proposed A	Proposed B
1	576.7	0	28.4
2	200.4	0	10.2
3	246.7	0	15.2
4	495.8	0	19.2
5	622.5	0	33.6
6	80.6	0	0

The existing condition flood extent is shown for reference.

AeroGRID, ICN, and the GIS User Community


C:\2018\UT-1024-1801_Santaquin_Debris_Basin_Plan_EAP\Project_Data\GIS\Horricks\Mxd\FLO-2D\Flow_Comparison_Map_100.mxd, 9/13/2018 7:21:55 PM, JacobO



100-Yr Flow Rate Comparison

DATE
9/13/2018

DRAWN



Legend

- Flow Rate Comparison Lines
- Flood Extents

Section	200-Yr (cfs)		
	Existing	Proposed A	Proposed B
1	774.5	174.4	216.2
2	284.7	0	51.8
3	341.6	84.1	85.2
4	639.4	139.3	199.6
5	831.5	94.9	244.8
6	156.1	0	8.3

The existing condition flood extent is shown for reference.


AeroGRID, ICN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin_Debris_Basin_Plan_EAP\Project_Data\GIS\Horricks\Mxd\FLO-2D\Flood_Comparison_Map_200.mxd, 9/13/2018 7:35:16 PM, JacobO



200-Yr Flow Rate Comparison

DATE 9/13/2018
DRAWN



Legend

- Flow Rate Comparison Lines
- Flood Extents

Section	500-Yr (cfs)		
	Existing	Proposed A	Proposed B
1	1107.1	505.5	657.7
2	414.6	116.3	223.5
3	499	228.8	218.1
4	929.2	444.4	475.5
5	1155.7	461.0	928.8
6	334.9	52.4	90.1

The existing condition flood extent is shown for reference.

AeroGRID, ICN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin_Debris_Basin_Plan_EAP\Project_Data\GIS\Horricks\Mxd\FLO-2D\Flood_Comparison_Map_500.mxd, 9/13/2018 7:37:44 PM, JacobO



500-Yr Flow Rate Comparison

DATE
9/13/2018

DRAWN



Appendix G: Dam Breach Hydrographs, Dam Breach Maps

Dambreach Hydrographs via TRs 60 & 66 NRCS guidance
version 3, July 2018

Input data required:


data	variable	explanation
5057	crestEL	dam crest elevation
5054	wsEL	w.s. elev at time of breach
15	TW	dam top width (feet)
3	SSup	dam side slope (upstream, SSUp:1)
3	SSdn	dam side slope (downstream, SSdn:1)
5040	floorEL	valley floor elev (see note)
25.9	Vs	resv vol at time of breach (acre-feet)
370	L	valley width at dam axis & w.s. elev (feet)
	ELwave	top of wave berm elevation
8	Wwave	width of top of wave berm feet
3	SSwave	wave berm side slope (SSwave:1)
	ELstab	top of stability berm elevation
5	Wstab	width of top of stability berm (feet)
2.5	SSstab	stability berm side slope (SSstab:1)
2	ts	timestep (minutes) for breach hydrograph



output variable		breach hydrograph	
variable	results	time (min)	Q (cfs)
T	394	0	0
(L < T)?	Y	2	2347
H _w	14	4	1424
Q ₁	8063	6	1110
(H _w < 103)?	Y	8	865
A _{wave}	0	10	674
A _{stab}	0	12	525
A	1122	14	409
Br	0	16	319
Q ₂	239	18	248
Q _{min}	2347	20	193
(Q ₂ < Q _{min})?	Y	22	151
(Q ₂ > Q ₁)?	N	24	117
(Q ₁ < Q _{min})?	N	26	91
Q _{max}	2347	28	71
		30	56
		32	43
		34	34
		36	26
		38	20
		40	16
		42	12
		44	10
		46	8
		48	6
		50	5
		52	4
		54	3
		56	2
		58	2
		60	1
		62	1
		64	1
		66	1
		68	0
		70	0
		72	0



auto-scale

Basin 4 breach hydrograph





Legend	
Flow Depth (ft)	
	0.00 - 0.50
	0.51 - 1.00
	1.01 - 3.00
	3.01 +


Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

C:\2018\UT-1024-1801_Santaquin_Debriis_Basin_Plan_EAP\Project_Data\GIS\Horricks\Mxd\LO-20\Dam_Breach\Breach_4_depth.mxd, 11/15/2018 2:41:40 PM, Jacobo




Basin 4 Dam Breach Analysis

DATE 11/15/2018
DRAWN



Legend	
Velocity (ft/s)	
	0.000 - 1.000
	1.001 - 4.000
	4.001 - 7.000
	7.001 - 10.000
	10.001 - 17.000



Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community



Basin 4 Dam Breach Analysis

DATE	11/15/2018
DRAWN	



C:\2018\UT-1024-1801_Santaquin_Dam_Breach_Analysis\Map\Basin 4 Dam Breach Analysis.mxd, 11/15/2018 2:49:35 PM, Jacobo

Dambreach Hydrographs via TRs 60 & 66 NRCS guidance
 version 3, July 2018

Input data required:


data	variable	explanation
5000	crestEL	dam crest elevation
4997	wsEL	w.s. elev at time of breach
15	TW	dam top width (feet)
3	SSup	dam side slope (upstream, SSUp:1)
3	SSdn	dam side slope (downstream, SSdn:1)
4983.5	floorEL	valley floor elev (see note)
18.6	Vs	resv vol at time of breach (acre-feet)
512	L	valley width at dam axis & w.s. elev (feet)
	ELwave	top of wave berm elevation
8	Wwave	width of top of wave berm feet
3	SSwave	wave berm side slope (SSwave:1)
	ELstab	top of stability berm elevation
5	Wstab	width of top of stability berm (feet)
2.5	SSstab	stability berm side slope (SSstab:1)
2	ts	timestep (minutes) for breach hydrograph


output variable		breach hydrograph	
variable	results	time (min)	Q (cfs)
T	389	0	0
(L < T)?	N	2	2143
H _w	13.5	4	1136
Q ₁	8017	6	827
(H _w < 103)?	Y	8	602
A _{wave}	0	10	438
A _{stab}	0	12	319
A	1064	14	232
Br	0	16	169
Q ₂	157	18	123
Q _{min}	2143	20	90
(Q ₂ < Q _{min})?	Y	22	65
(Q ₂ > Q ₁)?	N	24	48
(Q ₁ < Q _{min})?	N	26	35
Q _{max}	2143	28	25
		30	18
		32	13
		34	10
		36	7
		38	5
		40	4
		42	3
		44	2
		46	1
		48	1
		50	1
		52	1
		54	0
		56	0
		58	0
		60	0
		62	0
		64	0
		66	0
		68	0
		70	0







auto-scale

Basin 6 breach hydrograph





Legend	
Flow Depth (ft)	
	0.00 - 0.50
	0.51 - 1.00
	1.01 - 3.00
	3.01 +


Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community






C:\2018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horricks\Mxd\FLO-2D\Dam Breach\Breach 6 depth.mxd, 11/15/2018 2:56:44 PM, jacobbo



Basin 6 Dam Breach Analysis

DATE	11/15/2018
DRAWN	



Legend	
Velocity (ft/s)	
	0.000 - 1.000
	1.001 - 4.000
	4.001 - 7.000
	7.001 - 10.000
	10.001 - 17.000

C:\2018\UT-1024-1801_Santaquin_Debriis_Basin_Plan_EAP\Project_Data\GIS\Horricks\Mxd\FLO-2D\Dam_Breach\Breach_6_velocity.mxd, 11/15/2018 2:54:11 PM, JacobO

Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community



Basin 6 Dam Breach Analysis

DATE	11/15/2018
DRAWN	

Appendix H: Wave Runup Calculations

Santaquin Wave Runup Summary Sheet

Made by Mickey Navidomskis
7/10/2018

- References: (1) Albert Holler "New Information For Design of Dam Freeboard" (2005, ASDSO Dam Safety Conference)
(2) Albert Holler "Computation Of Dam Freeboard For Wind Generated Waves" (2001, ASDSO Dam Safety Conference)

Key:

Inputs	outputs	Dam attributes
--------	---------	----------------

Basin	Fetch used (maximum distance) ft	fetch used miles	Average Water Depth mph	Overland wind speed mph	Roughness	Wave Height ft	Wave Steepness	Significant Runup ft	Max Runup ft	Wind Tide Setup ft	Freeboard for average of highest 1/3 of waves - 13% could exceed ft	For maximum wave action ft	Principal Spillway elev (ft)	Auxiliary Spillway elev (ft)	Dam Crest elev (ft)	Principal Spillway elev (ft)	Auxiliary Spillway elev (ft)	100-yr Event Freeboard ft
Basin 1 Above Grade	342.6	0.0649	12	100	Grass	0.9	0.238	2.2	3.6	0.03	2.2	3.7	5407	5408.5	5411.5	5408.5	5411.5	4.5
Basin 2 Above Grade	170.2	0.0322	12	100	Grass	0.6	0.273	1.6	2.7	0.02	1.7	2.7	5316	5317	5320	5316	5320	4
Basin 3 Above Grade	148.5	0.0281	12	100	Grass	0.6	0.279	1.5	2.6	0.01	1.5	2.6	5266	5267	5270	5266	5270	4
Basin 4E Above Grade	285.7	0.0541	12	100	Grass	0.8	0.246	2	3.4	0.02	2	3.4	5052	5054	5057	5052	5057	5
Basin 4B Above Grade	337.7	0.0640	12	100	Grass	0.9	0.238	2.2	3.6	0.03	2.2	3.6	5027	5029.2	5032.2	5027	5032.2	5.2
Basin 4A Above Grade	200.1	0.0379	12	100	Grass	0.7	0.264	1.7	2.9	0.02	1.8	2.9	4997	4999.2	5002.2	4997	5002.2	5.2
Basin 5 Above Grade	366.5	0.0694	12	100	Grass	0.9	0.235	2.2	3.7	0.05	2.3	3.8	5011	5012.5	5015.5	5011	5015.5	4.5
Basin 6A Above Grade	391.8	0.0742	12	100	Grass	0.9	0.233	2.3	3.9	0.05	2.4	3.9	5021	5022.5	5025.5	5021	5025.5	4.5
Basin 6B Above Grade	329.1	0.0623	12	100	Grass	0.8	0.24	2.1	3.6	0.04	2.2	3.6	5037	5038.5	5041.5	5037	5041.5	4.5

Note: Input values assume water is at Auxiliary Spillway, overland wind is 100mph, the dam is grass lined, the longest fetch is perpendicular to the dam, and the average water depth is 12 feet

Basin	Fetch used (maximum distance) ft	fetch used miles	Average Water Depth mph	Overland wind speed mph	Roughness	Wave Height ft	Wave Steepness	Significant Runup ft	Max Runup ft	Wind Tide Setup ft	Freeboard for average of highest 1/3 of waves - 13% could exceed ft	For maximum wave action ft	100-yr Water Surface elev (ft)	Principal Spillway elev (ft)	Auxiliary Spillway elev (ft)	Dam Crest elev (ft)	Principal Spillway elev (ft)	Auxiliary Spillway elev (ft)	100-yr Event Freeboard ft
Basin 1 Above Grade	342.6	0.0649	12	50	Grass	0.4	0.189	1.1	1.8	0.01	1.1	1.8	5408.03	5407	5408.5	5408.5	5411.5	4.5	
Basin 2 Above Grade	170.2	0.0322	12	50	Grass	0.3	0.213	0.8	1.3	0	0.8	1.3	5315.48	5316	5317	5317	5320	4	
Basin 3 Above Grade	148.5	0.0281	12	50	Grass	0.3	0.218	0.7	1.2	0	0.7	1.2	5263.95	5266	5267	5266	5270	4	
Basin 4E Above Grade	285.7	0.0541	12	50	Grass	0.4	0.195	1	1.6	0.01	1	1.6	5053.99	5052	5054	5052	5057	5	
Basin 4B Above Grade	337.7	0.0640	12	50	Grass	0.4	0.19	1.1	1.8	0.01	1.1	1.8	5029.52	5027	5029.6	5029.6	5032.6	5.6	
Basin 4A Above Grade	200.1	0.0379	12	50	Grass	0.3	0.207	0.8	1.4	0.01	0.8	1.4	4999.2	4997	4999.2	4999.2	5002.2	5.2	
Basin 5 Above Grade	366.5	0.0694	12	50	Grass	0.4	0.187	1.1	1.8	0.01	1.1	1.9	5012.49	5011	5012.5	5011	5015.5	4.5	
Basin 6A Above Grade	391.8	0.0742	12	50	Grass	0.5	0.185	1.1	1.9	0.01	1.2	1.9	5022.11	5021	5022.5	5021	5025.5	4.5	
Basin 6B Above Grade	329.1	0.0623	12	50	Grass	0.4	0.191	1	1.7	0.01	1.1	1.8	5038.18	5037	5038.5	5037	5041.5	4.5	

Note: Input values assume water is at Auxiliary Spillway, overland wind is 50mph, the dam is grass lined, the longest fetch is perpendicular to the dam, and the average water depth is 12 feet

ATTACHMENT 3
SEDIMENTATION REPORT

To: Nathaniel Todea
Natural Resources Conservation Service (NRCS), USDA

From: Aaron Spencer, P.E.

Date: July 30, 2018

Technical Memo

Subject: Santaquin City Flood Control Plan-EA – Sedimentation Analysis

Project: UT-1024-1801

INTRODUCTION

Sediment transport into reservoirs and debris basins is a major design consideration, since the volume taken up by the sediment reduces the capacity of the basin, and its ability to control flood flows. Additional volume must be provided for sediment so that throughout its design life the basin will function as intended. In order to determine the required volume the sediment yield must be calculated. The NRCS normally requires that a no-maintenance design life of 50 or 100 years be considered. Other solutions may be considered if meeting the sediment demands is not reasonable or feasible, such as regular cleaning and maintenance, but such solutions must be compared to the standard requirements and be approved.

BACKGROUND AND BASIS OF DESIGN

The NRCS has performed a similar study (Todea, 2015, unpublished) on the nearby Santaquin Canyon watershed as part of its work to address any deficiencies in the existing debris basin there. It and other resources provided by the NRCS have been used as general references to guide this study, including: Technical Release No. 12, Procedure – Sediment Storage Requirements (TR-12), and Chapter 8 of the National Engineering Handbook – Sedimentation.

Due to an accelerated schedule, initial sizing of the basins for use in hydraulic analysis required some assumptions be made on the sediment volume in the proposed basins. Based on past experience it was assumed approximately 20% of the total volume was reserved for sediment. This study refines the volumes that are recommended for planning and design.

APPROACH

In order to arrive at a reasonable sediment yield and sediment pool volume for the watersheds and basins in question, multiple methodologies for calculating sediment yield were used and compared. With no stream gages or existing basins collecting sediment to compare to, this limited the ability to calibrate the estimates. The NRCS study for the nearby Santaquin Canyon was used as a general reference (Todea, 2015), and empirical hydrologic calculations using the curve number method were used to give a rough order of magnitude check on the values determined. This memo gives a brief introduction to the types of analysis performed, and summarizes the final results. Further detail on each method is provided in the method-specific attached technical memos.

ANALYSIS

The analysis included determining sediment yield using several methods, performing rough checks on the order of magnitude of the results, and selection of the most appropriate yield values based on review of the sites and the applicability of each model. The trap efficiency of the basins, which determines how much of the sediment is actually trapped in the reservoir, is then applied to the recommended yield values to determine sediment pool volume requirements based on various design life intervals.

SEDIMENT YIELD

To evaluate sediment yield several methods were employed. These included the Rangeland Hydrology and Erosion Model (RHEM), the Pacific Southwest Inter-Agency Committee (PSIAC) method, and consulting the Bridges (1973) map. Further detail on each method is provided below. There is no ready means of evaluating historical yield or to calibrate the methods used at the sites other than general observations from geological investigation. The geological and geotechnical investigation is in process, and any significant findings will be taken into consideration upon completion.

RHEM

Rangeland Hydrology and Erosion Model (RHEM) is a formula designed to estimate runoff and sediment yield. United States Department of Agriculture (USDA) provides a user friendly web tool through the Southwest Watershed Research Center, <http://dss.tucson.ars.ag.gov/rhem/>, which runs the RHEM using input parameters. The RHEM method is an adaptation of the Water Erosion Prediction Model (WEPP), and accommodates rangeland instead of croplands by modifying slope and infiltration based on land cover. The RHEM Web Tool uses storm data, soil types, land cover information, and slope as input parameters. Detailed information on the collection of input parameters for Santaquin debris basins is found in the “RHEM Technical Memo” appendix. The table below shows results produced by the RHEM Web Tool. As described in the “RHEM Technical Memo,” each basin has a lower and higher yield limit based on a range of criteria used as parameters. The RHEM tool is designed as an event based model, but annualizes the results of a range of events from 2 years to 100 years to produce a final annual average.

Table 1. RHEM Sediment Yield Results

	Basin 1		Basin 2		Basin 3		Basin 4		Basin 5		Basin 6	
	Low	High	Low	High	Low	High	Low	High	Low	High	Low	High
Sediment Yield (Ac-Ft/Sq-Mi/Yr)	0.07	0.27	0.03	0.13	0.02	0.08	0.04	0.14	0.03	0.12	0.06	0.21
Total Annual Yield (Ac-Ft)	0.05	0.17	0.002	0.01	0.001	0.01	0.024	0.08	0.024	0.08	0.026	0.10

PSIAC

In 1974 the Pacific Southwest Inter-Agency Committee (PSIAC) evaluated methods for estimating erosion and sediment yield. Ten contributing factors were identified: surface geology, soils, climate, runoff, topography, effective ground cover, land type/management quality, upland erosion, and channel erosion/sediment transport. The PSIAC Method for estimating sediment yield requires field observations and data collection for each contributing factor. Norm Evenstad with the Natural Resources Conservation Service (NRCS) provided a 1991 revision of the PSIAC procedures. Details about the use of this scale are in the “PSIAC Technical Memo” appendix. Below is a table showing the results of the PSIAC Method.

Table 2. PSIAC Sediment Yield Results

	Basin 1	Basin 2	Basin 3	Basin 4	Basin 5	Basin 6
Sediment Yield (Ac-Ft/Sq-Mi/Yr)	0.24	0.24	0.25	0.28	0.26	0.27
Total Annual Yield (Ac-Ft)	0.15	0.017	0.013	0.19	0.18	0.13

Bridges

Nathaniel Todea with NRCS provided a copy of the “Estimated Sediment Yield Rates for the State of Utah” map, also known as the 1973 Bridges map. The Bridges map was developed by the NRCS. It gives estimated yearly sediment yields per square mile of area across Utah. It is typically used for estimating sediment yield over very large areas and is not recommended for specific sites. Refer to the “Bridges Sediment Yield Map” appendix for information regarding results in the table below. The Bridges map gave a range of 0.2 to 0.5 acre-feet per square mile per year. From observation it was assumed that these watersheds would generally be on the lower end of the spectrum, so a value of 0.3 was used to prepare Table 3 below showing expected yields.

Table 3. Bridge Sediment Yield Results

	Basin 1	Basin 2	Basin 3	Basin 4	Basin 5	Basin 6
Sediment Yield (Ac-Ft/Sq-Mi-Yr)	0.3	0.3	0.3	0.3	0.3	0.3
Total Annual Yield (Ac-Ft)	.19	.02	.02	.21	.21	.14

CHECK ON RESULTS

HYDROLOGIC ORDER OF MAGNITUDE

As an order of magnitude check on the yield quantities determined above, a backcheck was performed using design storm volumes and peak flows for 24-hour storms with 1-year and 2-year recurrence intervals that were evaluated as part of the hydrology study.

Sediment concentrations of 10% were used to estimate yearly runoff values. The 1-year recurrence interval storms had such low peak flows that they were not considered representative, as they would have mobilized minimal sediment. Therefore the 2-year event was used, and then annualized. The results are shown below:

Table 4. Hydrologic Check on Magnitude

Basin	Area (sq. mi.)	Area (acres)	2-yr Runoff Volume (inches)	2-yr Runoff Volume (acre-ft)	2-yr Peak Flow (cfs)	2-yr Sediment Volume @ 10%	Yearly deposition at 10% (acre-ft)
1	0.627	401.28	0.14	4.682	12	0.47	0.234
2	0.069	44.16	0.015	0.055	0.6	0.01	0.003
3	0.053	33.92	0.021	0.059	0.9	0.01	0.003
4	0.688	440.32	0.118	4.330	8.8	0.43	0.216
5	0.711	455.04	0.067	2.540	3.1	0.25	0.127
6	0.451	288.64	0.134	3.223	9.5	0.32	0.161

This rough method of checking sediment loads is oversimplified, and therefore must be used only as a general order of magnitude check. The 2-year event peak flows are minimal, meaning that assuming the storm transports sediment equal to 10% of the event’s runoff volume may be conservative, since during most of the storm the flows would be insufficient to mobilize significant sediment. This supports observations that there are not regular flows out of these watersheds that have a significant impact, and that the majority of sediment yield occurs during more extreme, less frequent events. A “yearly” sediment load would therefore need to be an average of the yield of larger infrequent events. The values do appear to confirm the general order of magnitude of the results of the other methods.

COMPARISON STUDIES

An intensive sediment yield study was performed by the NRCS on Santaquin Canyon, the mouth of which is located one to two miles southwest of the basins under consideration. The canyon is similar in most characteristics to the basins being studied in this analysis, except that it is larger, has a continuously flowing creek, and likely has a lower average slope. The Santaquin Canyon study examined the Bridges map, RHEM tool, and PSAC just as this study has, but also included other methods such as AGWA modeling, RiverMorph, and others. There is an existing flood control and debris basin at the mouth of the canyon, and through examination of original design documentation they concluded the planned sedimentation rate for that basin was 0.12 acre-feet per square mile per year.

The unit sediment yield per square mile that they found for the Bridges map and the RHEM methods resulted in similar sediment yields as found in this study. The PSIAC results they cited were notably higher.

The study in the end recommended using the results of a RiverMorph FlowSed model, which requires input of specific flow gage data and dimensionless sediment yield parameters selected based on site specific characteristics. They concluded that a yield equivalent to 0.07 acre-feet per square mile was appropriate. This is more in line with the RHEM results than those of PSIAC or the Bridges map.

SEDIMENT YIELD CONCLUSIONS

The RHEM method was adapted from a cropland erosion prediction method for individual events, and is designed around looking at a single hillslope, not necessarily an entire watershed. But considering that these watersheds do not have continuous flows, and sediment yield is the result of the accumulation of less frequent isolated rainfall events, the comparison may be appropriate. The values generally appear to reasonably match findings in other studies in the area. Therefore the results of the RHEM models are recommended for use in this study.

Visual observations of the test pits performed in the alluvial fans below the watersheds suggest that the material being mobilized in Watersheds 1, 4, 5, and 6 is a loam with limited clay content, and significant sand, gravel, cobbles and boulders that are mobilized in isolated larger events. Watersheds 2 and 3 showed significantly less gravel and cobbles, appearing to consist of a sandy loam. The prevalence of sand, gravels, and larger materials suggest that the highest yield values from RHEM may be conservative, and that the lower values may be acceptable. To be conservative the upper values are recommended, with one exception. Basin 1 has a range of 0.07 to 0.27 ac-ft/sq.mi./yr. This is a wide range with an upper value notably higher than the other basins. The test pit below this watershed showed significant sand, gravel and cobble, suggesting that the loamy sand associated with the lower limit is likely more appropriate. PSIAC predicts a yield of 0.24 ac-ft/sq.mi./yr, or 0.15 acre-feet per year, which is recommended for use. The recommended design values are shown in Table 5 below.

Table 5. Recommended Sediment Yield Values

	Basin 1	Basin 2	Basin 3	Basin 4	Basin 5	Basin 6
Sediment Yield (Ac-Ft/Sq-Mi/Yr)	0.24	0.13	0.08	0.14	0.12	0.21
Total Annual Yield (Ac-Ft)	0.15	0.01	0.01	0.10	0.08	0.10

These values are not considered to include atypical events, such as those caused by runoff during burned conditions or debris flows, which would have to be cleaned out as they occurred.

TRAP EFFICIENCY

Debris basins are designed to remove sediment suspended in runoff flows. This “trapped” sediment is deposited in the basin. Not all of the sediment can be removed before the flows continue downstream. The quantity of sediment retained in the basin is expressed as a ratio. This ratio is known as trap efficiency. The USDA-NRCS Technical Release No. 12 “Procedure – Sediment Storage Requirements for Reservoirs” provides an outline for estimating trap efficiency. The results of the analysis are shown in the tables below. Sediment yield conclusions found using RHEM, PSIAC, and Bridges methods were used to estimate the sediment yield. Average annual precipitation was found through the USDA online application, StreamStats. Annual runoff was determined for each basin by using the Curve Number determined in the Hydrology Technical Memo. Assuming the curve number method runoff would average out and therefore apply to the average annual precipitation, inflow was found in each basin. We consider this to be a conservative assumption, since snowmelt and smaller events tend to have a greater opportunity to percolate than larger events.

With estimated debris basin capacities from the preliminary hydrology and hydraulics analysis, capacity/inflow (C/I) ratios were determined. That number is converted directly into trap efficiency using the graph provided in Technical Release No. 12 (1975, see Trap Efficiency Calculations appendix for further detail). Basins 2 and 3 used the median curve because visual site observations and gradation test results from test pit samples showed that the sediment emanating from these watersheds was finer than the others. The sediment deposits below the watersheds for Basins 1, 4, 5, and 6 were coarser, with significant gravel, cobbles and boulders. Therefore the upper curve of the trap efficiency curve in TR-12 was used, which is identified as being for highly flocculated and coarse-grained sediment.

In the table below, basin volumes required given varying design lives of 25, 50, and 100 years are shown.

Table 6. Sediment Storage and Basin Volumes

	Required Flood Capacity (ac-ft)	25 Year Design Life			
		Sediment Yield (ac-ft)	Trap Efficiency	Deposition (ac-ft)	Required Basin (ac-ft)
Basin 1	16.76	3.75	72%	2.70	19.46
Basin 2	1.34	0.25	64%	0.16	1.50
Basin 3	1.02	0.3	64%	0.16	1.18
Basin 4	15.39	2.5	79%	1.98	17.37
Basin 5	12.79	2.0	75%	1.50	14.29
Basin 6	11.98	2.5	82%	2.05	14.03

	Required Flood Capacity (ac-ft)	50 Year Design Life			
		Sediment Yield (ac-ft)	Trap Efficiency	Deposition (ac-ft)	Required Basin (ac-ft)
Basin 1	16.76	7.5	75%	5.63	22.39
Basin 2	1.34	0.5	69%	0.35	1.69
Basin 3	1.02	0.5	69%	0.35	1.37
Basin 4	15.39	5.0	80%	4.00	19.39
Basin 5	12.79	4.0	79%	3.16	15.95
Basin 6	11.98	5.0	85%	4.25	16.23

	Required Flood Capacity (ac-ft)	100 Year Design Life			
		Sediment Yield (ac-ft)	Trap Efficiency	Deposition (ac-ft)	Required Basin (ac-ft)
Basin 1	16.76	15.0	80%	12.00	28.76
Basin 2	1.34	1.0	74%	0.74	2.08
Basin 3	1.02	1.0	76%	0.76	1.78
Basin 4	15.39	10.0	85%	8.50	23.89
Basin 5	12.79	8.0	81%	6.48	19.27
Basin 6	11.98	10.0	88%	8.80	20.78

CONCLUSIONS

A 100-year design life requires significant additional capacity in the reservoirs, nearly doubling the volume in some cases. These calculations include some significant uncertainty when the yield estimates are extended over 100 years.

The 50-year design life results in sediment storage that can be accommodated with a 25% to 35% increase in volume over the required flood capacity. This would still be a relatively maintenance free option, perhaps except in extreme events that would likely initiate emergency cleanup operations anyway.

A 25-year design life requires only a 12% to 17% increase in volume over the required flood capacity, but would necessitate that the city plan on cleaning it out on a recurring basis. If the cleaning occurred only every 25 years, the likelihood of proper maintenance occurring when needed is highly questionable. Frequent cleaning would be recommended.

Final design recommendations will be provided in the final planning documents where economic, project sponsor, and stakeholder considerations will be evaluated.

APPENDICES

- RHEM Technical Memo
- PSIAC Technical Memo
- Bridges Sediment Yield Map
- Trap Efficiency Calculations

APPENDIX – RHEM TECHNICAL MEMO

RHEM TECHNICAL MEMO

APPROACH

The Rangeland Hydrology and Erosion Model (RHEM) Web Tool is a software model able to produce estimates on watershed sediment yield based on varying types of data.

This memo summarizes the analysis process for one of the watersheds, “Basin 4”, to illustrate the process used for the remainder of the basins. Critical data used for analyzing the other basins is also tabulated in the conclusion section of this memo, or in other relevant sections. The range of data was collected for the RHEM model for “Basin 4” using 4 factors: Climate Station, Soil Texture Class, Slope, and Cover Characteristics. Climate data is determined by selecting a location in the RHEM interface, and the Santaquin, Utah region was selected. No specific data sets are available for the cover inputs required by the RHEM program, but it proved to be the biggest contributor to sediment yield variation. Information was interpolated from the land cover data sources that were available and field visits.

The RHEM model was run twice as shown in table 5 and table 6. The tables give upper and lower limits to the annual sediment yield based on the given ranges of input parameters. Climate and slope are assumed to be constants. Soil Texture Class assumes Loam as the higher sediment yield condition and Loamy Sand as the lower sediment yield condition. Cover Characteristics assumes 15% more foliar and 15% more ground cover for the lower sediment yield condition.

Additional information on each category of inputs is provided below, with Basin 4 used as the example to illustrate the analysis process.

CLIMATE

The RHEM Model has climate settings based on location. Basin 4 is in the Santaquin PH area.

SLOPE

GIS data processing calculated steep slopes averaging 58% across Basin 4.

United States Department of Agriculture (USDA) maps show Basin 4 to have a three slope conditions. Some of the lower parts of the basin range from 25% to 40% slopes (soil type YaE), as you move up the canyon slopes range from 30% to 70% (soil type ShF), and the west facing slopes at the mouth of the canyon range from 35% to 70% (soil type HKG).

GIS digital elevation data is assumed to be the most accurate data available and is consistent with most USDA slope ranges. The region average slope of 58% was used as constant in both high and low sediment yield conditions.

SOIL TEXTURE CLASS

USDA Soil maps showed Basin 4 as having four soil descriptions as shown in Figure 1. Henefer-Rake Association (HKG) described as a mountain shallow loam with a hydrologic group D; Yeats hollow Very Stony Loam (YaE) with a hydrologic group C; Pachic Cryoborolls (PD) soil


derived from limestone, sandstone, shale and volcanic rocks; and Sheep Creek Very Cobbly Loam (ShF) with a hydrologic group C.

Figure 1 - USDA Soil Map, Basin 4



United States Geological Survey (USGS) soil type maps are shown in Figure 2. The entire Basin 4 region is classified as, or is assumed to be, Type C soil. See the Hydrology Technical Memo for further details on hydrologic soil group data and assumptions.

Figure 2 - USGS Soil Type Map, Basin 4




Comparing data from these sources it is concluded that most soils in this basin are classified primarily as group C and less than 5% group D. Soil types were assumed by comparing USDA soil types and hydraulic soil groups, and the soil profile chart in Figure 3. Soil classifications are described below from “Part 630 Hydrology, National Engineering Handbook” Chapter 7 – Hydrologic Soil Groups:

“Group C—Soils in this group have moderately high runoff potential when thoroughly wet. Water transmission through the soil is somewhat restricted. Group C soils typically have between 20 percent and 40 percent clay and less than 50 percent sand and have loam, silt loam, sandy clay loam, clay loam, and silty clay loam textures. Some soils having clay, silty clay, or sandy clay textures may be placed in this group if they are well aggregated, of low bulk density, or contain greater than 35 percent rock fragments. The limits on the diagnostic physical characteristics of group C are as follows. The saturated hydraulic conductivity in the least transmissive layer between the surface and 50 centimeters [20 inches] is between 1.0 micrometers per second (0.14 inches per hour) and 10.0 micrometers per second (1.42 inches per hour). The depth to any water impermeable layer is greater than 50 centimeters [20 inches]. The depth to the water table is greater than 60 centimeters [24 inches]. Soils that are deeper than 100 centimeters [40 inches] to a restriction and a water table are in group C if the saturated hydraulic conductivity of all soil layers within 100 centimeters [40 inches] of the surface exceeds 0.40 micrometers per second (0.06 inches per hour) but is less than 4.0 micrometers per second (0.57 inches per hour)”

“Group D—Soils in this group have high runoff potential when thoroughly wet. Water movement through the soil is restricted or very restricted. Group D soils typically have greater than 40 percent clay, less than 50 percent sand, and have clayey textures. In some areas, they also have high shrink-swell potential. All soils with a depth to a water impermeable layer less than 50 centimeters [20 inches] and all soils with a water table (210-VI-NEH, May 2007) 7-3 Part 630 National Engineering Handbook Chapter 7 Hydrologic Soil Groups within 60 centimeters [24 inches] of the surface are in this group, although some may have a dual classification, as described in the next section, if they can be adequately drained. The limits on the physical diagnostic characteristics of group D are as follows. For soils with a water impermeable layer at a depth between 50 centimeters and 100 centimeters [20 and 40 inches], the saturated hydraulic conductivity in the least transmissive soil layer is less than or equal to 1.0 micrometers per second (0.14 inches per hour). For soils that are deeper than 100 centimeters [40 inches] to a restriction or water table, the saturated hydraulic conductivity of all soil layers within 100 centimeters [40 inches] of the surface is less than or equal to 0.40 micrometers per second (0.06 inches per hour).”

Loam and Loamy Sand were assumed to be the primary soil types in Basin 4. Loamy Sand was used as the soil type with lower sediment yield limit and Loam was used in the higher sediment yield limit.

Figure 3 - Soil Profile Chart




LAND COVER

National Land Cover Database (NLCD) maps evaluated on GIS show three land cover types as shown in Figure 4. GIS mapping was able to evaluate each land cover type percentage based on area in Basin 4: 51% Evergreen Forest, 24% Deciduous Forest and 25% shrub/scrub.

- *Evergreen Forest* - Areas dominated by trees generally greater than 5 meters tall, and greater than 20% of total vegetation cover. More than 75 percent of the tree species maintain their leaves all year. Canopy is never without green foliage.
- *Deciduous Forest* - Areas dominated by trees generally greater than 5 meters tall, and greater than 20% of total vegetation cover. More than 75 percent of the tree species shed foliage simultaneously in response to seasonal change.
- *Shrub/Scrub* - Areas dominated by shrubs; less than 5 meters tall with shrub canopy typically greater than 20% of total vegetation. This class includes true shrubs, young trees in an early successional stage or trees stunted from environmental conditions.

Figure 4 - NLCD Land Cover Map, Basin 4



Using the land cover information given in the NLCD, combined with knowledge of the area gained from on-site observation, the total foliar and ground cover estimations were made as shown in Table 3. Table 1 shows land cover type percentages derived from GIS data processing for all six basins.

Table 1 - Ground Cover Percentages

	Evergreen Forest	Deciduous Forest	Shrub/Scrub
Basin 1	65	29	6
Basin 2	48	23	29
Basin 3	41	29	30
Basin 4	51	24	25
Basin 5	28	44	18
Basin 6	60	26	11

CONVERSION AND CONCLUSION

RHEM model results for sediment yield are given as “Avg. Sediment Yield (ton/ac/year).” In order to convert that into “Avg. Sediment Yield (ac-ft/sq-mi/year),” weight (tons) must be turned into volume (ac-ft) by dividing out density. Table 2 shows density for different sediments. All six basins are assumed to be 100% aerated and either sand-silt mixtures (equal parts) or poorly sorted sand and gravel based on observations during field visits and from test pits. Basins 1, 4, 5, and 6 were assumed to be 100 lb/cubic foot. Basins 2 and 3 were assumed to be 95 lb/cubic foot. Here is the resulting conversion factor:

(640 acre / square mile), (2000 pounds / Ton), (cubic feet / 95-100 pounds), (acre feet / 43560 cubic feet).

Climate, Slope, Soil Type, and Land Cover are all input parameters needed to run the RHEM model for sediment yield. Basin 4 is located in the middle of all the basins and was chosen to be used as an example of the evaluation process and is the only basin with a thorough description of the development of input parameters. The same process for collecting input parameters was used for every basin. Screenshots from the RHEM model runs showing the high and low limits for sediment yield in Basin 4 are shown in figures 5 and 6. Tables 3 and 4 show the RHEM input parameters and results for all six basins. In table 3 the range of soil types and land covers used to evaluate the upper and lower limits on sediment yield are shown.

Table 2 – Soil Density - National Engineering Handbook Chapter 8

Table 8-1.—Volume-weight of sediment by grain size

Grain size	Volume-weight of sediment	
	Submerged	Aerated
	<i>lb/ft³</i>	<i>lb/ft³</i>
Clay	35–55	55–75
Silt	55–75	75–85
Clay-silt mixtures (equal parts)	40–65	65–85
Sand-silt mixtures (equal parts)	75–95	95–110
Clay-silt-sand mixtures (equal parts)	50–80	80–100
Sand	85–100	85–100
Gravel	85–125	85–125
Poorly sorted sand and gravel	95–130	95–130

Table 3 - RHEM Input Parameters

	Climate	Slope	Soil Type	Land Cover
Basin 1	Santaquin, Utah	66°	Loam and Loamy Sand	Bunch grass 20% to 25% Forbs/annuals 25% to 30% Shrubs 10% to 15% Basal 10% to 15% Rock 20% to 25% Litter 50% to 55%
Basin 2	Santaquin, Utah	58°	Loam and Loamy Sand	Bunch grass 15% to 20% Forbs/annuals 15% to 20% Shrubs 40% to 45% Basal 10% to 15% Rock 20% to 25% Litter 55% to 60%
Basin 3	Santaquin, Utah	47°	Loam and Loamy Sand	Bunch grass 15% to 20% Forbs/annuals 20% to 25% Shrubs 40% to 45% Basal 10% to 15% Rock 20% to 25% Litter 45% to 50%
Basin 4	Santaquin, Utah	58°	Loam and Loamy Sand	Bunch grass 15% to 20% Forbs/annuals 20% to 25% Shrubs 40% to 45% Basal 10% to 15% Rock 20% to 25% Litter 45% to 50%
Basin 5	Santaquin, Utah	50°	Loam and Loamy Sand	Bunch grass 15% to 20% Forbs/annuals 10% to 15% Shrubs 20% to 25% Basal 10% to 15% Rock 20% to 25% Litter 55% to 60%
Basin 6	Santaquin, Utah	59°	Loam and Loamy Sand	Bunch grass 20% to 25% Forbs/annuals 20% to 25% Shrubs 15% to 20% Basal 10% to 15% Rock 20% to 25% Litter 45% to 50%

Table 4 – RHEM Sediment Yield

Watershed Area	Sediment Yield (TN/Ac/Yr)	Sediment Yield (Ac-Ft/Sq-Mi/Yr)	Annual Yield (Ac-Ft)	50 Year Yield (Ac-Ft)
Basin 1	0.25-0.915	0.07-0.27	0.05-0.17	2.31-8.44
Basin 2*	0.102-0.416	0.03-0.13	0.002-0.01	0.11-0.45
Basin 3*	0.062-0.252	0.02-0.08	0.001-0.01	0.05-0.21
Basin 4	0.121-0.479	0.04-0.14	0.024-0.097	1.22-4.85
Basin 5	0.114-0.400	0.03-0.12	0.024-0.08	1.19-4.18
Basin 6	0.198-0.724	0.06-0.21	0.026-0.10	1.31-4.80

**Denotes Basins with soil density 95 lbs/cubic foot (all other basins are 100)*

Figure 5 - RHEM Model, Higher Yielding Limit of Basin 4

SCENARIO INPUTS		Download results as CSV ?				
		SANTAQUIN				
Version		2.3				
State ID		UT				
Climate Station		Santaquin Ph				
Soil Texture		Loam				
Soil Water Saturation %		25				
Slope Length (feet)		164.04				
Slope Shape		Convex				
Slope Steepness %		58				
Bunch Grass Foliar Cover %		15				
Forbs and/or Annual Grasses Foliar Cover %		20				
Shrubs Foliar Cover %		40				
Sod Grass Foliar Cover %		0				
TOTAL FOLIAR COVER %		75				
Basal Cover %		10				
Rock Cover %		20				
Litter Cover %		45				
Biological Crusts Cover %		0				
TOTAL GROUND COVER %		75				
ANNUAL AVERAGES		SANTAQUIN				
Avg. Precipitation (inches/year)		7.090				
Avg. Runoff (inches/year)		0.205				
Avg. Sediment Yield (ton/ac/year)		0.479				
Avg. Soil Loss (ton/ac/year)		0.485				
RETURN FREQUENCY RESULTS FOR YEARLY MAXIMUM DAILY		?				
VARIABLE	2 YR	5 YR	10 YR	25 YR	50 YR	100 YR
Rain (inches)	1.207	1.602	1.951	2.373	2.900	2.995
Runoff (inches)	0.042	0.302	0.514	0.724	1.054	1.275
Soil Loss (ton/ac)	0.160	0.682	1.047	1.369	1.865	2.399
Sediment Yield (ton/ac)	0.156	0.679	1.047	1.364	1.859	2.396
RETURN FREQUENCY RESULTS FOR YEARLY TOTALS		?				
VARIABLE	2 YR	5 YR	10 YR	25 YR	50 YR	100 YR
Rain (inches)	6.868	9.212	10.513	11.797	12.427	14.095
Runoff (inches)	0.049	0.385	0.593	0.971	1.177	1.765
Soil Loss (ton/ac)	0.179	0.872	1.384	1.927	2.412	3.182
Sediment Yield (ton/ac)	0.178	0.865	1.368	1.903	2.409	3.172

Figure 6 - RHEM Model, Lower Yielding Limit of Basin 4

SCENARIO INPUTS		Download results as CSV ?				
		SANTAQUIN				
Version	2.3					
State ID	UT					
Climate Station	Santaquin Ph					
Soil Texture	Loamy Sand					
Soil Water Saturation %	25					
Slope Length (feet)	164.04					
Slope Shape	Convex					
Slope Steepness %	58					
Bunch Grass Foliar Cover %	20					
Forbs and/or Annual Grasses Foliar Cover %	25					
Shrubs Foliar Cover %	45					
Sod Grass Foliar Cover %	0					
TOTAL FOLIAR COVER %	90					
Basal Cover %	15					
Rock Cover %	25					
Litter Cover %	50					
Biological Crusts Cover %	0					
TOTAL GROUND COVER %	90					
ANNUAL AVERAGES		SANTAQUIN				
Avg. Precipitation (inches/year)	2.489					
Avg. Runoff (inches/year)	0.047					
Avg. Sediment Yield (ton/ac/year)	0.121					
Avg. Soil Loss (ton/ac/year)	0.123					
RETURN FREQUENCY RESULTS FOR YEARLY MAXIMUM DAILY		?				
VARIABLE	2 YR	5 YR	10 YR	25 YR	50 YR	100 YR
Rain (inches)	0.983	1.444	1.781	2.371	2.780	3.006
Runoff (inches)	0.000	0.037	0.150	0.281	0.450	0.783
Soil Loss (ton/ac)	0.001	0.169	0.445	0.668	0.895	1.227
Sediment Yield (ton/ac)	0.000	0.167	0.433	0.660	0.890	1.216
RETURN FREQUENCY RESULTS FOR YEARLY TOTALS		?				
VARIABLE	2 YR	5 YR	10 YR	25 YR	50 YR	100 YR
Rain (inches)	2.200	3.592	4.537	5.755	7.042	7.756
Runoff (inches)	0.000	0.038	0.154	0.291	0.454	0.783
Soil Loss (ton/ac)	0.001	0.182	0.481	0.781	0.971	1.225
Sediment Yield (ton/ac)	0.000	0.177	0.477	0.773	0.956	1.214

APPENDIX – PSIAC TECHNICAL MEMO

PSIAC TECHNICAL MEMO

INTRODUCTION

The Pacific Southwest Interagency Committee Sediment Yield Procedure (PSIAC) – 1991 revision is a method of estimating watershed sediment yield over time. The PSIAC method evaluates on a numerical scale nine contributing factors to sediment yield.

- Surface geology
- Soils
- Climate
- Runoff
- Topography
- Effective Ground Cover
- Land Type / Management Quality
- Upland Erosion
- Channel Erosion / Sediment Transport

These nine contributing factors identified by the PSIAC method are each given a qualitative numerical score based on observed site conditions. The total score is then used to calculate sediment yield in a watershed area.

This memo summarizes the analysis process for one of the watersheds, “Basin 4”, to illustrate the process used for the remainder of the basins.


A copy of the spreadsheet used to score each category is shown in Table 4 at the end of this memo. This spreadsheet was supplied by the Utah office of the United States Department of Agriculture – Natural Resources Conservation Service. A few categories are derived by evaluating available GIS numerical data, such as soil type and vegetation, while many categories required qualitative observation and assumptions. In addition to the PSIAC documentation, the ranges of scores and the associated descriptions provided in the PSIAC spreadsheet are the basis of the score and justification used in determining the sediment yield.

SURFACE GEOLOGY

The Utah Geological Survey has geological maps identifying rock types as shown in Figure 1. The most common rock types identified in Basin 4 are Middle Cambrian Rock made up of quartzite, dolomite, limestone, and some sandstone; Gardison, Desert, and Great Blue Limestones; and Big Cottonwood Formation made up of quartzite and sandstone.

These rock types are above average on the hardness scale; there is no shale, mudstone, or siltstone in this area. The bedrock at or near the surface includes lightly weathered rock, minimal amounts of highly fractured rock, and a few large rock formations. The Geology factor is given a PSIAC scale factor of 1.


Figure 1 - UGS Geological Map, Basin 4



SOILS


USDA Soil maps showed Basin 4 as having three soil descriptions as shown in Figure 2: Yeats Hollow Very Stony Loam (YaE) with a hydrologic soil group (HSG) of C; Pachic Cryoborolls (PD) soil derived from limestone, sandstone, shale and volcanic rocks (no hydrologic soil group provided, C assumed); and Sheep Creek Very Cobbly Loam (ShF) with a HSG of C.

Figure 2 - USDA Soil Map, Basin 4



United States Geological Survey soil type maps shown in Figure 3 show the majority of Basin 4 classified as HSG Type C soil. Areas with no specified hydrologic soil group were assumed to have a HSG of C (See Hydrology Technical Memo for further detail).

Figure 3 - USGS Soil Type Map, Basin 4



Comparing data from the USGS map and soil descriptions provided above it is concluded that most soils in this basin are classified primarily as group C and less than 5% group D. Soil types were assumed by comparing USDA soil types, soil classification group C, soil classification group D, and soil the classification in figure 4. Soil classifications are described below from “Part 630 Hydrology, National Engineering Handbook” Chapter 7 – Hydrologic Soil Groups:


“Group C—Soils in this group have moderately high runoff potential when thoroughly wet. Water transmission through the soil is somewhat restricted. Group C soils typically have between 20 percent and 40 percent clay and less than 50 percent sand and have loam, silt loam, sandy clay loam, clay loam, and silty clay loam textures. Some soils having clay, silty clay, or sandy clay textures may be placed in this group if they are well aggregated, of low bulk density, or contain greater than 35 percent rock fragments. The limits on the diagnostic physical characteristics of group C are as follows. The saturated hydraulic conductivity in the least transmissive layer between the surface and 50 centimeters [20 inches] is between 1.0 micrometers per second (0.14 inches per hour) and 10.0 micrometers per second (1.42 inches per hour). The depth to any water impermeable layer is greater than 50 centimeters [20 inches]. The depth to the water table is greater than 60 centimeters [24 inches]. Soils that are deeper than 100 centimeters [40 inches] to a restriction and a water table are in group C if the saturated hydraulic conductivity of all soil layers within 100 centimeters [40 inches] of the surface

exceeds 0.40 micrometers per second (0.06 inches per hour) but is less than 4.0 micrometers per second (0.57 inches per hour)”

“Group D—Soils in this group have high runoff potential when thoroughly wet. Water movement through the soil is restricted or very restricted. Group D soils typically have greater than 40 percent clay, less than 50 percent sand, and have clayey textures. In some areas, they also have high shrink-swell potential. All soils with a depth to a water impermeable layer less than 50 centimeters [20 inches] and all soils with a water table (210–VI–NEH, May 2007) 7–3 Part 630 National Engineering Handbook Chapter 7 Hydrologic Soil Groups within 60 centimeters [24 inches] of the surface are in this group, although some may have a dual classification, as described in the next section, if they can be adequately drained. The limits on the physical diagnostic characteristics of group D are as follows. For soils with a water impermeable layer at a depth between 50 centimeters and 100 centimeters [20 and 40 inches], the saturated hydraulic conductivity in the least transmissive soil layer is less than or equal to 1.0 micrometers per second (0.14 inches per hour). For soils that are deeper than 100 centimeters [40 inches] to a restriction or water table, the saturated hydraulic conductivity of all soil layers within 100 centimeters [40 inches] of the surface is less than or equal to 0.40 micrometers per second (0.06 inches per hour).”

Loam and Loamy Sand were assumed to be the primary soil types in Basin 4. Loamy Sand was used as the soil type in the analysis of lower sediment yield limit, and Loam was used in the upper sediment yield limit analysis.

Figure 4 - Soil Profile Chart



Soils in this watershed have a high percentage of rock fragments, aggregated clays, some organic matter, no caliche layers, no saline alkaline, no high shrink-swell characteristics, and medium textured soil. Based on these factors a scale factor of 3 was used.

CLIMATE

The National Climatic Data Center (NCDC) located in Asheville, North Carolina published a report titled "Climate of Utah" which presents a climatological summary of climate conditions in Utah. The report contains many relevant condition descriptions:

- "During the past 100 years approximately 300 flash floods, resulting from high intensity rainfall and 135 snowmelt floods, have been recorded."
- "Utah experiences relatively strong insolation during the day and rapid nocturnal cooling, resulting in wide daily ranges in temperature."
- "There are however, from 4.5 to five months of freeze-free growing weather"
- "The bulk of moisture falling over that area can be attributed to movement of Pacific storms through the region during the winter and spring months."
- "The eastern portion receives rain from summer thunderstorms."
- "Snowfall is moderately heavy in the mountains, especially over the northern part"
- "Flash floods from summer thunderstorms are more frequent, but they affect only small, local areas."

Using information collected from NCDC and general knowledge of the climate in the Santaquin area, a PSIAC scale factor of 5 was used. It is not humid, precipitation does come in the form of snow, it is an arid climate with low intensity storms, convective storms come in the form of high winds moderately frequent, freeze-thaw occurrences are high, and storm duration of several days are very rare.

RUNOFF

Hydrology models that were run with standard curve number loss methodologies and time of concentration calculations resulted in high runoff values per square mile (CSM) as compared to those reported in the NRCS and McMillen study for nearby stream gages.


GIS mapping resulted in steep slopes averaging 58% across Basin 4.

The basins consist predominately of soils in the Group C Hydrologic Soil Group. As described in the "Soils," section of this report, these soils have a moderately high runoff potential.

In addition to our deterministic model approach, the United States Geological Survey (USGS) StreamStats modeling software was utilized as a more statistical approach in preparing a representative range of flows. Figure 5 and Figure 6 are model runs for Basin 4. The inputs are outside the recommended range for the Streamstats model, so errors are unknown. The 100-year event is estimated at approximately 56 cfs. Give the basin area of 0.6266 square miles, which is 89 CSM, which is far higher than the highest CSM from the stream gages analysis of about 40 CSM. Our uncalibrated deterministic models produced much higher flows.

High peak flows per unit area result in a recommended PSIAC scale rating of 7.

Figure 5 - StreamStats Model Profile, Basin 4



Basin Characteristics

Parameter Code	Parameter Description	Value	Unit
DRNAREA	Area that drains to a point on a stream	0.68	square miles
LU92HRBN	Percent Natural Herbaceous Upland from NLCD1992	1.6	percent

Annual Flow Statistics Parameters (Mean Flow SRSR 5230 Regions 3 and 5)

Parameter Code	Parameter Name	Value	Units	Min Limit	Max Limit
DRNAREA	Drainage Area	0.68	square miles	1.98	450

Annual Flow Statistics Disclaimers (Mean Flow SRSR 5230 Regions 3 and 5)

Figure 6 - StreamStats Model Results, Basin 4

One or more of the parameters is outside the suggested range. Estimates were extrapolated with unknown errors.

Annual Flow Statistics Flow Report (Mean Flow SRSR 5230 Regions 3 and 5)

Statistic	Value	Unit
Mean Annual Flow	0.994	ft ³ /s

Annual Flow Statistics Citations

Wilkowske, C.D., Kenney, T.A., and Wright, S.J., 2009, Methods for Estimating Monthly and Annual Streamflow Statistics at Ungaged Sites in Utah: U.S. Geological Survey Scientific Investigations Report 2008-5230, 62 p.

Peak-Flow Statistics Parameters (Region 3)

Parameter Code	Parameter Name	Value	Units	Min Limit	Max Limit
DRNAREA	Drainage Area	0.68	square miles	0.91	629
LU92HRBN	Percent Nat Herb Upland from NLCD1992	1.6	percent	2.14	15.6

Peak-Flow Statistics Disclaimers (Region 3)

One or more of the parameters is outside the suggested range. Estimates were extrapolated with unknown errors.

Peak-Flow Statistics Flow Report (Region 3)

Statistic	Value	Unit
2 Year Peak Flood	5.49	ft ³ /s
5 Year Peak Flood	14.1	ft ³ /s
10 Year Peak Flood	21.5	ft ³ /s
25 Year Peak Flood	32.8	ft ³ /s
50 Year Peak Flood	42.8	ft ³ /s
100 Year Peak Flood	55.7	ft ³ /s
200 Year Peak Flood	71	ft ³ /s
500 Year Peak Flood	96	ft ³ /s

TOPOGRAPHY

GIS mapping resulted in steep slopes averaging 58% across Basin 4.

United States Department of Agriculture (USDA) maps show Basin 4 as having three slope conditions. Some of the lower parts of the basin range from 25% to 40% slopes (soil type YaE). As you move up the canyon slopes range from 30% to 70% (soil type ShF), and the west facing slopes at the mouth of the canyon range from 35% to 70% (soil type HKG).


Extremely steep upland slopes and little or no floodplain development results in our recommending the maximum sediment contribution PSIAC scale factor of 20.

EFFECTIVE GROUND COVER

National Land Cover Database (NLCD) maps evaluated in GIS show three land cover types as shown in Figure 4. GIS data processing was able to evaluate each land cover type percentage based on area in Basin 4: 51% Evergreen Forest, 24% Deciduous Forest and 25% shrub/scrub.

- *Evergreen Forest* - Areas dominated by trees generally greater than 5 meters tall, and greater than 20% of total vegetation cover. More than 75 percent of the tree species maintain their leaves all year. Canopy is never without green foliage.
- *Deciduous Forest* - Areas dominated by trees generally greater than 5 meters tall, and greater than 20% of total vegetation cover. More than 75 percent of the tree species shed foliage simultaneously in response to seasonal change.
- *Shrub/Scrub* - Areas dominated by shrubs; less than 5 meters tall with shrub canopy typically greater than 20% of total vegetation. This class includes true shrubs, young trees in an early successional stage or trees stunted from environmental conditions.

Figure 7 - NLCD Land Cover Map, Basin 4



Using the information given combined with knowledge of the area gained from on-site observation, the total foliar cover estimation is 50% to 60% and total ground cover is 60% to 75%. Table 1 shows land cover type percentages derived from GIS mapping for all six basins.

Table 1 - Ground Cover Percentages

	Evergreen Forest	Deciduous Forest	Shrub/Scrub
Basin 1	65	29	6
Basin 2	48	23	29
Basin 3	41	29	30
Basin 4	51	24	25
Basin 5	28	44	18
Basin 6	60	26	11

Ground cover does exceed 20%; vegetation is not sparse; there is rock in surface soil cover; cover does exceed 40%; there is noticeable litter; trees are present but understory is not well developed; area is not completely protected by vegetation, rock fragments, litter; and there is moderate opportunity for rainfall to reach erodible material. Based on this description effective ground cover is given a PSIAC scale factor of -6.

LAND TYPE AND MANAGEMENT QUALITY

Observations obtained from field visits show Basin 4 to have no overgrazed area, no recent logging, no areas recently burned (this assumption is made due to the scope and time scale of this study), no badlands, and no roads cutting through this area. The recommended PSIAC sediment yield contribution scale factor is -8.

UPLAND EROSION

Observations obtained from field visits show Basin 4 to have much less than 25% of the area characterized by concentrated flow erosion with increasing gully development, but exhibiting some apparent signs of erosion. The recommended PSIAC sediment yield contribution scale factor is 4.

CHANNEL EROSION AND SEDIMENT TRANSPORT

Observations obtained from field visits show Basin 1 has some eroding banks at infrequent intervals, relatively shallow flow depths, minimal active headcuts, some degradation in tributary channels, no artificially controlled channels, rare channels in massive rock, occasional large boulders in the channel, channel banks with fair vegetation cover, and no wide channels with flat and short flow durations. This information collected results in PSIAC scale factor of 8.

CONCLUSION

Surface geology, soils, climate, runoff, topography, effective ground cover, land type and management quality, upland erosion, and channel erosion / sediment transport are the nine contributing factors and are all input parameters needed in the evaluation process of the PSIAC method for sediment yield. Basin 4 is located in the middle of all the basins and was chosen to be used as an example of the evaluation process and is the only basin with information provided on the collection of input parameters. The same process for collecting input parameters was used for every basin. The resulting recommended parameters for each basin are shown in Table 2. Climate is applied over a large area covering all six basins and was assumed to be constant for every basin. Surface Geology, Soils, Topography, Land Type / Management Quality, Upland Erosion, and Channel Erosion / Sediment Transport were not considered constants but yielded similar data resulting in identical PSIAC scale factors for all six basins. All six basins are centrally located in consistent terrain, similar results were anticipated for these categories. Table 3 shows results for sediment yield derived from the PSIAC model in all six basins.

Table 2 - PSIAC Scale Factor Parameters

	Basin 1	Basin 2	Basin 3	Basin 4	Basin 5	Basin 6
Surface Geology	1	1	1	1	1	1
Soils	3	3	3	3	3	3
Climate	5	5	5	5	5	5
Runoff	5	3	3	7	6	5
Topography	20	20	20	20	20	20
Effective Ground Cover	-8	-6	-5	-6	-7	-6
Land Type / Management Quality	-8	-8	-8	-8	-8	-8
Upland Erosion	4	4	4	4	4	4
Channel Erosion / Sediment Transport	8	8	8	8	8	8

Table 3 - PSIAC Sediment Yield

Watershed Area	Sediment Yield (Ac-Ft/Sq-Mi/Yr)	Annual Yield (Ac-Ft)	50 Year Yield (Ac-Ft)
Basin 1	0.24	0.15	7.54
Basin 2	0.24	0.017	0.83
Basin 3	0.25	0.013	0.67
Basin 4	0.28	0.19	9.64
Basin 5	0.26	0.18	9.25
Basin	0.27	0.126	6.09

Table 4 - PSIAC Model Evaluation Table

Pacific Southwest Interagency Committee Sediment Yield Procedure (PSIAC) - 1991 rev.						
Watershed:	SantaquinDB	Square Miles:	0.69	Acres (sq mi * 640):	442	
Factor	Discipline	PSIAC Rating			Points	
(a) Surface Geology	Geologist	Marine shales and related mudstones and siltstones	Rocks of Medium Hardness	Massive, hard formations	1	
			Moderately weathered			
			Moderately fractured			
			5	0		
(b) Soils	Soil Scientist	Fine textured; easily dispersed; saline alkaline; high shrink swell characteristics; single grain silt and fine sands	Medium textured soil	High percentage of rock fragments	3	
			Occasional rock fragments	Aggregated clays		
		Single grain silt and fine sands	Cliché layers	High in organic matter	0	
			10	0		
(c) Climate	Local	Storms of several day's duration with short periods of intense rainfall	Storms of moderate duration and intensity	Humid climate with rainfall of low intensity	5	
		Frequent intense convective storms	Infrequent convective storms	Precipitation in form of snow		
		Freeze-thaw occurrences		Arid climate, low intensity storm		
			5	0		
(d) Runoff	Hydrologist	High peak flows per unit area	Moderate peak flows per unit area	Low peak flow per unit area	7	
		Large volume of flow per unit area	Moderate volume of flow per unit area	Low volume of runoff per unit area		
				Rare runoff events		
			10	0		
(e) Topography	GIS Specialist	Steep upland slopes (in excess of 30%)	Moderate upland slopes (less than 20%)	Gentle upland slopes (less than 5%)	20	
		High relief; little or no floodplain development	Moderate fan or floodplain development	Extensive alluvial plains		
			20	0		
(f) Effective Ground Cover	GIS Specialist	Ground cover does not exceed 20%	Cover not exceeding 40%	Area completely protected by vegetation, rock fragments, litter	-6	
		Vegetation sparse; little or no litter	Noticeable litter	Little opportunity for rainfall to reach erodible material		
		No rock in surface soil cover	If trees present, understory not well developed			
				10	0	
	Alternative Calculation	Alternative Calculation: Enter percent of surface covered by vegetation, litter and rock				
				Vegetation (%)	20	
				Litter (%)	20	
				Rock (%)	15	
				Calculated Points	-6	
(g) Land Type and Management Quality	GIS Specialist	Almost all of area overgrazed or historic overgrazing impacts still active	<50% of area overgrazed or with historic overgrazing impacts still active	No recent logging	-8	
		All of area recently burned	<50% of area recently logged	Good grazing management or historic overgrazing impact under control		
		Roads in need of O&M or improved design	Ordinary road and other construction	Badlands are totally armored		
		Almost all of area is badlands with minimal armor	Almost all of area is badlands with 50% of area covered with armor			
			10	0		
(h) Upland Erosion	Geologist	More than 50% of the area characterized by concentrated flow erosion with increasing gully development	About 25% of the area characterized by concentrated flow erosion with increasing gully development	No apparent signs of erosion	4	
	Alternative Calculation	Percent of area with apparent erosion			10	
				Calculated Points	4	
(i) Channel Erosion and Sediment Transport	Geologist	Eroding banks, continuously or at frequent intervals, with deep flow of long duration	Moderate flow depths, medium flow duration with occasionally eroding banks or bed	Wide shallow channels with flat gradients and short flow duration	8	
		Active headcuts and degradation in tributary channels		Channels in massive rock, large boulders, or well vegetated		
				Artificially controlled channels		
			25	0		
				Subtotal (a) thru (g)	22	
				Subtotal (h) thru (i)	12	
				Grand total	34	
				Soil Bulk Density (gram/cm3)	1.3	
		Watershed:	SantaquinDB	Sediment Yield (Ac ft/sq mi/year)	0.28	
		Acres:	442	Sediment Yield (Tons/acre/year)	0.86	
				Total Sediment (Tons/year)	379	



APPENDIX – BRIDGES SEDIMENT YIELD MAP



BRIDGES SEDIMENT YIELD MAP

INTRODUCTION

NRCS provided sediment yield maps of the Santaquin, Utah region shown in Figure 1 and Figure 2 (Bridges, 1973). This map is intended for analysis over very large areas and provided an approximation which supports data collected from other sources. The foothills above Santaquin are shown with a yield class of 4. Figure 2 shows the yield rate associated with this yield class as 0.2 to 0.5 acre-feet per square mile per year. The 80-20 marking indicating sheet versus rill erosion is consistent with our assumption of minimal rill erosion in the PSIAC method.

Figure 1 – NRSC Bridges Sediment Yield Map 4




Figure 2 – Trap Efficiency Calculations, Basin 4

- EXPLANATION -

YIELD CLASS	YIELD RATE (Ac. Ft./Sq. Ft./Yr.)	TOTAL AREA (SQ. FT.)
1	> 3.0	_____
2	1.0-3.0	_____
3	0.5-1.0	_____
4	0.2-0.5	_____
5	0.1-0.2	_____
6	< 0.1	_____

▼ 0.45 AVERAGE ANNUAL SUSPENDED SEDIMENT YIELDS DETERMINED FROM SEDIMENT TRANSPORT RECORDS. RATES ARE IN AC. FT./SQ. FT./YR.
 80 - 20 ECT. (PERCENT OF SHEET AND RILL EROSION - PERCENT OF CHANNEL AND GULLY EROSION).

SUBREGION NUMBER	SUBREGION
1	SNIVE
2	BEAR LAKE
3	GREAT SALT LAKE
4	SCYPER LAKE
5	GREEN RIVER
6	SAN JUAN - COLORADO
7	UPPER MAIN STEM
8	LOWER MAIN STEM

✓ DO NOT USE THESE RATES TO DETERMINE SEDIMENT YIELDS AT SPECIFIC SITES. LARGE VARIATIONS IN SEDIMENT RATES MAY OCCUR WITHIN THE DELINEATED AREAS.

APPENDIX – TRAP EFFICIENCY CALCULATIONS

TRAP EFFICIENCY CALCULATIONS

INTRODUCTION

NRCS Technical Memo No. 12 (1975) provides Figure 1 below to determine trap efficiency given a capacity/inflow (C/I) ratio. Tables 2 and 3 show the calculations used to determine the C/I ratio. The floodwater storage input was calculated from the volumes necessary to hold and pass the 100-year 24-hour storm as determined in our hydrology and hydraulic analysis, as discussed in the Hydraulics Technical Memo. The sediment yield used is the rate determined for each watershed in the Sediment Technical Memo. The curve number method was used to find the inflow volume from the precipitation depth (NEH-630, Ch. 10), utilizing an assumption that the event based runoff formula could be assumed to average out for all events throughout the year. This is likely a conservative assumption because on average precipitation in the form of snowmelt and in very small rainfall events has a greater chance to percolate. Separate volume and trap efficiencies are shown for different design life periods (25, 50, 75, and 100 years).

Figure 1 – USDA Trap Efficiency Graph, Basin 4




Figure 2. Trap Efficiency of Reservoirs

Table 1 – Curve Numbers, Basins 1-6

	Curve Number (CN)
Basin 1	71.8
Basin 2	69.2
Basin 3	70.9
Basin 4	70.9
Basin 5	67.3
Basin 6	72.1


Table 2 – Trap Efficiency Calculations, Basin 1-3

Santequin Debris Basin 1												
Drainage Area	A. Capacity of Reservoir		1 -- Sediment Storage				2 -- Flood Water		3 -- Sum of 1 and 2, Total Capacity	B. Average Annual Runoff		C. Divide B from A-3
	sq. mi	acre-feet	inches	Acre feet/year	years	acre feet total years	inches	acre-feet	inches	inches	Precip	inches
0.63	20.51	0.61	0.15	25	3.75	0.112	16.76	0.500	0.61	20.3	16.24	0.038
0.63	24.26	0.72	0.15	50	7.5	0.224	16.76	0.500	0.724	20.3	16.24	0.045
0.63	28.01	0.84	0.15	75	11.25	0.34	16.76	0.500	0.836	20.3	16.24	0.051
0.63	31.76	0.95	0.15	100	15	0.448	16.76	0.500	0.948	20.3	16.24	0.058
Santequin Debris Basin 2												
Drainage Area	A. Capacity of Reservoir		1 -- Sediment Storage				2 -- Flood Water		3 -- Sum of 1 and 2, Total Capacity	B. Average Annual Runoff		C. Divide B from A-3
	sq. mi	acre-feet	inches	Acre feet/year	years	acre feet total years	inches	acre-feet	inches	inches	Precip	inches
0.07	1.59	0.43	0.01	25	0.25	0.068	1.34	0.365	0.43	20.3	15.79	0.027
0.07	1.84	0.50	0.01	50	0.5	0.136	1.34	0.365	0.501	20.3	15.79	0.032
0.07	2.09	0.57	0.01	75	0.75	0.20	1.34	0.365	0.570	20.3	15.79	0.036
0.07	2.34	0.64	0.01	100	1	0.273	1.34	0.365	0.638	20.3	15.79	0.040
Santequin Debris Basin 3												
Drainage Area	A. Capacity of Reservoir		1 -- Sediment Storage				2 -- Flood Water		3 -- Sum of 1 and 2, Total Capacity	B. Average Annual Runoff		C. Divide B from A-3
	sq. mi	acre-feet	inches	Acre feet/year	years	acre feet total years	inches	acre-feet	inches	inches	Precip	inches
0.05	1.27	0.45	0.01	25	0.25	0.088	1.02	0.360	0.45	20.3	16.09	0.028
0.05	1.52	0.54	0.01	50	0.5	0.177	1.02	0.360	0.537	20.3	16.09	0.033
0.05	1.77	0.63	0.01	75	0.75	0.26	1.02	0.360	0.625	20.3	16.09	0.039
0.05	2.02	0.71	0.01	100	1	0.353	1.02	0.360	0.713	20.3	16.09	0.044

Table 3 – Trap Efficiency Calculations, Basin 4-6

Santequin Debris Basin 4												
Drainage Area	A. Capacity of Reservoir		1 --Sediment Storage				2 -- Flood Water		3 -- Sum of 1 and 2, Total Capacity	B. Average Annual Runoff		C. Divide B from A-3
	sq. mi	acre-feet	inches	Acre feet/year	years	acre feet total years	inches	acre-feet	inches	inches	Precip	inches
0.69	17.89	0.49	0.10	25	2.5	0.068	15.39	0.420	0.49	20.3	16.09	0.030
0.69	20.39	0.56	0.10	50	5	0.136	15.39	0.420	0.556	20.3	16.09	0.035
0.69	22.89	0.62	0.10	75	7.5	0.20	15.39	0.420	0.624	20.3	16.09	0.039
0.69	25.39	0.69	0.10	100	10	0.273	15.39	0.420	0.692	20.3	16.09	0.043
				6.8								
Santequin Debris Basin 5												
Drainage Area	A. Capacity of Reservoir		1 --Sediment Storage				2 -- Flood Water		3 -- Sum of 1 and 2, Total Capacity	B. Average Annual Runoff		C. Divide B from A-3
	sq. mi	acre-feet	inches	Acre feet/year	years	acre feet total years	inches	acre-feet	inches	inches	Precip	inches
0.71	14.79	0.39	0.08	25	2	0.053	12.79	0.337	0.39	20.3	15.45	0.025
0.71	16.79	0.44	0.08	50	4	0.106	12.79	0.337	0.443	20.3	15.45	0.029
0.71	18.79	0.50	0.08	75	6	0.16	12.79	0.337	0.496	20.3	15.45	0.032
0.71	20.79	0.55	0.08	100	8	0.211	12.79	0.337	0.548	20.3	15.45	0.036
Santequin Debris Basin 6												
Drainage Area	A. Capacity of Reservoir		1 --Sediment Storage				2 -- Flood Water		3 -- Sum of 1 and 2, Total Capacity	B. Average Annual Runoff		C. Divide B from A-3
	sq. mi	acre-feet	inches	Acre feet/year	years	acre feet total years	inches	acre-feet	inches	inches	Precip	inches
0.45	14.48	0.60	0.10	25	2.5	0.104	11.98	0.498	0.60	20.3	16.30	0.037
0.45	16.98	0.71	0.10	50	5	0.208	11.98	0.498	0.706	20.3	16.30	0.043
0.45	19.48	0.81	0.10	75	7.5	0.31	11.98	0.498	0.810	20.3	16.30	0.050
0.45	21.98	0.91	0.10	100	10	0.416	11.98	0.498	0.914	20.3	16.30	0.056

ATTACHMENT 4
CONCEPT DRAWINGS



PRELIMINARY

NOT FOR CONSTRUCTION

REVISIONS

SCALE

HORIZONTAL
1" = 150'

VERTICAL
N/A

WARNING

1/2

IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE


HORROCKS
ENGINEERS

2162 West Grove Parkway
Suite 400
Pleasant Grove, UT 84062
(801) 763-5100

SANTAQUIN DEBRIS BASINS

BASIN 1 - BELOW GRADE

DESIGNED	####	DATE	####	PROJECT NO.	PG-1024-1801
DRAWN	####	DATE	####	SHEET NO.	# OF #
CHECKED	####	DATE	####	DRAWING NO.	P-01



PRELIMINARY

NOT FOR CONSTRUCTION

REVISIONS

SCALE

HORIZONTAL
1" = 60'

VERTICAL
N/A

WARNING

0 1/2 1
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE



HORROCKS
ENGINEERS

2162 West Grove Parkway
Suite 400
Pleasant Grove, UT 84062
(801) 763-5100

SANTAQUIN DEBRIS BASINS

BASIN 3A - BELOW GRADE (WATERSHEDS 2 & 3 COMBINED)

DESIGNED	####	DATE	###/###/###	PROJECT NO.	PG-1024-1801
DRAWN	####	DATE	###/###/###	SHEET NO.	# OF #
CHECKED	####	DATE	###/###/###	DRAWING NO.	P-05



5050

5075

5100

HIGH WATER
EL. 5053

BOTTOM
EL. 5039.5

DEBRIS BASIN 4E
25.9 AC FT

CREST EL. 5056

OUTLET PIPE

OUTLET
STRUCTURE

50' WIDE SPILLWAY

CHANNEL

CHANNEL

PRELIMINARY

NOT FOR CONSTRUCTION

REVISIONS

SCALE
HORIZONTAL
1" = 100'

VERTICAL
N/A

WARNING
0 1/2 1

IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE


HORROCKS
ENGINEERS

2162 West Grove Parkway
Suite 400
Pleasant Grove, UT 84062
(801) 763-5100


SANTAQUIN DEBRIS BASINS

BASIN 4E - ABOVE GRADE (WATERSHED ONLY)

DESIGNED	####	DATE	###	PROJECT NO.	PG-1024-1801
DRAWN	####	DATE	###	SHEET NO.	5 OF 12
CHECKED	####	DATE	###	DRAWING NO.	P-05



<p>PRELIMINARY</p> <p>NOT FOR CONSTRUCTION</p> <p>REVISIONS</p>	<p>SCALE</p> <p>HORIZONTAL: 1" = 150'</p> <p>VERTICAL: N/A</p>		<p>WARNING</p> <p>1/2"</p> <p>0</p> <p>IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p>		<p>HORROCKS</p> <p>ENGINEERS</p>		<p>2162 West Grove Parkway Suite 400 Pleasant Grove, UT 84062 (801) 763-5100</p>		<p>SANTAQUIN DEBRIS BASINS</p> <p>BASIN 5 - BELOW GRADE</p>		<p>DESIGNED: #####</p>	<p>DATE: #####</p>	<p>PROJECT NO.: PG-1024-1801</p>
							<p>DRAWN: #####</p>	<p>DATE: #####</p>	<p>SHEET NO.: # OF #</p>	<p>DRAWING NO.: P-12</p>	<p>CHECKED: #####</p>	<p>DATE: #####</p>	<p>SHEET NO.: # OF #</p>
											<p>DRAWING NO.: P-12</p>	<p>DATE: #####</p>	<p>SHEET NO.: # OF #</p>



PRELIMINARY

NOT FOR CONSTRUCTION

REV. DATE REVISIONS

SCALE

HORIZONTAL
1" = 100'

VERTICAL

N/A

WARNING

1/2

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

HORROCKS
ENGINEERS

2162 West Grove Parkway
Suite 400
Pleasant Grove, UT 84062
(801) 763-5100

SANTAQUIN DEBRIS BASINS

BASIN 6A - ABOVE GRADE

DESIGNED	####	DATE	####	PROJECT NO.	PG-1024-1801
DRAWN	####	DATE	####	SHEET NO.	# OF #
CHECKED	####	DATE	####	DRAWING NO.	P-07

ATTACHMENT 5

GEOTECHNICAL REPORT, PRELIMINARY SEISMIC ANALYSIS



14425 South Center Point Way Bluffdale, Utah 84065
Phone (801) 501-0583 | Fax (801) 501-0584

**Preliminary Feasibility Study for 5 Debris Basins
Santaquin, Utah**

GeoStrata Job No. 320-013

August 3, 2018

Prepared for:

**Horrocks Engineers, Inc.
Attn: Jacob O'Bryant, P.E.
2162 West Grove Parkway Suite 400
Pleasant Grove, Utah 84062**



Learn More


Prepared for:

Horrocks Engineers
Attn: Jacob O'Bryant, P.E.
2162 West Grove Parkway Suite 400
Pleasant Grove, Utah 84062

**Preliminary Feasibility Study for 5 Debris Flow Basins
Santaquin, Utah**

GeoStrata Job No. 320-013

Sofia Agopian
Staff Geologist



Daniel J. Brown, P.E.
Senior Geotechnical Engineer



Timothy Thompson, P.G.
Principal Geologist

GeoStrata
14425 South Center Point Way
Bluffdale, UT 84065
(801) 501-0583

August 3, 2018

TABLE OF CONTENTS

1.0	EXECUTIVE SUMMARY	1
2.0	INTRODUCTION.....	2
2.1	<i>PURPOSE AND SCOPE OF WORK</i>	2
2.2	<i>PROJECT DESCRIPTION</i>	3
3.0	GEOLOGIC CONDITIONS	4
3.1	<i>GEOLOGIC SETTING</i>	4
3.2	<i>TECTONIC SETTING</i>	4
4.0	METHOD OF STUDY	6
4.1	<i>FIELD INVESTIGATION</i>	6
4.3	<i>DRAINAGE 1</i>	7
4.3	<i>DRAINAGE 2</i>	7
4.4	<i>DRAINAGE 3</i>	8
4.5	<i>DRAINAGE 4</i>	8
4.6	<i>DRAINAGE 5</i>	9
4.7	<i>DRAINAGE 6</i>	9
5.0	PRELIMINARY ALLUVIAL FAN INVESTIGATION.....	10
5.1	<i>TEST PIT 1</i>	10
5.2	<i>TEST PIT 2</i>	10
5.3	<i>TEST PIT 3</i>	11
5.4	<i>TEST PIT 4</i>	11
5.6	<i>TEST PIT 6</i>	12
5.7	<i>LABORATORY TESTING</i>	12
6.0	PRELIMINARY ESTIMATES OF DEBRIS VOLUME	14
7.0	PRELIMINARY HAZARD MITIGATION RECOMMENDATIONS	16
7.1	<i>PREFERRED MITIGATION</i>	16
7.2	<i>DEBRIS BASINS</i>	16
7.2	<i>DIVERSION STRUCTURES</i>	17
8.0	PRELIMINARY ENGINEERING RECOMMENDATIONS	18
9.0	CLOSURE.....	20
9.1	<i>LIMITATIONS</i>	20
10.0	REFERENCES CITED.....	21

APPENDICES

Appendix A

Plate A-1 – Site Vicinity Map

Plate A-2 – Exploration Location Map

Plate A-3a – Site Vicinity Geologic Map

Plate A-3b – Site Vicinity Geologic Map Unit Descriptions

Plate A-3a – Site Vicinity 30' x 60' Geologic Map

Plate A-3b – Site Vicinity 30' x 60' Geologic Map Unit Descriptions

Plate A-5 – Hillshade Map

Appendix B

Plates B-1 to B-12 – Channel Cross Sections

Appendix C

Plates C-1 to C-6 – Test Pit Logs

Plate C-7 – Key to Soil Symbols and Terms

Appendix D

Plate D-1 – Laboratory Summary Table

Plate D-2 – Atterberg Limits Test Results

Plates D-3 to D-4 – Grain Size Distribution Test Results

Appendix E

Plates E-1 to E-4 – Photos of Test Pits

1.0 EXECUTIVE SUMMARY

The purpose of this investigation and report is to provide a preliminary assessment of the debris flow volume of six drainage basins located along the Wasatch Front in Santaquin, Utah in order to provide preliminary recommendations for the size, type and number of check dams that could be constructed within each drainage channel. The work performed for this report was performed in accordance with our proposal, dated April 19, 2018.

GeoStrata completed a site reconnaissance and test pit observations of the alluvial fan deposits on June 26, 2018. GeoStrata completed an additional site reconnaissance of Drainage 2 and Drainage 4 on July 18, 2018. Along with GeoStrata's field observations, geologic mapping of the study area (Solomon, 2010; Witkind and Weiss, 1991) was reviewed by GeoStrata as part of this investigation. Wasatch Front 2013-2014 0.5-meter LiDAR elevation data and 2006 5-meter DEM provided by the State of Utah AGRC were also assessed as part of this investigation to create cross sections along the drainage channels to assess the availability of soil that could ultimately trigger or contribute to a debris-flow event.

Preliminary analysis of the potential debris flow volumes was conducted using a bulking factor applied to the hydrology of each of the canyons and evaluating the available sediment within the channels. A description of the methodology and results of our preliminary analysis are presented in Section 6.0.

Prior to final design of the proposed hazard mitigation structures, a design level evaluation of each of the drainages addressed by this report should be conducted. Debris flow volumes presented in this report should be considered preliminary and should be refined with additional data from the channels in the canyons and from the alluvial fans.

Based on our preliminary engineering analysis of the proposed debris basin sites, the proposed locations are suitable for the proposed construction provided that design level geotechnical evaluations of each of the locations are performed and that recommendations from these studies are incorporated into the final design of the structures.

NOTICE: The scope of services provided within this report are limited to the assessment of the subsurface conditions for the proposed development. This executive summary is not intended to replace the report of which it is part and should not be used separately from the report. The executive summary is provided solely for purposes of overview. The executive summary omits a number of details, any one of which could be crucial to the proper application of this report.

2.0 INTRODUCTION

2.1 PURPOSE AND SCOPE OF WORK

The purpose of this investigation and report is to provide a preliminary assessment of the debris flow volume of six drainage basins located along the Wasatch Front in Santaquin, Utah in order to provide preliminary recommendations for the size, type and number of check dams that could be constructed within each drainage channel. The work performed for this report was performed in accordance with our proposal, dated April 19, 2018.

The recommendations presented by GeoStrata in this preliminary alluvial fan flood hazard report will be specific to the basins located in Santaquin, Utah that were evaluated for this report and are intended to provide geologic data necessary to design mitigation structures to increase the safety of the current and future residences on the alluvial fan associated with these basins.

Our scope of services for the debris-flow/alluvial fan flood hazard assessment for various drainage basins located in Santaquin, Utah included the following:

- Review of available references and maps of the area.
- Stereographic aerial photograph interpretation of aerial photographs covering the site area.
- Review of 2013-2014 0.5-meter LiDAR and 2006 5-meter DEM obtained from the State of Utah AGRC.
- Geologic reconnaissance of the site by an engineering geologist to observe and document pertinent surface features indicative of possible surface rupture fault hazards, alluvial fan flooding hazards or other geologic hazards.
- Subsurface investigation consisting of excavation of test pits on alluvial fans
- Sample collection of subsurface soils
- Laboratory testing:
 - Grain Size Distribution Analysis (ASTM D422)
 - Atterberg Limits Test (ASTM 4318)
- Preliminary assessment of geologic and geotechnical engineering conditions

The preliminary recommendations contained in this report are subject to the limitations presented in the Limitations section of this report.

2.2 PROJECT DESCRIPTION

The project site is located along the Wasatch Front Range in Santaquin, Utah (Plate A-1 Site Vicinity Map). The study area includes six drainage basins, Drainage 1 through Drainage 6, as identified on Plate A-2, Exploration Location Map. Construction of five detention basins are planned to mitigate the alluvial fan flooding hazard of the six drainage basins. Established residential developments are located on alluvial fan deposits and in the alluvial fan flooding paths of Drainage 1 through Drainage 5. An orchard field is located on the alluvial fan deposit and alluvial fan flooding path of Drainage 6.

3.0 GEOLOGIC CONDITIONS

3.1 GEOLOGIC SETTING

The study area and the location of the proposed mitigation structures are located at the base of the Wasatch Front Range in Santaquin, Utah. The geology of the mountains east of Santaquin range from Tertiary to Precambrian age. The bedrock in the Santaquin area has been uplifted and faulted during the Sevier Orogeny and later extensional faulting during late Eocene to middle Miocene. Santaquin is located in Utah Valley, a deep, sediment-filled structural basin of Cenozoic age flanked by uplifted blocks, the Wasatch Range on the east and the Spring Mountains and Western Mountains to the west (Hintze, 1980; Hintze, 1993). The Wasatch Range is the easternmost expression of pronounced Basin and Range extension in north-central Utah.

The near-surface geology of Santaquin is dominated by sediments which were deposited within the last 30,000 years by Lake Bonneville (Scott and others, 1983; Hintze, 1993; Crittenden and Sorensen, 1985). The lacustrine sediments near the mountain front consist mostly of gravel and sand. As the lake receded, streams began to incise large deltas formed at the mouths of major canyons along the Wasatch Range, and the eroded material was deposited in shallow lakes and marshes in the basin and in a series of recessional deltas and alluvial fans. Sediments toward the center of the valley are predominately deep-water deposits of clay, silt and fine sand. However, these deep-water deposits are in places covered by a thin post-Bonneville alluvial cover. Geologic maps of the study area are included with this report (Plate A-3a Site Vicinity Geologic Map; Plate A-4a Site Vicinity 30x60 Geologic Map).

The near-surface geology at the mouth of the drainage basins evaluated as part of this study are mapped by Solomon (2010) as Holocene to Pleistocene age alluvial fan deposits (Q_{afy}, Q_{af1-5}) overlying Pleistocene age deltaic deposits related to the transgressive phase of the Lake Bonneville cycle. Landslide and colluvial, undivided, deposits (Q_{mc}) are mapped within the drainage basins and along the canyon walls. A Holocene to middle Pleistocene age alluvial and colluvial, undivided, deposit (Q_{ac}) is mapped at the base of Drainage 1. Bedrock outcroppings are mapped throughout each drainage basin.

3.2 TECTONIC SETTING

The study area is located on the generally west dipping bench along the western foothills of the Wasatch Mountain Range. The Nephi segment is the southernmost segment of the Wasatch fault

zone and is mapped trending north and northwest through the study area. A steeply west dipping scarp or drastic drop in topography trends along the Nephi segment. The Nephi segment extends approximately 20 miles from its southern terminus in Nephi to its northern terminus at the Payson salient. Dry Mountain, Tithing Mountain, and Little Mountain are located south of Payson, Utah and mark the northern extent of the Nephi segment. The Nephi segment includes surface faulting along two strands, the northern strand bounded by Dry Mountain and a southern strand bounded by the Wasatch Range east of Juab Valley (DuRoss and McDonald, 2007). At a paleo-seismic trench excavated in 2005 along the northern strand of the Nephi segment, fault scarps between 10 and 13 feet high were exposed in late Holocene, less than 5,000 years old, alluvial fan deposits. Trench studies indicate that a surface fault rupture event along the northern strand of the Nephi segment has displacement of 10 feet within the last 500 years.

Analysis of the ground shaking hazard along the Wasatch Front suggests that the Wasatch Fault Zone is the single greatest contributor to the seismic hazard in the Salt Lake City region. Each of the faults listed above show evidence of Holocene-age movement and are therefore considered active.

4.0 METHOD OF STUDY

4.1 FIELD INVESTIGATION

Field investigations and observations used to assess the debris flow potential, probability and magnitude can be categorized into three areas of study (Giraud, 2005):

1. Channel Investigation – Studies of debris flows indicate that the majority of material/debris transported onto the alluvial fan comes from existing deposits within the defined drainage channel. The unit volume technique is commonly used to assign applicable debris yield rates (unit volume along distinct reaches of the channel) in order to approximate the potential debris volume.
2. Alluvial Fan Investigation – the thickness of debris deposits measured on the alluvial fan contribute to an understanding of past debris flow magnitude and potential run-out distance.

GeoStrata completed a site reconnaissance and test pit observations of the alluvial fan deposits on June 26, 2018. GeoStrata completed an additional site reconnaissance of Drainage 2 and Drainage 4 on July 18, 2018. Along with GeoStrata's field observations, geologic mapping of the study area (Solomon, 2010; Witkind and Weiss, 1991) was reviewed by GeoStrata as part of this investigation. Wasatch Front 2013-2014 0.5-meter LiDAR elevation data and 2006 5-meter DEM provided by the State of Utah AGRC were also assessed as part of this investigation to create cross sections along the drainage channels to assess the availability of soil that could ultimately trigger or contribute to a debris-flow event.

Six drainage channels were assessed as part of this investigation and aptly named Drainage 1 through Drainage 6. The location of the six drainage basins, test pit locations and profile cross section locations are shown on the Exploration Location Map Plate A-2.

The cross-sectional geometry of the channels within the drainages is variable. It was our objective to produce cross-sections that would be representative of the various geometries that exist in the main channels of the drainages. The following are the drainage basins in order from smallest to largest per area: Drainage 3, Drainage 2, Drainage 6, Drainage 1, Drainage 4 and Drainage 5. Tributary channels within all drainage basins exist but were not evaluated as part of this study. Each drainage is moderately to heavily vegetated within the channel and along the southern slopes of the drainage basins. Vegetation consists mainly of scrub oak and large brush.

A second site reconnaissance was conducted to further evaluate Drainage 2 and Drainage 4. A cross-section was collected in the field within Drainage 2 and Drainage 4 as shown on Plate A-2, Exploration Location Map. The GPS locations of these cross-sections were collected using a Trimble Handheld GeoXT. The cross-sections collected in the field were later compared to cross-sections derived from 2006 5-meter DEM and 2013-2014 0.5-meter LiDAR. Based on our comparison, the area calculated for each cross-section could have an error of $\pm 30\text{-ft}^2$ for cross-sections derived from 2006 5-meter DEM and $\pm 0.5\text{-ft}^2$ for cross-sections derived from 2013-2014 0.5-meter LiDAR.

In addition, volumes were calculated based on the assumption that the geometry of the channel remained unchanged along the designated lengths for each cross-section. Lastly, cross-sections were not calculated up the entire drainage due to lack of high resolution elevation data in these areas. The geometry of the final drawn cross-sections was assumed along the remaining length of the drainage. The estimations provided below are part of a preliminary assessment. A more in-depth study including cross-sectional data collected in the field is necessary prior to final design of mitigation structures. The following sections present results of our field and office investigations of the drainage basins assessed as part of this study. Cross section drawings of the channels are included in Appendix B (Plates B-1 to B-12).

4.3 DRAINAGE 1

Drainage 1 is approximately 408.4 acres (0.64 square miles) in size with a total defined channel length of approximately 7,068 feet. The properties of the main drainage channel are variable with some areas containing low to moderate amounts of stored debris and other areas with debris yield rates calculated to be approximately 385 ft^3/ft . To estimate potential debris discharge volumes from Drainage 1, GeoStrata produced cross sections in 17 different locations within the drainage channel to estimate the amount of debris currently available for transport. Cross-sections for Drainage 1 were derived from the 2006 5-meter DEM. The approximate locations of profile cross-sections are shown on the Exploration Location Map (Plate A-2).

4.3 DRAINAGE 2

Drainage 2 is approximately 45.1 acres (0.07 square miles) in size with a total defined channel length of approximately 2,397 feet. The properties of the main drainage channel are variable with some areas containing very little debris (exposed bedrock) and other areas where debris yield rates have been estimated to be approximately 250 ft^3/ft . To estimate potential debris discharge

volumes from Drainage 2, GeoStrata produced cross section in 8 different locations within the drainage channel to estimate the amount of debris currently available for transport. Cross-sections for Drainage 2 were derived from of 2006 5-meter DEM. The approximate locations of profile cross-sections are shown on the Exploration Location Map (Plate A-2). Descriptions of the drainage basin and channel are summarized below.

The channel within Drainage 2 was observed to have shallow banks and to consist of rocks and cobbles approximately 250 feet from the mouth of the drainage. Bedrock exposure along the channel was observed approximately 1,700 feet up the drainage basin. Vegetation was observed to be moderately dense in the channel.

4.4 DRAINAGE 3

Drainage 3 is approximately 34.6 acres (0.05 square miles) in size with a total defined channel length of approximately 1,295 feet. The properties of the main drainage channel are variable with some areas containing low to moderate amounts of stored debris and other areas with debris yield rates calculated to be approximately 7.7 f³/ft. To estimate potential debris discharge volumes from Drainage 3, GeoStrata produced cross sections in 7 different locations within the drainage channel to estimate the amount of debris currently available for transport. Cross-sections for Drainage 3 were derived from 2013-2014 0.5-meter LiDAR. The approximate locations of profile cross-sections are shown on the Exploration Location Map (Plate A-2).

4.5 DRAINAGE 4

Drainage 4 is approximately 445.8 acres (0.70 square miles) in size with a total defined channel length of approximately 3,828 feet. The properties of the main drainage channel are variable with some areas containing low to moderate amounts of stored debris and other areas with debris yield rates calculated to be approximately 10 f³/ft. To estimate potential debris discharge volumes from Drainage 4, GeoStrata produced cross sections in 7 different locations within the drainage channel estimate the amount of debris currently available for transport. Cross-sections for Drainage 4 were derived from 2013-2014 0.5-meter LiDAR. The approximate locations of profile cross-sections are shown on the Exploration Location Map (Plate A-2). Descriptions of the drainage basin and channel are summarized below.

The channel within Drainage 4 was observed to have steep banks and a broad, flat channel bottom. Bank cuts were observed to range from approximately 6 to 12 feet high and the channel

itself was observed to be broad and U-shaped. Bedrock exposure along the channel was observed at approximately 1,800 feet from the mouth of the drainage. A ramp lined with rip rap on the bottom of the channel to divert the direction of alluvial fan flooding was observed at the mouth of Drainage 4. Vegetation was observed to be moderately dense within the channel.

4.6 DRAINAGE 5

Drainage 5 is approximately 460.6 acres (0.72 square miles) in size with a total defined channel length of approximately 10,670 feet. The properties of the main drainage channel are variable with some areas containing low to moderate amounts of stored debris and other areas with debris yield rates calculated to be approximately 85 f³/ft. To estimate potential debris discharge volumes from Drainage 6, GeoStrata produced cross sections in 14 different locations within the drainage channel to estimate the amount of debris currently available for transport. Cross-sections for Drainage 5 were derived from 2013-2014 0.5-meter LiDAR. The approximate locations of profile cross-sections are shown on the Exploration Location Map (Plate A-2).

4.7 DRAINAGE 6

Drainage 6 is approximately 292.6 acres (0.46 square miles) in size with a total defined channel length of approximately 5,699 feet. The properties of the main drainage channel are variable with some areas containing low to moderate amounts of stored debris and other areas with debris yield rates calculated to be approximately 112 f³/ft. To estimate potential debris discharge volumes from Drainage 1, GeoStrata produced cross sections in 8 different locations within the drainage channel to more accurately estimate the amount of debris currently available for transport. Cross-sections for Drainage 3 were derived from 2013-2014 0.5-meter LiDAR. The approximate locations of profile cross-sections are shown on the Exploration Location Map (Plate A-2).

5.0 PRELIMINARY ALLUVIAL FAN INVESTIGATION

The preliminary alluvial fan investigation included the excavation, photographing and logging of six test pits on the alluvial fan deposits of each of the six canyons to observe the near-surface geology and assess the nature and extent of past alluvial fan flooding events across the alluvial fan surface. The logs of these Test Pits are presented on Plates C-1 through C-6. In general, the soils exposed in the test pit excavations consisted of alluvial fan flooding sediments ranging from fluvial to debris flow type deposits that extended the full depth. The approximate locations of the test pits are shown on the Exploration Location Map (Plate A-2). The alluvial fan geomorphology was also assessed using 2013-2014 0.5-meter LiDAR and 2006 5-meter DEM data provided by the State of Utah AGRC (Plate A-5). The following paragraphs provide detailed descriptions of conditions encountered in each test pit.

5.1 TEST PIT 1

Test Pit 1 was excavated approximately 10 feet deep. The log of the test pit that shows soil stratigraphy is included in Appendix C as Plate C-1. Test Pit 1 was excavated to a depth to expose alluvial fan sediments that would allow GeoStrata to assess the site for alluvial fan flooding hazard and to evaluate the soil suitability for the construction of a mitigation structure.

The uppermost soils exposed in Test Pit 1 were observed to be approximately 6 inches of A soil Horizon comprised of gravel, silt and sand. Underlying the A soil Horizon and in the upper 1½ to 2 feet were lenses of hyper-concentrated deposit, clast supported subangular pea gravel and gravels up to 2 inches with little to no fines, that were approximately 6 inches to 1 foot thick as shown on Plate E-1. Underlying the hyper-concentrated flows was a matrix supported, brown Silty, Clayey GRAVEL with sand and occasional subangular cobbles. Clasts within this unit were observed to be 2 inches and subangular. Fine roots were observed at a depth of approximately 2 feet into this unit.

5.2 TEST PIT 2

Test Pit 2 was excavated approximately 9 feet deep. The log of the test pit that shows soil stratigraphy is included in Appendix C as Plate C-2. Test Pit 2 was excavated to a depth to expose alluvial fan sediments that would allow GeoStrata to assess the site for alluvial fan flooding hazard and to evaluate the soil suitability for the construction of a mitigation structure.

The uppermost soils exposed in Test Pit 2 was observed to be approximately 6 inches of A soil Horizon. Underlying the A soil Horizon was a matrix supported, brown Silty SAND with gravel. Clasts in this unit were observed to be approximately 2 inches and subangular. A fluvial deposit consisting of Poorly Graded SAND approximately 6 inches thick was observed in the upper 2 ½ feet of this unit as shown on Plate E-2. The unit is comprised of dark-brown Silty SAND with gravel. Roots were observed to extend into the upper 2 feet of this unit.

5.3 TEST PIT 3

Test Pit 3 was excavated approximately 9 feet deep. The log of the test pit that shows soil stratigraphy is included in Appendix C as Plate C-3. Test Pit 3 was excavated to a depth to expose alluvial fan sediments that would allow GeoStrata to assess the site for alluvial fan flooding hazard and to evaluate the soil suitability for the construction of a mitigation structure.

The uppermost soils exposed in Test Pit 3 was observed to be approximately 6 inches of A soil Horizon comprised of gravel, silt and sand. A Silty, Clayey SAND with gravel was observed to underlie the A soil Horizon and to extend the depth of the test pit. The upper 3 feet of this unit was observed to be heavily rooted and clast supported, hyper-concentrated debris flow deposit, with few cobbles; clasts were observed to be subangular as shown on Plate E-3. The lower 6 feet of the test pit was observed to be matrix supported with subangular clasts approximately 2 inches in size.

5.4 TEST PIT 4

Test Pit 4 was excavated approximately 6 feet deep. The log of the test pit that shows soil stratigraphy is included in Appendix C as Plate C-4. Test Pit 4 was excavated to a depth to expose soils to evaluate the soil suitability for the construction of a mitigation structure and to observe potential alluvial fan sediments that would allow GeoStrata to assess the site for alluvial fan flooding hazard. The location of Test Pit 4 is located on the distal margins of the main alluvial fan deposit sourced by Drainage 4.

The uppermost unit in Test Pit 4 was observed to be approximately 6 inches of A soil Horizon. A Clayey GRAVEL with sand was observed to underlie the A soil Horizon and to extend the full depth of the test pit. This unit was observed to be matrix supported and to contain subangular clasts. Large subangular boulders approximately 2 to 3 feet in diameter were observed at the bottom of Test Pit 4.

5.5 TEST PIT 5

Test Pit 5 was excavated approximately 6 feet deep. The log of the test pit that shows soil stratigraphy is included in Appendix C as Plate C-5. Test Pit 5 was excavated to a depth to expose alluvial fan sediments that would allow GeoStrata to assess the site for alluvial fan flooding hazard and to evaluate the soil suitability for the construction of a mitigation structure.

The uppermost unit in Test Pit 5 was observed to be approximately 6 inches of A soil Horizon. The soils observed to underlie the A soil Horizon was observed to consist of a brown Well Graded GRAVEL with silt and sand and occasional cobbles up to approximately 8 inches in size. Clasts predominantly ranged from subangular pea gravel to 2 inches in size. Boulders approximately 1 foot in diameter and subangular were observed at the bottom of Test Pit 5.

5.6 TEST PIT 6

Test Pit 6 was excavated approximately 8 feet deep. The log of the test pit that shows soil stratigraphy is included in Appendix C as Plate C-6. Test Pit 6 was part of a sewer trench that was logged to allow GeoStrata to assess the site for alluvial fan flooding hazard.

The uppermost soils exposed in Test Pit 6 was observed to be approximately 6 inches of A soil Horizon. A matrix supported, brown Silty Gravel with sand and numerous large subangular cobbles up to approximately 2 feet was observed to underlie the A soil Horizon and to extend the full depth of the test pit. Roots were observed to extend approximately 3 feet into this unit.

5.7 LABORATORY TESTING

Geotechnical laboratory tests were conducted on selected soil samples obtained during our field investigation. The laboratory testing program was designed to evaluate the engineering characteristics of onsite earth materials. Laboratory tests conducted during this investigation include:

- Grain Size Distribution Analysis (ASTM D422)
- Atterberg Limits Test (ASTM D4318)
- Moisture Content of Soil Test (ASTM D2216)

The results of laboratory tests are presented on the test pit logs in Appendix C (Plates C-1 to C-6), the Lab Summary Report (Plate D-1), on the test result plates presented in Appendix D (Plates D-2 to D-4).

6.0 PRELIMINARY ESTIMATES OF DEBRIS VOLUME

The prediction of total debris and peak debris-flow volumes is complex and dependent on several factors. Precipitation (rainfall and snowmelt) data is readily available and the addition of moisture is generally viewed as a debris-flow trigger, but this represents only one of the many factors that contribute to debris-flow hazard. Vegetation, root depth, soil gradation, antecedent moisture conditions, and long-term climatic cycles all contribute to the generation of debris and initiation of debris-flows. Events of relatively short duration, such as a fire, can significantly alter a basin's natural resistance to debris-flow mobilization for approximately 5 years (Giraud and Castleton, 2009). These factors are difficult to quantify or predict and vary not only between different watersheds, but also within each sub-area of a drainage basin.

In general, there are two methods by which a debris-flow can be mobilized: 1) when shallow landslides from channel side-slopes are conveyed in existing channels when mixed with water and 2) channel scour where debris is initially mobilized by moving water in a channel and then the mobilized debris continues to assemble and transport downstream sediments. While methods of initiation differ, our observations of the drainage basins and channels lead us to assume that under existing conditions the majority of debris currently available for transport in the subject drainage basins would be mobilized from existing deposits within their developed channel beds and likely only in a post fire condition.

There are several methods available for predicting peak discharge rates and total debris flow volumes associated with debris-flows. The methods used in our preliminary analysis for this investigation are discussed below. Results of each of the methods of analysis are presented in the table below.

Method 1

Analysis of the hydrology of the canyons was performed by the project Civil Engineer (Horrocks) to provide peak flow and total flow data in order to calculate potential debris flow volumes. Stream flow is considered to be debris flow when the concentration by volume of sediment is between 40% and 85% (Keaton, et al., 1991). In order to calculate debris flow volumes, we assumed a 75% bulking rate, meaning that of the total rainstorm runoff, a volume of sediment equal to 3 times the volume of water may be mobilized.

Method 2

The unit-volume analysis method involves measuring and estimating the stored erodible sediment in the channel. Cross-sections are taken at various points along a channel and the geometry of the channel is used to estimate the sediment stored in the channel (Giraud, 2005). Estimating channel sediment volume available for bulking is critical because study of historical debris flows indicates that 80% to 90 % of the debris flow volume comes from the channel (Bowman and Lund, 2016).

All of the cross sections were developed utilizing 0.5-meter Wasatch Front LIDAR Elevation Data 2013 to 2014 and 2006 5-meter DEM data from the National Elevation Data Set. Available debris was estimated from field observations and measurements collected in the vicinity of those cross sections. General descriptions of these cross sections are contained in Section 4 of this report. Debris yield at these cross-sections was then extrapolated beyond investigation locations in order to approximate the potential debris yield for each of the drainages.

Considering alluvial fan flooding event that mobilizes 75% of the sediment stored in the channels and a 25-year burned condition storm event with water runoff volumes as provided by the Civil Engineer for each of the canyons, the table below presents estimated debris flow volumes for each of the subject canyons.

Drainage Basin	Method 1		Method 2		Estimated Total Debris Flow Volume (ac-ft)
	25-yr Burned Condition Runoff Volume (ac-ft)	Estimated Debris Flow Volume (ac-ft)	Estimated Available Streambed Sediment (ac-ft)	Estimated Debris Flow Volume (ac-ft)	
1	10.7	42.8	17.2	23.6	23.6
2	0.9	3.6	6.0	5.4	3.6
3	0.8	3.2	0.3	1.0	1.0
4	10.8	43.2	2.4	12.6	12.6
5	7.8	31.2	9.1	14.6	14.6
6	7.9	31.6	12.7	17.4	17.4

7.0 PRELIMINARY HAZARD MITIGATION RECOMMENDATIONS

7.1 PREFERRED MITIGATION

Methods for reducing debris-flow hazards in order of diminishing effectiveness are: 1) avoidance, 2) source area stabilization, 3) transportation-zone modification and 4) defense measures in the depositional zone (Hungr and others, 1987). Owing to the difficulties associated with equipment and personnel access which would accompany mitigation within the steep mountain drainages (methods 2 and 3) GeoStrata is providing only recommendations for defenses within the depositional zone (the alluvial fan). Other methods, if employed in the source areas and transportation zones within the canyon could further reduce the debris-flow hazard and may be explored if desired. However, this report assumes that mitigation measures will not be constructed within the canyon prior to completion of defense measures within the depositional zone.

Prior to final design of the proposed hazard mitigation structures, a design level evaluation of each of the drainages addressed by this report should be conducted. Debris flow volumes presented in this report should be considered preliminary and should be refined with additional data from the channels in the canyons and from the alluvial fans.

7.2 DEBRIS BASINS

Alluvial fan flooding defenses for the depositional zone recommended in this report may be generally categorized as retention within the depositional zone. Because of the unpredictability of alluvial fan flooding movements within the depositional zone it is generally preferable to locate retention structures as near to the fan apex as possible. Deflection berms or retention structures located to protect individual structures/facilities are useful but will leave other areas of the deposition zone unprotected if and when the alluvial fan flooding creates its own run-out path. In order to provide protection from the potential alluvial fan flooding hazard associated with the various canyons, we recommend that a debris retention basin be constructed as near as possible to the mouth of each canyon and that a spillway and channel be designed and constructed for diversion/direction of flood water flows.

In order to protect existing and proposed development below the canyons, debris detention/retention basins should be designed and constructed to capture and retain the debris flow volumes anticipated to flood flows from each of the canyons.

Based on these results, we recommend that preliminary design of debris detention/retention basins at the mouths of each canyon consider a storage volume of at least the volumes listed in the above table. Some risk associated with this size debris detention/retention basin does exist if a storm event larger than the 25-year burned condition storm event considered in this report were to occur while the canyons were in a post fire condition. Debris detention/retention basins with smaller storage volumes could also be designed with a higher level of risk associated with the smaller storage capacity of the debris detention/retention basins. The final constructed basins should incorporate appropriate outlet works and undergo regular maintenance to preserve design storage capacity. If constructed above grade it becomes a regulated dam and must be designed according to the requirements of the Utah Division of Water Rights, Dam Safety Division. If the basin can be constructed without an embankment (entirely below grade) it will not be regulated by Dam Safety. It is our opinion that debris basin dams can likely be located at or near the mouths of each of the canyons. No geologic or geotechnical features were identified at these locations that would preclude construction of the proposed dams.

Final design of detention/retention structures should consider design guidelines by Prochaska, Santi, and Higgins (2008).

7.2 DIVERSION STRUCTURES

As the proposed location of the debris basin for Drainage 4 is located on the distal margins of the main alluvial fan for the canyon, diversion structures will be required to direct debris and flood runoff to the proposed debris basin. Following the debris flows that occurred as a result of the 2002 fire, a diversion berm was constructed to direct flows away from a residential subdivision.

As part of a design level study, an evaluation of the diversion berm should be performed to verify compliance with design guidelines by Prochaska, Santi, and Higgins (2008).

8.0 PRELIMINARY ENGINEERING RECOMMENDATIONS

In order to evaluate the engineering properties of the existing soils in the vicinity of the proposed debris basins, a test pit was excavated in the approximate location of proposed debris retention/detention structures. A description of each of the test pits excavated and subsurface conditions encountered in each test pit is presented in Section 5.0 of this report and the test pit locations are shown on Plate A-2, Exploration Location Map.

Deeper subsurface investigations will be required in order to assess excavatability of subsurface soils if basins are to be constructed below the existing site grade or to assess bearing capacity of the subsurface strata if embankments are to be constructed above the existing site grade. Test pits TP-1, TP-2, TP-3, TP-5, and TP-6 were able to be excavated to depths requested for this preliminary investigation with a rubber-tired backhoe while digging was difficult and refusal was encountered in test pit TP-4 on either bedrock or large boulders.

We consider the likelihood of a seismic event occurring while one of the debris basins is loaded to be very low; therefore, seismic design of a fully loaded basin will not be required; however, the Nephi section of the Wasatch Fault Zone lies in close proximity to the proposed debris basin locations. We recommend that an evaluation of the proximity of the fault to each of the proposed debris basin locations be performed as fault rupture could impact the stability and performance of the debris basin embankments/slopes. A preliminary fault study should include examining the footprint of the proposed debris basins compared to the mapped location of the Nephi section of the Wasatch Fault Zone to determine whether further studies will be required, including trenching within the footprint of the proposed debris basins, to clear the sites of faults and/or identify the locations of faults. All fault studies should be completed by a licensed Professional Geologist.

A design level geotechnical investigation should be performed for each of the proposed debris basins including boreholes to sufficient depth to evaluate excavatability and bearing capacity of the subsurface soils, soil strength testing, soil permeability testing, slope stability analysis of proposed cuts and fills, foundation soil bearing capacity, and identification of borrow areas for proposed embankments (as needed).

Based on our preliminary engineering analysis of the proposed debris basin sites, the proposed locations are suitable for the proposed construction provided that design level geotechnical

evaluations of each of the locations are performed and that recommendations from these studies are incorporated into the final design of the structures.

9.0 CLOSURE

9.1 LIMITATIONS

Despite the best efforts to quantitatively assess debris-flow hazards, estimating design parameters including peak flows and the subsequent design of mitigation measures has practical limits. As stated by Giraud (2005) “historical records of debris-flows have shown the flows to be highly variable in terms of size, material properties, and travel and depositional behavior.” Predicting the depth of flow, super-elevation, impact forces and location of critical sections should be considered best estimates of intricate natural processes.

The conclusions and recommendations contained in this report which include professional opinions and judgments, are based on the information available to us at the time of our exploration, the results of our field observations, our limited subsurface exploration and our understanding of the proposed site development. The subsurface data used in the preparation of this report were obtained from the explorations made for this investigation. If any conditions are encountered at this site that are different from those described in this report, our firm should be immediately notified so that we may make any necessary revisions to recommendations contained in this report. In addition, if the scope of the proposed mitigation project changes from that described in this report, our firm should also be notified.

This report was prepared in accordance with the generally accepted standard of practice at the time the report was written. No other warranty expressed or implied is made. Development of property on or in the vicinity of alluvial fans involves a certain level of inherent risk.

This report was written for the exclusive use of the above Client and only for the proposed project described herein. It is the Client's responsibility to see that all parties to the project including the Designer, Contractor, Subcontractors, etc. are made aware of this report in its entirety. GeoStrata is not responsible for the technical interpretations by others of the information described or documented in this report.


10.0 REFERENCES CITED

- Bonnin, G.M., Martin, D., Lin, B., Parzybok, T., Yekta, M., Riley, D., 2011, Precipitation-Frequency Atlas of the United States, NOAA Atlas 14, Volume 1, Version 5.0: Semiarid Southwest (Arizona, Southeast California, Nevada, New Mexico, Utah), U.S. Department of Commerce, National Oceanic and Atmospheric Administration, National Weather Service.
- Bowman, S.D., Lund, W.R., 2016, Guidelines for investigating geologic hazards and preparing engineering geology reports with a suggested approach to geologic-hazard ordinances in Utah, Utah Geological Survey, Circular 122, p. 203.
- Cannon, S. H., Gartner, J.E., Rupert, M.G., Michael, J.A., Rea, A.H., and Parrett, C., 2010, Predicting the Probability and Volume of Postwildfire Debris Flows in the Intermountain Western United States, Geological Society of America GSA Bulletin; January/February 2010; v. 122; no. 1/2; p. 127-144.
- DuRoss, C. and McDonald, G., 2007, Survey Notes, v. 39 no. 1, The Most Recent Large Earthquake on the Nephi Segment of the Wasatch Fault Zone Near Santaquin: Results from 2005 Fault Trenches.
- Gartner, J.E., Cannon, S.H., Santi, P.M. and Dewolfe, V.G., 2008, Empirical Models to Predict the Volumes of Debris Flows Generated by Recent Burned Basins in the Western U.S., *Geomorphology* 96 (2008) 339-354.
- Giraud, R.E., 2005, Guidelines for the Geologic Evaluation of Debris-Flow Hazards on Alluvial Fans in Utah, Utah Geological Survey Miscellaneous Publication 05-6, 16 p.
- Giraud, R.E. and Castleton, J.J., 2009, Estimation of Potential Debris-Flow Volumes for Centerville Canyon, Davis County, Utah, Utah Geological Survey Report of Investigation 267, 33 p.
- Hintze, L. F., 1980, Geologic Map of Utah: Utah Geological and Mineral Survey Map-A-1, scale 1:500,000.
- Hintze, 1993, Geologic History of Utah, Brigham Young University Studies, Special Publication 7, 202 p.
- Hungr, O., Morgan, G.C., VanDine, D.F., and Lister, D.R., 1987, Debris flow defenses in British Columbia, *in* Costa, J.E., and Wieczorek, G.F., editors, Debris flows/avalanches: Geological Society of America, Reviews in Engineering Geology, Volume VII, p. 201-222.
- Keaton, J.R., Anderson, L.R., and Mathewson, C.C., 1991, Assessing debris flow hazards on alluvial fans in Davis County, Utah, Utah Geological Survey, Contract Report 91-11, p. 167.
- Prochaska, A.B., Santi, P.M. and Higgins, J.D., 2008, Debris basin and deflection berm design for fire-related debris-flow mitigation, The Geological Society of America, Environmental & Engineering Geoscience, Volume 14, No. 4, November 2008, pp. 297-313.
- Scott, W.E., McCoy, W.D., Shorba, R.R., and Rubin, Meyer, 1983, Reinterpretation of the exposed record of the last two cycles of Lake Bonneville, western United States: *Quaternary Research*, v.20, p. 261-285.
- USDA, 1986, Urban Hydrology for Small Watersheds, U.S. Department of Agriculture Technical Release 55

Appendix A




Legend
 Drainage Basins



1 inch = 2,000 feet

Basemap:

2009 1 meter NAIP aerial imagery and hillshades derived from 5 meter Auto-Corrected DEM provided by the State of Utah AGRC.



GeoStrata

Copyright GeoStrata 2018

Geologic Hazards Assessment
 Horrocks Engineers
 Santaquin Debris Basin
 Santaquin, Utah
 Project Number: 320-013


Site Vicinity Map

**Plate
 A-1**



- Legend**
- Drainage Basins
 - Approximate Test Pit Location
 - Cross Section


0 475 950 1,900 2,850 3,800 Feet
 1 inch = 1,500 feet
 Basemap:
 2009 1 meter NAIP aerial imagery and hillshades derived from 5 meter Auto-Corrected DEM provided by the State of Utah AGRC.




GeoStrata
 Copyright GeoStrata 2018

Geologic Hazards Assessment
 Horrocks Engineers
 Santaquin Debris Basin
 Santaquin, Utah
 Project Number: 320-013
Exploration Location Map

**Plate
 A-2**



Legend
 Drainage Basins



1 inch = 2,000 feet

Basemap:

Interim Geologic Map of Unconsolidated Deposits in the Payson Lakes Quadrangle, Utah County, Utah, Solomon, 2010, Interim Geologic Map of the Santaquin Unconsolidated Deposits in the Payson Lakes Quadrangle, Utah County, Utah, Solomon, 2010 and hillshades derived from 5 meter Auto-Corrected DEM provided by the State of Utah AGRC.



GeoStrata

Copyright GeoStrata 2018

Geologic Hazards Assessment
 Horrocks Engineers
 Santaquin, Utah
 Project Number: 320-013

**Plate
 A-3**

Site Vicinity Geologic Map

- R** **Rock (Tertiary to Precambrian) – Mapping of bedrock structure and stratigraphy is beyond the scope of this project.** Hintze (1962) and Witkind and Weiss (1991) compiled geologic maps of the region that include the Santaquin quadrangle at respective scales of 1:125,000 and 1:100,000, providing valuable overviews of regional geology, although many questions remain regarding stratigraphic relationships and geologic structure. For more information, refer to these maps as well as others cited in the Previous Investigations section of this report. According to these maps, Cretaceous and Tertiary rocks are most common on the east side of Warm Springs Mountain and near Santaquin Canyon; Paleozoic rocks are most common on Goshen Hill, the northern end of Dry Mountain, the west side of Warm Springs Mountain, and in the mountains west and east of Juab Valley; and Precambrian rocks are most common at the base of the western side of Dry Mountain.
- QTmb** **Megabreccia deposits (Pleistocene to Pliocene?) – Includes large bedrock blocks, rubble, and younger Quaternary landslide deposits too small to map separately; bedrock blocks are comprised largely of Paleozoic quartzite, dolomite, and limestone on the northwest margin of Dry Mountain, east of Santaquin; mapped by Demars (1956), Hintze (1962), and Witkind and Weiss (1991) as highly faulted and deformed bedrock, but a prominent arcuate main scarp lies to the east of the deposit, which has a more subdued upper surface than surrounding bedrock and lies in an amphitheater at least 150 feet (45 meters) below the scarp; displacement of the deposit is thought to have started in the late Tertiary (possibly Pliocene) and continued intermittently during the Pleistocene as movement along the Wasatch fault zone uplifted the range front relative to the valleys. Thickness as much as 200 feet (60 m).**
- Qmc** **Landslide and colluvial deposits, undivided (Holocene to middle Pleistocene) – Deposits of landslides (slides and slumps), slopewash, and soil creep that grade into one another in areas of subdued morphology, where mapping colluvium separately from landslides is not possible at map scale; composition and texture depend on local sources; mapped in scattered areas of the Wasatch Range. Thickness less than 40 feet (12 m).**
- Qac** **Alluvial and colluvial deposits, undivided (Holocene to middle Pleistocene) – Poorly to moderately sorted, generally poorly stratified, clay- to boulder-size, locally derived sediment mapped in drainages scattered throughout the quadrangle that are in bedrock or are underlain by bedrock at shallow depths beneath a veneer of Quaternary deposits, where deposits of alluvium, slopewash, and creep grade into one another; small, unmapped deposits are likely in most small drainages. Thickness less than 10 feet (3 m).**


GeoStrata

Copyright GeoStrata 2018


Geologic Hazards Assessment
Horrocks Engineers
Santaquin, Utah
Project Number: 320-013

**Site Vicinity Geologic Map
Unit Descriptions**

**Plate
A-3a**



Legend
 Drainage Basins



1 inch = 2,000 feet

Basemap:

Geologic Map of the Ne[hi 30' x 60' Quadrangle, Carbon, Emery, Juab, Sanpete, Utah, and Wasatch Counties, Utah, Witkind and Weiss, 1991. Hillshades derived from 5 meter Auto-Corrected DEM provided by the State of Utah AGRC.



GeoStrata

Copyright GeoStrata 2018

Geologic Hazards Assessment
 Horrocks Engineers
 Santaquin, Utah
 Project Number: 320-013

Site Vicinity 30x60 Geologic Map

**Plate
 A-4**

Mgb **Great Blue Limestone (Upper Mississippian)**—Light-bluish-gray to bluish-gray limestone and some shale. The limestone is chiefly thick bedded to massive and has been much fractured. About 91 m (300 ft) thick

Md **Deseret Limestone (Upper and Lower Mississippian)**—Dark bluish-gray, thin-bedded limestone that contains abundant interlayered lenticular thin beds of black chert. Chert is characteristic and is found wherever the formation is exposed. Limestone is commonly medium to coarsely crystalline. A few thin shale beds are near base. Includes minor interbedded dolomite. Thickness ranges from 183 to 275 m (600–900 ft) (Rigby and Clark, 1962, p. 19)

Mg **Gardison Limestone (Lower Mississippian)**—Dark bluish-gray, thin-bedded fossiliferous limestone containing minor interleaved dolomite. Highly fossiliferous beds are characteristic. Contains abundant black and light-gray chert as nodules and thin seams. Lower part of formation is marked by scree-covered slopes, upper part forms prominent cliffs and steep slopes. Likely correlative with part of the Madison Limestone of Montana, Wyoming, and northern Utah. Ranges in thickness from 183 to 275 m (600–900 ft) in the southern Wasatch Range (Rigby and Clark, 1962, p. 19)

Cu **Upper Cambrian rocks, undivided**—Includes units of the Ajax Dolomite and Opex Formation

Ajax Dolomite—Light-gray to dark-gray, mottled dolomite and minor limestone. About 27 m (90 ft) of Ajax is exposed on Long Ridge. Uncertain if exposed in the southern Wasatch Range (Hintze, 1962, p. 14)

Opex Formation—Dark bluish-gray dolomite that contains some cherty beds and a few oolite beds. Ranges in thickness from about 30 to 145 m (100–475 ft)

Cmu **Middle Cambrian rocks, undivided**—Includes units of the following formations (in descending order): Cole Canyon Dolomite, Bluebird Dolomite, Herkimer Limestone, Dagmar Dolomite, and Teutonic Limestone

Cole Canyon Dolomite—Alternating light- and dark-gray beds of dolomite that locally contain sparse, small twig-like rods. Ranges in thickness from 88 to 152 m (290 to 500 ft) on Long Ridge, and from 70 to 140 m (230–460 ft) in the southern Wasatch Range (Hintze, 1962, p. 13)

Bluebird Dolomite—Dark bluish-gray dolomite characterized by white, sinuous twig-like rods of dolomite scattered irregularly through the formation. Ranges in thickness from 30 to 52 m (100–170 ft) on Long Ridge, and from 30 to 58 m (100–190 ft) in the southern Wasatch Range

Herkimer Limestone—Bluish-gray limestone characterized by abundant orange-mottled siltstone. Similar in appearance to the Teutonic Limestone but separated from that unit by the white Dagmar Dolomite. Cliff former. About 91 m (300 ft) thick on Long Ridge; ranges in thickness from 70 to 137 m (230–450 ft) in the southern Wasatch Range (Hintze, 1962, p. 12)

Dagmar Dolomite—Light-gray to white, dense, thin-bedded dolomite that contrasts sharply with both the underlying and overlying darker limestone units. About 30 m (100 ft) thick

Teutonic Limestone—Bluish-gray limestone characterized by abundant orange mottled siltstone. Ranges in thickness from about 85 to 145 m (280–475 ft)

Co **Ophir Formation (Middle Cambrian)**—Pale-green to olive-green phyllitic shale. Light-green sandstone beds are interleaved in basal part and light-brown limestone beds are common in the middle. Forms gentle slopes between cliffs and steep slopes formed on underlying Tintic Quartzite (Ct) and overlying Teutonic Limestone (part of unit Cmu). About 91 m (300 ft) thick on Long Ridge and 76 m (250 ft) thick in the southern Wasatch Range (Hintze, 1962, p. 11)

Ct **Tintic Quartzite (Lower Cambrian)**—Light-brown to orange-brown, thin- to medium-bedded, fine- to medium-grained quartzite. Grains are coated with limonite. Locally contains basal conglomerate. Forms resistant, steep ledges and slopes. Ranges in thickness from about 275 to 335 m (900–1100 ft) in southern Wasatch Range (Hintze, 1962, p. 11)

Cot **Ophir Formation and Tintic Quartzite, undivided (Middle and Lower Cambrian)**—Units combined locally for cartographic purposes

MfPzu **Mesozoic and Paleozoic rocks, undivided**—Only shown in cross sections. Includes Ankareh Formation (Ka), Thaynes Limestone (Tt), Woodside Formation (Fw), Park City Formation (Ppc), Diamond Creek Sandstone (Pdc), Kirkman Limestone (Pk), Oquirrh Formation (Pfo), Manning Canyon Shale (Pmmc), Great Blue Limestone (Mgb), Humbug Formation (Mh), Deseret Limestone (Md), Gardison Limestone (Mg), Fitchville Formation (Mdf), Upper Devonian rocks of uncertain correlation (Du), Devonian and Ordovician rocks, undivided (DO), Upper Cambrian rocks, undivided (Cu), Middle Cambrian rocks, undivided (Cmu), Ophir Formation (Co), Diabasic lava flow (Cdf), and Tintic Quartzite (Ct)

PROTEROZOIC AND ARCHEAN METAMORPHIC ROCKS

Ybc **Big Cottonwood Formation (Middle Proterozoic)**—Maroon quartzite, arkosic sandstone, and siltstone containing interbedded green, red, brown, and yellowish-green phyllitic shale. Thickness uncertain, possibly as much as 375 m (1230 ft) thick (Metter, 1955, p. 218)

XAf **Farmington Canyon Complex (Early Proterozoic and Archean)**—Dark-gray to reddish-gray foliated rocks, chiefly schist, granitoid gneiss, and amphibolite, that have been intruded by dikes of pegmatite and medium- to coarse-grained granite. Thickness unknown

QTcf **Coalesced alluvial-fan deposits (Holocene to Pliocene?)**—Brown to dark-brown or gray, unconsolidated to semiconsolidated, thin- to thick-bedded, commonly crossbedded sediments of fluvial origin. Deposits consist of silt, sand, granules, pebbles, cobbles, and sparse boulders. Formed by the overlapping and interfingering of adjacent alluvial fans; forms broad, low, sloping apron at foot of adjacent highlands. Includes Sevier River Formation, which probably ranges in age from Miocene to Pleistocene. Thickness uncertain; possibly as much as 30 m (100 ft) thick locally

DEPOSITS OF THE BONNEVILLE LAKE CYCLE

Qbn **Nearshore deposits of the Bonneville lake cycle (Pleistocene)**—Light-gray to gray, moderately well sorted, even-bedded deposits of cross-bedded silt, sand, gravel, and sparse cobbles. Chiefly of deltaic origin. Thickness uncertain; may be as much as 76 m (250 ft) thick


Qf **Alluvial-fan deposits (Holocene)**—Light-brown to brown, locally gray, unconsolidated to semiconsolidated, moderately well sorted silt, sand, granules, pebbles, and cobbles at stream mouths. Of fluvial origin. Deposits commonly lobate. Thickness uncertain, probably as much as 15 m (50 ft) locally

GeoStrata

Copyright GeoStrata 2018


Geologic Hazards Assessment
Horrocks Engineers
Santaquin, Utah
Project Number: 320-013
**Site Vicinity 30x60 Geologic Map
Unit Descriptions**

**Plate
A-4a**



Mgb


Legend
 Drainage Basins



1 inch = 1,500 feet

Basemap:

Hillshades derived from 2013-2014 0.5 meter LiDAR and 5 meter Auto-Corrected DEM provided by the State of Utah AGRC.



GeoStrata



Copyright GeoStrata 2018



Geologic Hazards Assessment
 Horrocks Engineers
 Santaquin, Utah
 Project Number: 320-013

Hillshade Map


Plate
A-5

Appendix B









Profile A-A'





Profile C-C'
















A-A'






C-C'














Appendix C

DATE		STARTED: 6/26/18		Horrocks Engineers Santaquin Debris Basin Santaquin, Utah Project Number 320-013			GeoStrata Rep: SA		TEST PIT NO: TP-2 Sheet 1 of 1				
		COMPLETED: 6/26/18					Rig Type: Backhoe						
		BACKFILLED: 6/26/18											
DEPTH		LOCATION			Dry Density (pcf)	Moisture Content %	Percent minus 200	Liquid Limit	Plasticity Index	Moisture Content and Atterberg Limits			
METERS	FEET	SAMPLES	WATER LEVEL	GRAPHICAL LOG						UNIFIED SOIL CLASSIFICATION	NORTHING	EASTING	ELEVATION
		MATERIAL DESCRIPTION									Plastic Limit Moisture Content Liquid Limit -----●----- 10 20 30 40 50 60 70 80 90		
0	0												
					SM								
					TOPSOIL - silt, sand, gravel, brown, slightly moist, fine roots.								
					Silty SAND with gravel - medium dense, moist, brown, matrix supported, subangular gravel 2 to 3 inches								
					- lenses of Poorly Graded SAND (SP)								
					- increase in fines, less gravel, cobbles and boulders, subangular clasts	2.6	12.2	NP	NP	●			
					Bottom of Test Pit @ 9 Feet								
3													



SAMPLE TYPE	
	- GRAB SAMPLE
	- 3" O.D. THIN-WALLED HAND SAMPLER
WATER LEVEL	
	- MEASURED
	- ESTIMATED

NOTES:

Plate
C-2

DATE		STARTED: 6/26/18		Horrocks Engineers Santaquin Debris Basin Santaquin, Utah Project Number 320-013			GeoStrata Rep: SA		TEST PIT NO:					
		COMPLETED: 6/26/18					Rig Type: Backhoe		TP-3 Sheet 1 of 1					
		BACKFILLED: 6/26/18												
DEPTH				LOCATION			Dry Density (pcf)	Moisture Content %	Percent minus 200	Liquid Limit	Plasticity Index	Moisture Content and Atterberg Limits		
METERS	FEET	SAMPLES	WATER LEVEL	NORTHING	EASTING	ELEVATION						Plastic Limit Moisture Content Liquid Limit -----●----- 10 20 30 40 50 60 70 80 90		
		GRAPHICAL LOG		MATERIAL DESCRIPTION										
0				TOPSOIL - silt, sand, gravel, brown, slightly moist, fine roots.										
1				Silty Clayey SAND with gravel - medium dense, moist, brown, matrix supported, lenses of Poorly GRADED SAND (SP), occasional large subangular boulders in upper 3 feet										
5				SC-SM			3.2 16.1 24 5 ● H							
2														
3				Bottom of Test Pit @ 9 Feet										



Copyright (c) 2018, GeoStrata.

SAMPLE TYPE
 □ - GRAB SAMPLE
 ▣ - 3" O.D. THIN-WALLED HAND SAMPLER

WATER LEVEL
 ▼ - MEASURED
 ▽ - ESTIMATED

NOTES:

Plate
C-3

DATE		STARTED: 6/26/18	Horrocks Engineers Santaquin Debris Basin Santaquin, Utah Project Number 320-013			GeoStrata Rep: SA			TEST PIT NO:									
		COMPLETED: 6/26/18				Rig Type: Backhoe			TP-6 Sheet 1 of 1									
		BACKFILLED: 6/26/18																
DEPTH		METERS	FEET	SAMPLES	WATER LEVEL	GRAPHICAL LOG	UNIFIED SOIL CLASSIFICATION	LOCATION			Moisture Content and Atterberg Limits							
								NORTHING	EASTING	ELEVATION	Dry Density (pcf)	Moisture Content %	Percent minus 200	Liquid Limit	Plasticity Index	Plastic Limit	Moisture Content	Liquid Limit
MATERIAL DESCRIPTION																		
0		0						TOPSOIL - silt, sand, gravel, brown, slightly moist, fine roots.										
							GM	Silty GRAVEL with sand - dense, slightly moist, brown, matrix supported, subangular cobbles up to 1 foot in diameter.										
1																		
5											2.1	15.9	NP	NP				
2																		
3								Bottom of Test Pit @ 8 Feet										



Copyright (c) 2018, GeoStrata.

SAMPLE TYPE

- ☐ - GRAB SAMPLE
- ⊠ - 3" O.D. THIN-WALLED HAND SAMPLER

WATER LEVEL

- ▼ - MEASURED
- ▽ - ESTIMATED

NOTES:

Plate
C-6

UNIFIED SOIL CLASSIFICATION SYSTEM

MAJOR DIVISIONS		USCS SYMBOL	TYPICAL DESCRIPTIONS
COARSE GRAINED SOILS <small>(More than half of material is larger than the #200 sieve)</small>	GRAVELS <small>(More than half of coarse fraction is larger than the #4 sieve)</small>	GW	WELL-GRADED GRAVELS, GRAVEL-SAND MIXTURES WITH LITTLE OR NO FINES
		GP	POORLY-GRADED GRAVELS, GRAVEL-SAND MIXTURES WITH LITTLE OR NO FINES
		GM	SILTY GRAVELS, GRAVEL-SILT-SAND MIXTURES
		GC	CLAYEY GRAVELS, GRAVEL-SAND-CLAY MIXTURES
	SANDS <small>(More than half of coarse fraction is smaller than the #4 sieve)</small>	SW	WELL-GRADED SANDS, SAND-GRAVEL MIXTURES WITH LITTLE OR NO FINES
		SP	POORLY-GRADED SANDS, SAND-GRAVEL MIXTURES WITH LITTLE OR NO FINES
FINE GRAINED SOILS <small>(More than half of material is smaller than the #200 sieve)</small>	SILTS AND CLAYS <small>(Liquid limit less than 60)</small>	SM	SILTY SANDS, SAND-GRAVEL-SILT MIXTURES
		SC	CLAYEY SANDS SAND-GRAVEL-CLAY MIXTURES
		ML	INORGANIC SILTS & VERY FINE SANDS, SILTY OR CLAYEY FINE SANDS, CLAYEY SILTS WITH SLIGHT PLASTICITY
		CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
SILTS AND CLAYS <small>(Liquid limit greater than 60)</small>	OL	ORGANIC SILTS & ORGANIC SILTY CLAYS OF LOW PLASTICITY	
	MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SAND OR SILT	
	CH	INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS	
	OH	ORGANIC CLAYS & ORGANIC SILTS OF MEDIUM-TO-HIGH PLASTICITY	
HIGHLY ORGANIC SOILS		PT	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS

LOG KEY SYMBOLS

	BORING SAMPLE LOCATION		TEST-PIT SAMPLE LOCATION
	WATER LEVEL (level after completion)		WATER LEVEL (level where first encountered)

CEMENTATION

DESCRIPTION	DESCRIPTION
WEAKLY	CRUMBLES OR BREAKS WITH HANDLING OR SLIGHT FINGER PRESSURE
MODERATELY	CRUMBLES OR BREAKS WITH CONSIDERABLE FINGER PRESSURE
STRONGLY	WILL NOT CRUMBLE OR BREAK WITH FINGER PRESSURE

OTHER TESTS KEY

C	CONSOLIDATION	SA	SIEVE ANALYSIS
AL	ATTERBERG LIMITS	DS	DIRECT SHEAR
UC	UNCONFINED COMPRESSION	T	TRIAXIAL
S	SOLUBILITY	R	RESISTIVITY
O	ORGANIC CONTENT	RV	R-VALUE
CBR	CALIFORNIA BEARING RATIO	SU	SOLUBLE SULFATES
COMP	MOISTURE/DENSITY RELATIONSHIP	PM	PERMEABILITY
CI	CALIFORNIA IMPACT	-200	% FINER THAN #200
COL	COLLAPSE POTENTIAL	Gs	SPECIFIC GRAVITY
SS	SHRINK SWELL	SL	SWELL LOAD

MODIFIERS

DESCRIPTION	%
TRACE	<5
SOME	5 - 12
WITH	>12

GENERAL NOTES

- Lines separating strata on the logs represent approximate boundaries only. Actual transitions may be gradual.
- No warranty is provided as to the continuity of soil conditions between individual sample locations.
- Logs represent general soil conditions observed at the point of exploration on the date indicated.
- In general, Unified Soil Classification designations presented on the logs were evaluated by visual methods only. Therefore, actual designations (based on laboratory tests) may vary.

MOISTURE CONTENT

DESCRIPTION	FIELD TEST
DRY	ABSENCE OF MOISTURE, DUSTY, DRY TO THE TOUCH
MOIST	DAMP BUT NO VISIBLE WATER
WET	VISIBLE FREE WATER, USUALLY SOIL BELOW WATER TABLE

STRATIFICATION

DESCRIPTION	THICKNESS	DESCRIPTION	THICKNESS
SEAM	1/16 - 1/2"	OCCASIONAL	ONE OR LESS PER FOOT OF THICKNESS
LAYER	1/2 - 12"	FREQUENT	MORE THAN ONE PER FOOT OF THICKNESS

APPARENT / RELATIVE DENSITY - COARSE-GRAINED SOIL

APPARENT DENSITY	SPT (blows/ft)	MODIFIED CA. SAMPLER (blows/ft)	CALIFORNIA SAMPLER (blows/ft)	RELATIVE DENSITY (%)	FIELD TEST
VERY LOOSE	<4	<4	<5	0 - 15	EASILY PENETRATED WITH 1/2-INCH REINFORCING ROD PUSHED BY HAND
LOOSE	4 - 10	5 - 12	5 - 15	15 - 35	DIFFICULT TO PENETRATE WITH 1/2-INCH REINFORCING ROD PUSHED BY HAND
MEDIUM DENSE	10 - 30	12 - 35	15 - 40	35 - 65	EASILY PENETRATED A FOOT WITH 1/2-INCH REINFORCING ROD DRIVEN WITH 5-LB HAMMER
DENSE	30 - 50	35 - 60	40 - 70	65 - 85	DIFFICULT TO PENETRATED A FOOT WITH 1/2-INCH REINFORCING ROD DRIVEN WITH 5-LB HAMMER
VERY DENSE	>50	>60	>70	85 - 100	PENETRATED ONLY A FEW INCHES WITH 1/2-INCH REINFORCING ROD DRIVEN WITH 5-LB HAMMER

CONSISTENCY - FINE-GRAINED SOIL

CONSISTENCY	SPT (blows/ft)	TORVANE		FIELD TEST
		UNTRAINED SHEAR STRENGTH (tsf)	POCKET PENETROMETER UNCONFINED COMPRESSIVE STRENGTH (tsf)	
VERY SOFT	<2	<0.125	<0.25	EASILY PENETRATED SEVERAL INCHES BY THUMB. EXUDES BETWEEN THUMB AND FINGERS WHEN SQUEEZED BY HAND.
SOFT	2 - 4	0.125 - 0.25	0.25 - 0.5	EASILY PENETRATED ONE INCH BY THUMB. MOLDED BY LIGHT FINGER PRESSURE.
MEDIUM STIFF	4 - 8	0.25 - 0.5	0.5 - 1.0	PENETRATED OVER 1/2 INCH BY THUMB WITH MODERATE EFFORT. MOLDED BY STRONG FINGER PRESSURE.
STIFF	8 - 15	0.5 - 1.0	1.0 - 2.0	INDENTED ABOUT 1/2 INCH BY THUMB BUT PENETRATED ONLY WITH GREAT EFFORT.
VERY STIFF	15 - 30	1.0 - 2.0	2.0 - 4.0	READILY INDENTED BY THUMBNAIL.
HARD	>30	>2.0	>4.0	INDENTED WITH DIFFICULTY BY THUMBNAIL.



Copyright GeoStrata, 2018


Soil Symbols Description Key

Horrocks Engineers
Santquin Debris Basin
Santquin, Utah
Project Number 320-013

Plate
C-7

Appendix D

Test Pit No.	Sample Depth (feet)	USCS Soil Classification	Natural Moisture Content (%)	Gradation			Atterberg	
				Gravel (%)	Sand (%)	Fines (%)	LL	PI
TP-1	5	GC	2.2	63.7	23.3	13	24	6
TP-2	5	SM	2.6	30.8	54.1	12.2	NP	NP
TP-3	5	SC-SM	3.2	27.3	56.6	16.1	22	4
TP-4	5	GC	3.4	49.3	24.6	15.4	26	10
TP-5	5	GW	2.4	46.7	37.9	11	NP	NP
TP-6	5	GM	2.1	54.3	23.8	15.9	NP	NP



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	


Sample Location	Depth	Classification					LL	PL	PI	Cc	Cu
● TP-1	5.0	Silty Clayey GRAVEL with sand					24	18	6		
▣ TP-2	5.0	Silty SAND with gravel					NP	NP	NP	2.03	51.59
▲ TP-3	5.0	Silty Clayey SAND with gravel					24	18	6		
★ TP-4	5.0	Clayey GRAVEL with sand					26	13	13		
⊙ TP-5	5.0	Well-Graded GRAVEL with silt and sand					NP	NP	NP	1.55	137.52
Sample Location	Depth	D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay		
● TP-1	5.0	75	23.43	2.222		63.7	23.3	13.0			
▣ TP-2	5.0	100	2.58	0.512		30.9	54.1	12.2			
▲ TP-3	5.0	75	1.978	0.325		27.3	56.7	16.1			
★ TP-4	5.0	100	13.616	1.008		49.3	24.6	15.4			
⊙ TP-5	5.0	100	8.413	0.893		46.8	37.9	11.0			

GRAIN SIZE DISTRIBUTION - ASTM D422



Horrocks Engineers
 Santaquin Debris Basin
 Santaquin, Utah
 Project Number: 320-013

Plate
D - 3



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Sample Location	Depth	Classification					LL	PL	PI	Cc	Cu
● TP-6	5.0	Silty GRAVEL with sand					NP	NP	NP		

Sample Location	Depth	D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay
● TP-6	5.0	100	16.983	0.995		54.3	23.8	15.9	

GRAIN SIZE DISTRIBUTION - ASTM D422

Horrocks Engineers
 Santaquin Debris Basin
 Santaquin, Utah
 Project Number: 320-013

**Plate
D - 4**



D_GSD_EXPLORATION_LOGS.GPJ GEOSTRATA.GDT 8/3/18

Appendix E

TEST PIT 1 EAST WALL

North

South



**Plate
E-1**

Geologic Hazards Investigation
Horrocks Engineers
Santaquin Debris Basin
Santaquin, Utah
Project Number: 320-013

GeoStrata
Copyright GeoStrata , 2018

TEST PIT 2 EAST WALL

North

South



**Plate
E-2**

Geologic Hazards Investigation
Horrocks Engineers
Santaquin Debris Basin
Santaquin, Utah
Project Number: 320-013

GeoStrata
Copyright GeoStrata , 2018

TEST PIT 3 EAST WALL

North

South



Hyper-Concentrated Flow

**Plate
E-3**

Geologic Hazards Investigation
Horrocks Engineers
Santaquin Debris Basin
Santaquin, Utah
Project Number: 320-013

GeoStrata
Copyright GeoStrata , 2018

TEST PIT 5 EAST WALL

North

South



**Plate
E-4**

Geologic Hazards Investigation
Horrocks Engineers
Santaquin Debris Basin
Santaquin, Utah
Project Number: 320-013


GeoStrata
Copyright GeoStrata , 2018

**To: Horrocks Engineers
Attn: Mr. Jacob O'Bryant
2162 West Grove Parkway, Suite 400
Pleasant Grove, Utah 84062**

**From: Daniel J. Brown, P.E.
Senior Geotechnical Engineer**

Date: June 10, 2019

**Subject: Preliminary Embankment Slope Stability
Santaquin Debris Basins
Santaquin, Utah
GeoStrata Job No. 320-013**



Mr. O'Bryant;

At your request, GeoStrata has completed a preliminary slope stability assessment of the five proposed embankments to be constructed at the mouths of six drainages in Santaquin, Utah. The proposed embankments are intended to mitigate debris flow hazard for the properties downstream and on the alluvial fan deposits of these drainages. Based on our understanding, the embankments are to consist of reworked native soils and have a maximum steepness of 3H:1V, a maximum height of 16 feet, and a top width of 12 feet.

Soils at the locations of each of the proposed debris basins were observed in test pits excavated for the *Preliminary Feasibility Study of 5 Debris Basins, Santaquin, Utah* report prepared by GeoStrata dated August 3, 2018. Based on laboratory testing completed on soil samples collected from these test pits, the soils consist of Silty, Clayey GRAVEL with sand, Silty SAND with gravel, Silty, Clayey SAND with gravel, Clayey GRAVEL with sand, Well-Graded GRAVEL with silt and sand, and Silty GRAVEL with sand. No soil strength testing was completed as part of the August 2018 preliminary feasibility study; however, for the purpose of this preliminary slope stability assessment, we have assumed soil strength parameters based on Table 2-6 of Bowles' *Foundation Analysis and Design* (1996) of a friction angle of 32 degrees and cohesion of 50 psf for the undisturbed native soil and a friction angle of 33 degrees and cohesion of 50 psf for the compacted embankment material.

Seismic design parameters were assessed for each of the proposed debris basin locations using the IBC 2015 Seismic Ground Motion Values maps. The table below summarizes seismic design parameters for these locations.

Drainage	1	2+3	4	5	6
Lat	39.9662	39.9705	39.9757	39.9817	39.9912
Long	-111.7585	-111.7603	-111.7646	-111.7613	-111.7443
S_s	1.303	1.32	1.341	1.355	1.362
S₁	0.48	0.484	0.489	0.494	0.503
S_{MS}	1.303	1.32	1.341	1.355	1.362
S_{M1}	0.730	0.734	0.739	0.744	0.755
S_{DS}	0.869	0.880	0.894	0.903	0.908
S_{D1}	0.486	0.489	0.493	0.496	0.503
F_a	1	1	1	1	1
F_v	1.52	1.516	1.511	1.506	1.5
PGA	0.591	0.598	0.607	0.613	0.615
F_{PGA}	1	1	1	1	1
PGA_M	0.591	0.598	0.607	0.613	0.615

Based on the seismic design data obtained from the IBC 2015 as summarized in the above table, a design PGA of 0.615g was utilized in our seismic slope stability analysis.

Slope stability modeling was completed using Slide, a computer program which incorporates Bishop's method of slope analysis. Analyses were completed using both full and empty basins, conservatively assuming the full basin contains only water. The full condition was assumed to have at least 2 feet of freeboard to the crest of the embankment.

Our rapid drawdown analysis used effective stresses but accounted for the pore pressure conditions created during such an event by using the B-bar method of analysis. The B-bar method calculates the change in pore pressure due to loading or unloading by multiplying the change in vertical pressure by B-bar. B-bar is usually a value from 0 to 1, with free draining soils having a value of 0. In our analysis we assumed a B-bar value of 1.0.

A deformation analysis for pseudo static conditions was completed on the embankment using the Bray and Travasarou method (2007). Our results indicate that during a seismic event, the embankment may experience total deformation of only approximately 1.9 inches if a seismic event were to occur during a time period when the embankment holds water with 2 feet of freeboard.


Results for our slope stability modeling are attached to this letter (Plate 1 to Plate 7). The results of the seepage analysis are presented on Plate 1. Based on our analysis, the proposed 3H:1V slopes constructed with the proposed native borrow material meets the minimum design standards. Our calculated safety factors are listed on the following table;


Analysis Type	Minimum Factor of Safety
Full – Static	2.307
Full – Pseudo Static	1.048
Rapid Drawdown	2.477
Dry – Static	2.477
Dry – Pseudo Static	1.181

Closure


The conclusions and recommendations contained in this memorandum which include professional opinions and judgments, are based on the information available to us at the time of our evaluation, the results of our field observations, our limited subsurface exploration and our understanding of the proposed site development. This memorandum was prepared in accordance with the generally accepted standard of practice at the time the report was written. No other warranty, expressed or implied, is made.

This memorandum was written for the exclusive use of Horrocks Engineers and only for the proposed project described herein. It is the Client's responsibility to see that all parties to the project including the Designer, Contractor, Subcontractors, etc. are made aware of this memorandum in its entirety. We are not responsible for the technical interpretations by others of the information described or documented in this memorandum. The use of information contained in this memorandum for bidding purposes should be done at the Contractor's option and risk.







Material Name	Color	Unit Weight (lbs/ft3)	Strength Type	Cohesion (psf)	Phi (deg)
Native	Yellow	120	Mohr-Coulomb	50	32
Embankment	Green	120	Mohr-Coulomb	50	33




Material Name	Color	Unit Weight (lbs/ft3)	Strength Type	Cohesion (psf)	Phi (deg)
Native	Yellow	120	Mohr-Coulomb	50	32
Embankment	Green	120	Mohr-Coulomb	50	33






Material Name	Color	Unit Weight (lbs/ft3)	Strength Type	Cohesion (psf)	Phi (deg)
Native	■	120	Mohr-Coulomb	50	32
Embankment	■	120	Mohr-Coulomb	50	33



Material Name	Color	Unit Weight (lbs/ft ³)	Strength Type	Cohesion (psf)	Phi (deg)
Native	■	120	Mohr-Coulomb	50	32
Embankment	■	120	Mohr-Coulomb	50	33



ATTACHMENT 6
COST ESTIMATES

**Basin 1 - Below Grade
Hillside Debris Basins**

Item	Description	Quantity	Units	Unit Cost	Cost
1	Mobilization	1	LS	----	\$200,190.00
2	15 Inch Storm Drain	0	LF	\$55.00	\$0.00
3	18 Inch Storm Drain	0	LF	\$60.00	\$0.00
4	21 Inch Storm Drain	0	LF	\$65.00	\$0.00
5	24 Inch Storm Drain	0	LF	\$70.00	\$0.00
6	30 Inch Storm Drain	300	LF	\$75.00	\$22,500.00
7	36 Inch Storm Drain		LF	\$95.00	\$0.00
8	42 Inch Storm Drain	0	LF	\$125.00	\$0.00
9	48 Inch Storm Drain	0	LF	\$155.00	\$0.00
10	Spillway Cut	9,087	CY	\$8.00	\$72,696.00
11	Spillway Structure and Riprap	1	EA	\$45,000.00	\$45,000.00
11	Outlet works	1	EA	\$35,000.00	\$35,000.00
12	Excavation (cut)	217,813	CY	\$8.00	\$1,742,504.00
13	Embankment (fill)	55	CY	\$0.00	\$0.00
14	Sediment Basin Additional Cut	0	CY	\$0.00	\$0.00
15	Liner/internal Cutoff Earthwork	0	CY	\$8.00	\$0.00
16	Manholes/Inlets/Structures	1	EA	\$8,000.00	\$8,000.00
17	Toe Drain	1	LS	\$55,000.00	\$55,000.00
18	Class "A" Road Repair	0	SF	\$6.00	\$0.00
19	Class "D" Field Repair	-	SF	\$0.25	\$0.00
20	Revegetation	21.2	Acres	\$1,000.00	\$21,200.00
21	Imported Fill	0	CY	\$10.00	\$0.00
22	Railroad and Canal Crossing	0	LS	\$108,000.00	\$0.00
23	State Road Crossing	0	LS	\$220,000.00	\$0.00
24	Traffic Control	0	LS	\$675.00	\$0.00
25	Utility Relocation (20% of pipe cost)	0	LS	\$4,500.00	\$0.00
Sub Total (Construction)					\$2,202,090.00
Contingencies		20%			\$440,418.00
Land		462,000	SF	\$2.00	\$924,000.00
Right of Way		-	SF	\$1.00	\$0.00
Total (Construction)					\$3,566,508.00
Environmental		0%			\$0.00
Design and Construction Engineering					\$440,418.00
Administration, Legal, and Bond Counsel					\$22,020.90
Total (Professional Services)					\$462,438.90
Grand Total					\$4,028,946.90

**Basin 3A - Below Grade
Hillside Debris Basins**

Item	Description	Quantity	Units	Unit Cost	Cost
1	Mobilization	1	LS	----	\$43,191.90
2	15 Inch Storm Drain	0	LF	\$55.00	\$0.00
3	18 Inch Storm Drain	0	LF	\$60.00	\$0.00
4	21 Inch Storm Drain	0	LF	\$65.00	\$0.00
5	24 Inch Storm Drain	0	LF	\$70.00	\$0.00
6	30 Inch Storm Drain	300	LF	\$75.00	\$22,500.00
7	36 Inch Storm Drain	0	LF	\$95.00	\$0.00
8	42 Inch Storm Drain	0	LF	\$125.00	\$0.00
9	48 Inch Storm Drain	0	LF	\$155.00	\$0.00
10	Trench Earthwork	0	LF	\$0.00	\$0.00
11	Spillway	1	EA	\$35,000.00	\$35,000.00
12	Outlet works	1	EA	\$20,000.00	\$20,000.00
13	Excavation (cut)	39836	CY	\$ 8.00	\$318,688.00
14	Embankment (fill)	0	CY	\$0.00	\$0.00
15	Imported Fill	0	CY	\$9.00	\$0.00
16	Cutoff Excavation and Backfill	0	CY	\$10.00	\$0.00
17	Sediment Basin Additional Cut	0	CY	\$5.00	\$0.00
18	Toe Drain	1	LS	\$25,000.00	\$25,000.00
19	Manholes/Inlets/Structures	1	EA	\$6,500.00	\$6,500.00
20	Class "A" Road Repair	0	SF	\$6.00	\$0.00
21	Class "D" Field Repair	3,150	SF	\$0.25	\$787.50
22	Revegetation	3.44	Acre	\$1,000.00	\$3,443.53
23	Railroad and Canal Crossing	0	LS	\$108,000.00	\$0.00
24	State Road Crossing	0	LS	\$220,000.00	\$0.00
25	Traffic Control	0	LS	\$675.00	\$0.00
	Utility Relocation (20% of pipe cost)	0	LS	\$4,500.00	\$0.00
Sub Total (Construction)					\$475,110.93
	Contingencies	20%			\$95,022.19
	Land	150,000	SF	\$2.00	\$300,000.00
	Right of Way	-	SF	\$1.00	\$0.00
Total (Construction)					\$870,133.11
	Environmental	0%			\$0.00
Design and Construction Engineering					\$95,022.19
Administration, Legal, and Bond Counsel					\$4,751.11
Total (Professional Services)					\$99,773.30
Grand Total					\$969,906.41

Basin 4 - Above Grade, Single Watershed (4E)

Hillside Debris Basins

Item	Description	Quantity	Units	Unit Cost	Cost
1	Mobilization	1	LS	----	\$80,308.99
2	15 Inch Storm Drain	0	LF	\$55.00	\$0.00
3	18 Inch Storm Drain	0	LF	\$60.00	\$0.00
4	21 Inch Storm Drain	0	LF	\$65.00	\$0.00
5	24 Inch Storm Drain	0	LF	\$70.00	\$0.00
6	30 Inch Storm Drain	200	LF	\$75.00	\$15,000.00
7	36 Inch Storm Drain	0	LF	\$95.00	\$0.00
8	42 Inch Storm Drain	0	LF	\$125.00	\$0.00
9	48 Inch Storm Drain		LF	\$155.00	\$0.00
10	60 Inch Pipe or Box Culvert (from upstream channel)	550	LF	\$250.00	\$137,500.00
11	Spillway Cut	8500	CY	\$6.00	\$51,000.00
12	Spillway Structure and Riprap	1	EA	\$50,000.00	\$50,000.00
13	Outlet works	1	EA	\$30,000.00	\$30,000.00
14	Excavation (cut)	67050	CY	\$6.00	\$402,300.00
15	Embankment (fill)	26600	CY	\$0.00	\$0.00
16	Imported Fill	0	CY	\$9.00	\$0.00
17	Cutoff Excavation and Fill	6028	CY	\$10.00	\$60,280.00
18	Sediment Basin Additional Cut	0	CY	\$5.00	\$0.00
19	Manholes/Inlets/Structures	1	EA	\$8,000.00	\$8,000.00
20	Toe Drain	1	EA	\$40,000.00	\$40,000.00
21	Class "A" Road Repair	0	SF	\$6.00	\$0.00
22	Class "D" Field Repair	-	SF	\$0.25	\$0.00
23	Revegetation	8	Acre	\$1,000.00	\$8,034.89
24	Imported Backfill	0	TON	\$12.00	\$0.00
25	Railroad and Canal Crossing	0	LS	\$108,000.00	\$0.00
26	State Road Crossing	0	LS	\$220,000.00	\$0.00
27	Traffic Control	1	LS	\$225.00	\$225.00
28	Utility Relocation (5% of pipe cost)	1	LS	\$750.00	\$750.00
Sub Total (Construction)					\$883,398.88
Contingencies		20%			\$176,679.78
Land		350,000	SF	\$2.00	\$700,000.00
Right of Way		-	SF	\$1.00	\$0.00
Total (Construction)					\$1,760,078.66
Environmental		0%			\$0.00
Design and Construction Engineering		20%			\$176,679.78
Administration, Legal, and Bond Counsel		1%			\$8,833.99
Total (Professional Services)					\$185,513.77
Grand Total					\$1,945,592.43

**Basin 5 (Below/hybrid)
Hillside Debris Basins**

Item	Description	Quantity	Units	Unit Cost	Cost			
1	Mobilization	1	LS	----	\$193,505.00			
2	15 Inch Storm Drain	0	LF	\$55.00	\$0.00			
3	18 Inch Storm Drain	0	LF	\$60.00	\$0.00			
4	21 Inch Storm Drain	0	LF	\$65.00	\$0.00			
5	24 Inch Storm Drain	0	LF	\$70.00	\$0.00			
6	30 Inch Storm Drain	200	LF	\$75.00	\$15,000.00			
7	36 Inch Storm Drain	0	LF	\$95.00	\$0.00			
8	42 Inch Storm Drain	0	LF	\$125.00	\$0.00			
9	48 Inch Storm Drain	0	LF	\$155.00	\$0.00			
10	Spillway and Channel Cut	23000	CY	\$8.00	\$184,000.00			
11	Spillway Structure and Riprap	1	EA	\$50,000.00	\$50,000.00			
12	Outlet works	1	EA	\$35,000.00	\$35,000.00			
13	Excavation (cut)	197100	CY	\$8.00	\$1,576,800.00			
14	Embankment (fill)	150	CY	\$0.00	\$0.00			
15	Imported Fill		CY	\$9.00	\$0.00			
16	Cutoff Excavation and Fill	1100	CY	\$20.00	\$22,000.00			
17	Sediment Basin Additional Cut	0	CY	\$5.00	\$0.00			
18	Manholes/Inlets/Structures	1	EA	\$6,500.00	\$6,500.00			
19	Toe Drain	1	EA	\$45,000.00	\$45,000.00			
20	Class "A" Road Repair	0	SF	\$6.00	\$0.00			
21	Class "D" Field Repair	-	SF	\$0.25	\$0.00			
22	Revegetation	-	Acre	\$1,000.00	\$0.00			
22	Imported Backfill	0	TON	\$12.00	\$0.00			
23	Railroad and Canal Crossing	0	LS	\$108,000.00	\$0.00			
24	State Road Crossing	0	LS	\$220,000.00	\$0.00			
25	Traffic Control	0	LS	\$450.00	\$0.00			
26	Utility Relocation (5% of pipe cost)	1	LS	\$750.00	\$750.00			
Sub Total (Construction)					\$2,128,555.00			
Contingencies					20%	\$425,711.00		
Land					SF	\$2.00	\$0.00	
Right of Way*					581,000	SF	\$0.10	\$58,100.00
Total (Construction)						\$2,612,366.00		
Environmental					0%	\$0.00		
Design and Construction Engineering					20%	\$425,711.00		
Administration, Legal, and Bond Counsel					1%	\$21,285.55		
Total (Professional Services)						\$446,996.55		
Grand Total						\$3,059,362.55		

*Administrative costs, based on land swap with the Forest Service

**Basin 6
Hillside Debris Basins**

Item	Description	Quantity	Units	Unit Cost	Cost			
1	Mobilization	1	LS	----	\$95,868.72			
2	15 Inch Storm Drain	0	LF	\$55.00	\$0.00			
3	18 Inch Storm Drain	0	LF	\$60.00	\$0.00			
4	21 Inch Storm Drain	0	LF	\$65.00	\$0.00			
5	24 Inch Storm Drain	0	LF	\$70.00	\$0.00			
6	30 Inch Storm Drain	350	LF	\$75.00	\$26,250.00			
7	36 Inch Storm Drain	0	LF	\$95.00	\$0.00			
8	42 Inch Storm Drain	0	LF	\$125.00	\$0.00			
9	48 Inch Storm Drain	0	LF	\$155.00	\$0.00			
10	Spillway Cut	12560	EA	\$6.00	\$75,360.00			
11	Spillway Structure and Riprap	1	EA	\$50,000.00	\$50,000.00			
12	Outlet works	1	EA	\$35,000.00	\$35,000.00			
13	Excavation (cut)	89100	CY	\$6.00	\$534,600.00			
14	Embankment (fill)	29091	CY	\$0.00	\$0.00			
15	Imported Fill	6209	CY	\$10.00	\$62,088.40			
16	Cutoff Excavation and Fill	6193	CY	\$10.00	\$61,930.00			
17	Sediment Basin Additional Cut	0	CY	\$5.00	\$0.00			
18	Toe Drain	1	EA	\$45,000.00	\$45,000.00			
19	Manholes/Inlets/Structures	2	EA	\$8,000.00	\$16,000.00			
20	Class "A" Road Repair	0	SF	\$6.00	\$0.00			
21	Class "D" Field Repair	3,675	SF	\$0.25	\$918.75			
22	Revegetation	9.04	Acre	\$1,000.00	\$9,045.00			
22	Imported Backfill	3476	TON	\$12.00	\$41,707.56			
23	Railroad and Canal Crossing	0	LS	\$108,000.00	\$0.00			
24	State Road Crossing	0	LS	\$220,000.00	\$0.00			
25	Traffic Control	1	LS	\$787.50	\$787.50			
26	Utility Relocation (20% of pipe cost)	0	LS	\$5,250.00	\$0.00			
Sub Total (Construction)					\$1,054,555.93			
Contingencies					20%	\$210,911.19		
Land					394,000	SF	\$2.00	\$788,000.00
Right of Way					-	SF	\$1.00	\$0.00
Total (Construction)								\$2,053,467.12
Environmental					0%			\$0.00
Design and Construction Engineering					20%			\$210,911.19
Administration, Legal, and Bond Counsel					1%			\$10,545.56
Total (Professional Services)								\$221,456.75
Grand Total								\$2,274,923.86

ATTACHMENT 7
CPA-52 ENVIRONMENTAL EVALUATION

U.S. Department of Agriculture Natural Resources Conservation Service ENVIRONMENTAL EVALUATION WORKSHEET		NRCS-CPA-52 6/2010		A. Client Name: Santaquin City, Utah			
D. Client's Objective(s) (purpose): The purpose of the project is to prevent flooding and debris flow from storm events in the hills above Santaquin.		B. Conservation Plan ID # (as applicable): Santaquin Storm Drain Program Authority (optional): WFPO Program 2017 Funding					
E. Need for Action: Wildfires in 2001 led to debris flows in 2002 and later in the hills above Santaquin. These debris flows have impacted residences and other public infrastructure. The need of the project is to prevent further debris flows.		G. Alternatives					
		No Action <input type="checkbox"/> if RMS		Alternative 1 <input type="checkbox"/> if RMS			
		Typical maintenance of existing storm drainage facilities will be continued		The project will construct five debris/water retention basins as well as installing pipelines and/or ditches to carry stormwater away from the hillsides to a safe outfall.			
				Alternative 2 <input type="checkbox"/> if RMS			
				The project will construct three debris/water retention basins as well as installing pipelines and/or ditches to carry stormwater away from the hillsides to a safe outfall.			
Resource Concerns							
In Section "F" below, analyze, record, and address concerns identified through the Resources Inventory process. (See FOTG Section III - Resource Quality Criteria for guidance).							
F. Resource Concerns and Existing / Benchmark Conditions (Analyze and record the existing/benchmark conditions for each identified concern)		H. Effects of Alternatives					
		No Action		Alternative 1		Alternative 2	
		Amount, Status, Description (short and long term)		Amount, Status, Description (short and long term)		Amount, Status, Description (short and long term)	
		<input type="checkbox"/> if does NOT meet QC		<input type="checkbox"/> if does NOT meet QC		<input type="checkbox"/> if does NOT meet QC	
SOIL							
Erosion (Streambank) Erosion is not a concern for the project.		Streambank erosion is not expected.		No erosional impacts are expected.		No erosional impacts are expected.	
		<input type="checkbox"/> NOT meet		<input type="checkbox"/> NOT meet		<input type="checkbox"/> NOT meet	
		QC		QC		QC	
Erosion (Sheet and Rill) Erosion and debris flows are major concerns.		Heavy storm events may cause additional debris flows near and through residential neighborhoods in eastern Santaquin.		The threat of debris flows will be greatly lessened through control of storm water.		The threat of debris flows will be greatly lessened through control of storm water. Two areas where debris flows have not yet, but could in the future, occur would not be protected.	
		<input type="checkbox"/> NOT meet		<input type="checkbox"/> NOT meet		<input type="checkbox"/> NOT meet	
		QC		QC		QC	
WATER							
Quantity (Excessive Runoff, Flooding, or Ponding) Excessive runoff and flooding is currently an issue in the project area.		Heavy storm events may cause additional flooding and/or debris flows near and through residential neighborhoods in eastern Santaquin.		The project will allow the capture of water and its diversion to a safe outfall.		The project will allow the capture of water and its diversion to a safe outfall.	
		<input type="checkbox"/> meet		<input type="checkbox"/> meet		<input type="checkbox"/> meet	
		QC		QC		QC	
Quality (Surface Water: Excessive Susp. Sedmt & Turbidity) There are no impaired waters in the study area.		No changes in water quality are expected.		No changes in water quality are expected.		No changes in water quality are expected.	
		<input type="checkbox"/> NOT meet		<input type="checkbox"/> NOT meet		<input type="checkbox"/> NOT meet	
		QC		QC		QC	

F. Resource Concerns and Existing / Benchmark Conditions (Analyze and record the existing/benchmark conditions for each identified concern)	H. (continued)					
	No Action		Alternative 1		Alternative 2	
	Amount, Status, Description (short and long term)	√ if does NOT meet QC	Amount, Status, Description (short and long term)	√ if does NOT meet QC	Amount, Status, Description (short and long term)	√ if does NOT meet QC
AIR Quality (Particulate Matter < 10µm diameter ("PM 10")) No Effect	No Effect	NOT meet <input type="checkbox"/> QC	Short term: fugitive dust expected during construction activities; Long term: no effect	NOT meet <input type="checkbox"/> QC	Short term: fugitive dust expected during construction activities; Long term: no effect	NOT meet <input type="checkbox"/> QC
PLANTS Other Vegetation consists primarily of low sage, bunch grasses, and Gambel oak.	No effect.	<input type="checkbox"/> meet QC	Short term: Removal of some vegetation during construction activities. Long term: some areas would be converted to debris/retention basins.	<input type="checkbox"/> meet QC	Short term: Removal of some vegetation during construction activities. Long term: some areas would be converted to debris/retention basins.	<input type="checkbox"/> meet QC
Condition (Noxious and Invasive Plants) Utah County uses the Utah State Noxious Weed list.	No change to existing management policies.	NOT meet <input type="checkbox"/> QC	Short term: Disturbed areas would be temporarily exposed to some invasive weed growth. Long term: No effect.	NOT meet <input type="checkbox"/> QC	Short term: Disturbed areas would be temporarily exposed to some invasive weed growth. Long term: No effect.	NOT meet <input type="checkbox"/> QC
ANIMALS Fish and wildlife (Impacts to Endangered or Threatened Animals) State listed threatened or endangered species: Canada lynx, yellow-billed cuckoo, June sucker. (Ref. IPaC, accessed 17Aug17)	No effect.	<input type="checkbox"/> NOT meet QC	There is no critical habitat for any state sensitive species in the project area or proximity.	<input type="checkbox"/> NOT meet QC	There is no critical habitat for any state sensitive species in the project area or proximity.	<input type="checkbox"/> NOT meet QC
HUMAN - Economic and Social Considerations						
Public Health and Safety Debris flows and flooding threaten health and safety of area residents.	Residential neighborhoods will continue to be threatened by flooding and debris flows.		The threat of flooding and debris flows will be greatly reduced.		The threat of flooding and debris flows will be greatly reduced.	

Special Environmental Concerns: Environmental Laws, Executive Orders, policies, etc.						
In Section "I" complete and attach applicable Environmental Procedures Guide Sheets for documentation. Items with a "*" may require a federal permit or consultation/coordination between the lead agency and another government agency. In these cases, effects may need to be determined in consultation with another agency. Planning and practice implementation may proceed for practices not involved in consultation.						
I. Special Environmental Concerns (Document compliance with Environmental Laws, Executive Orders, policies, etc.)	J. Impacts to Special Environmental Concerns					
	No Action Status and progress of compliance. (Complete and attach Guide Sheets as applicable)		Alternative 1 Status and progress of compliance. (Complete and attach Guide Sheets as applicable)		Alternative 2 Status and progress of compliance. (Complete and attach Guide Sheets as applicable)	
		√ if needs further action		√ if needs further action		√ if needs further action
•Clean Air Act No effect.	Upon Review, No Action Needed	<input type="checkbox"/>	Upon Review, No Effect	<input type="checkbox"/>	Upon Review, No Effect	<input type="checkbox"/>
•Clean Water Act / Waters of the U.S.	Upon Review, No Action Needed	<input type="checkbox"/>	Upon Review, No Effect	<input type="checkbox"/>	Upon Review, No Effect	<input type="checkbox"/>
•Coastal Zone Management	Upon Review, Not Applicable	<input type="checkbox"/>	Upon Review, Not Applicable	<input type="checkbox"/>	Upon Review, Not Applicable	<input type="checkbox"/>
Coral Reefs	Upon Review, Not Applicable	<input type="checkbox"/>	Upon Review, Not Applicable	<input type="checkbox"/>	Upon Review, Not Applicable	<input type="checkbox"/>
•Cultural Resources / Historic Properties	Upon Review, No Effect	<input type="checkbox"/>	Other Two non-eligible historic trash scatters have been previously recorded near one of the pipelines. A pipeline would also cross 42UT473, the Strawberry Highline Canal.	<input checked="" type="checkbox"/>	Other Two non-eligible historic trash scatters have been previously recorded near one of the pipelines. A pipeline would also cross 42UT473, the Strawberry Highline Canal.	<input type="checkbox"/>
•Endangered and Threatened Species	See Attached Documentation	<input type="checkbox"/>	Upon Review, No Effect There is no critical habitat for any state sensitive species in the project area or proximity.	<input checked="" type="checkbox"/>	Upon Review, No Effect There is no critical habitat for any state sensitive species in the project area or proximity.	<input checked="" type="checkbox"/>
Environmental Justice	Upon Review, No Action Needed	<input type="checkbox"/>	Upon Review, Not Present	<input type="checkbox"/>	Upon Review, Not Present	<input type="checkbox"/>
•Essential Fish Habitat	Upon Review, Not Applicable	<input type="checkbox"/>	Upon Review, Not Applicable	<input type="checkbox"/>	Upon Review, Not Applicable	<input type="checkbox"/>
Floodplain Management	Upon Review, Not Applicable	<input type="checkbox"/>	Upon Review, No Effect There is no flood map printed for the project area.	<input type="checkbox"/>	Upon Review, No Effect There is no flood map printed for the project area.	<input type="checkbox"/>
Invasive Species	Upon Review, No Effect There would be no change to invasive species.	<input type="checkbox"/>	Other Disturbed areas will be replanted-reseeded per agency consult.	<input checked="" type="checkbox"/>	Other Disturbed areas will be replanted-reseeded per agency consult.	<input type="checkbox"/>
•Migratory Birds/Bald and Golden Eagle Protection Act	Upon Review, No Action Needed	<input type="checkbox"/>	Upon Review, No Action Needed The IpAC database has shown the potential for migratory birds to be present; however, any removal of mature trees or shrubs during the bird nesting season (Feb 1- Aug31) would be surveyed prior by a qualified biologist. If any nesting birds are in the area or its proximity, USFWS guidance on temporal and spatial buffers will be followed.	<input type="checkbox"/>	Upon Review, No Action Needed The IpAC database has shown the potential for migratory birds to be present; however, any removal of mature trees or shrubs during the bird nesting season (Feb 1- Aug31) would be surveyed prior by a qualified biologist. If any nesting birds are in the area or its proximity, USFWS guidance on temporal and spatial buffers will be followed.	<input type="checkbox"/>
Prime and Unique Farmlands No effect	Upon Review, Not Applicable	<input type="checkbox"/>	Upon Review, Not Applicable	<input type="checkbox"/>	Upon Review, Not Applicable	<input type="checkbox"/>
Riparian Area	Upon Review, Not Present	<input type="checkbox"/>	Upon Review, Not Present	<input type="checkbox"/>	Upon Review, Not Present	<input type="checkbox"/>
•Wetlands No effect	Upon Review, Not Present	<input type="checkbox"/>	Upon Review, Not Present	<input type="checkbox"/>	Upon Review, Not Present	<input type="checkbox"/>
•Wild and Scenic Rivers Virgin River is the only designated Wild & Scenic River in Utah.	Upon Review, Not Applicable	<input type="checkbox"/>	Upon Review, Not Applicable	<input type="checkbox"/>	Upon Review, Not Applicable	<input type="checkbox"/>
K. Other Agencies and Broad Public Concerns	No Action		Alternative 1		Alternative 2	
Easements, Permissions, Public Review, or Permits Required and Agencies Consulted.	None needed		USFWS: T&E species; UDWATER: Stream Alt Permit; SHPO: Cultural Resources. Native American consultation. ACOE 401 WQ/NPDES Cert. To be completed before construction.			

K. (continued) Other Agencies and Broad Public Concerns		No Action	Alternative 1	Alternative 2																											
Cumulative Effects Narrative (Describe the cumulative impacts considered, including past, present and known future actions regardless of who performed the actions)		Residential areas will continue to be threatened by debris flow and flooding, potentially leading to lower property values and increased danger.	Residential areas will be safer from debris flows and flooding.																												
L. Mitigation		None																													
M. Preferred Alternative	√ preferred alternative	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>																											
	Supporting reason	Does not fit the purpose and need for EWP.	Consistent with WFPO program as it provides for flood protection.	Consistent with WFPO program as it provides for flood protection.																											
N. Context (Record context of alternatives analysis)		local	local	local																											
The significance of an action must be analyzed in several contexts such as society as a whole (human, national), the affected region, the affected interests, and the locality.																															
O. Determination of Significance or Extraordinary Circumstances Intensity: Refers to the severity of impact. Impacts may be both beneficial and adverse. A significant effect may exist even if the Federal agency believes that on balance the effect will be beneficial. Significance cannot be avoided by terming an action temporary or by breaking it down into small component parts. If you answer ANY of the below questions "yes" then contact the State Environmental Liaison as there may be extraordinary circumstances and significance issues to consider and a site specific NEPA analysis may be required.																															
<table border="0"> <thead> <tr> <th>Yes</th> <th>No</th> <th></th> </tr> </thead> <tbody> <tr> <td><input type="checkbox"/></td> <td><input checked="" type="checkbox"/></td> <td>• Is the preferred alternative expected to cause significant effects on public health or safety?</td> </tr> <tr> <td><input type="checkbox"/></td> <td><input checked="" type="checkbox"/></td> <td>• Is the preferred alternative expected to significantly effect unique characteristics of the geographic area such as proximity to historic or cultural resources, park lands, prime farmlands, wetlands, wild and scenic rivers, or ecologically critical areas?</td> </tr> <tr> <td><input type="checkbox"/></td> <td><input checked="" type="checkbox"/></td> <td>• Are the effects of the preferred alternative on the quality of the human environment likely to be highly controversial?</td> </tr> <tr> <td><input type="checkbox"/></td> <td><input checked="" type="checkbox"/></td> <td>• Does the preferred alternative have highly uncertain effects or involve unique or unknown risks on the human environment?</td> </tr> <tr> <td><input type="checkbox"/></td> <td><input checked="" type="checkbox"/></td> <td>• Does the preferred alternative establish a precedent for future actions with significant impacts or represent a decision in principle about a future consideration?</td> </tr> <tr> <td><input type="checkbox"/></td> <td><input checked="" type="checkbox"/></td> <td>• Is the preferred alternative known or reasonably expected to have potentially significant environment impacts to the quality of the human environment either individually or cumulatively over time?</td> </tr> <tr> <td><input type="checkbox"/></td> <td><input checked="" type="checkbox"/></td> <td>• Will the preferred alternative likely have a significant adverse effect on ANY of the special environmental concerns? Use the Evaluation Procedure Guide Sheets to assist in this determination. This includes, but is not limited to, concerns such as cultural or historical resources, endangered and threatened species, environmental justice, wetlands, floodplains, coastal zones, coral reefs, essential fish habitat, wild and scenic rivers, clean air, riparian areas, natural areas, and invasive species.</td> </tr> <tr> <td><input type="checkbox"/></td> <td><input checked="" type="checkbox"/></td> <td>• Will the preferred alternative threaten a violation of Federal, State, or local law or requirements for the protection of the environment?</td> </tr> </tbody> </table>					Yes	No		<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Is the preferred alternative expected to cause significant effects on public health or safety?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Is the preferred alternative expected to significantly effect unique characteristics of the geographic area such as proximity to historic or cultural resources, park lands, prime farmlands, wetlands, wild and scenic rivers, or ecologically critical areas?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Are the effects of the preferred alternative on the quality of the human environment likely to be highly controversial?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Does the preferred alternative have highly uncertain effects or involve unique or unknown risks on the human environment?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Does the preferred alternative establish a precedent for future actions with significant impacts or represent a decision in principle about a future consideration?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Is the preferred alternative known or reasonably expected to have potentially significant environment impacts to the quality of the human environment either individually or cumulatively over time?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Will the preferred alternative likely have a significant adverse effect on ANY of the special environmental concerns? Use the Evaluation Procedure Guide Sheets to assist in this determination. This includes, but is not limited to, concerns such as cultural or historical resources, endangered and threatened species, environmental justice, wetlands, floodplains, coastal zones, coral reefs, essential fish habitat, wild and scenic rivers, clean air, riparian areas, natural areas, and invasive species.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Will the preferred alternative threaten a violation of Federal, State, or local law or requirements for the protection of the environment?
Yes	No																														
<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Is the preferred alternative expected to cause significant effects on public health or safety?																													
<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Is the preferred alternative expected to significantly effect unique characteristics of the geographic area such as proximity to historic or cultural resources, park lands, prime farmlands, wetlands, wild and scenic rivers, or ecologically critical areas?																													
<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Are the effects of the preferred alternative on the quality of the human environment likely to be highly controversial?																													
<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Does the preferred alternative have highly uncertain effects or involve unique or unknown risks on the human environment?																													
<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Does the preferred alternative establish a precedent for future actions with significant impacts or represent a decision in principle about a future consideration?																													
<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Is the preferred alternative known or reasonably expected to have potentially significant environment impacts to the quality of the human environment either individually or cumulatively over time?																													
<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Will the preferred alternative likely have a significant adverse effect on ANY of the special environmental concerns? Use the Evaluation Procedure Guide Sheets to assist in this determination. This includes, but is not limited to, concerns such as cultural or historical resources, endangered and threatened species, environmental justice, wetlands, floodplains, coastal zones, coral reefs, essential fish habitat, wild and scenic rivers, clean air, riparian areas, natural areas, and invasive species.																													
<input type="checkbox"/>	<input checked="" type="checkbox"/>	• Will the preferred alternative threaten a violation of Federal, State, or local law or requirements for the protection of the environment?																													
P. The information recorded above is based on the best available information: In the case where a non-NRCS person (i.e. a TSP) assists with planning they are to sign the first signature block and then NRCS is to sign the second block as the responsible federal agency for the planning action.																															
_____ Signature (TSP if applicable)		_____ Title		_____ Date																											
_____ Signature (NRCS)		_____ Title		_____ Date																											

The following sections are to be completed by the Responsible Federal Official (RFO)

Q. NEPA Compliance Finding (check one)		Action required
The preferred alternative:		
<input type="checkbox"/>	1) is not a federal action where the agency has control or responsibility.	Document in "R.1" below. No additional analysis is required
<input type="checkbox"/>	2) is a federal action that is categorically excluded from further environmental analysis and there are no extraordinary circumstances .	Document in "R.2" below. No additional analysis is required
<input type="checkbox"/>	3) is a federal action that has been sufficiently analyzed in an existing Agency state, regional, or national NEPA document and there are no predicted <u>significant adverse environmental effects</u> or extraordinary circumstances .	Document in "R.1" below. No additional analysis is required.
<input type="checkbox"/>	4) is a federal action that has been sufficiently analyzed in another Federal agency's NEPA document (EA or EIS) that addresses the proposed NRCS action and its' effects and has been formally adopted by NRCS . NRCS is required to prepare and publish the agency's own Finding of No Significant Impact for an EA or Record of Decision for an EIS when adopting another agency's EA or EIS document. Note: This box is not applicable to FSA.	Contact the State Environmental Liaison for list of NEPA documents formally adopted and available for tiering. Document in "R.1" below. No additional analysis is required
<input type="checkbox"/>	5) is a federal action that has NOT been sufficiently analyzed or may involve predicted significant adverse environmental effects or extraordinary circumstances and may require an EA or EIS.	Contact the State Environmental Liaison. Further NEPA analysis required.

R. Rationale Supporting the Finding

R.1 Findings Documentation	
R.2 Applicable Categorical Exclusion(s) (more than one may apply)	

I have considered the effects of the alternatives on the Resource Concerns, Economic and Social Considerations, Special Environmental Concerns, and Extraordinary Circumstances as defined by Agency regulation and policy.

S. Signature of Responsible Federal Official:

Signature	Title	Date

Additional notes

Instructions for Completing the Environmental Evaluation Worksheet (Form NRCS-CPA-52),

INTRODUCTION

The Environmental Evaluation (EE) is “a concurrent part of the planning process in which the potential long-term and short-term impacts of an action on people, their physical surroundings, and nature are evaluated and alternative actions explored” (NPPH-Amendment 4, March 2003). This form provides for the documentation of that part of the planning process, and was designed to assist the conservation planner with compliance requirements for applicable Federal laws, regulations, Executive Orders, and policy. The form also provides a framework for documenting compliance with applicable State and local requirements.

NRCS is required to conduct an EE on all actions to determine if there is a need for an Environmental Assessment (EA) or an Environmental Impact Statement (EIS). The EE process results in a "Finding" or conclusion (see guidance for "Q" below) that, either further NEPA analysis is required (EA or EIS) or that no EA or EIS is required because: 1) There is no federal action; 2) The action is categorically excluded; or 3) There is an existing NRCS or NRCS-adopted NEPA document that has sufficiently analyzed the effects of this action. The EE applies to all assistance provided by NRCS (GM190, Part 410.5). The CPA-52 form is used by NRCS to document the results of the evaluation and show compliance with NRCS regulations implementing NEPA at 7 CFR Part 650.

A copy of the NRCS-CPA-52 must be included in the administrative file. Supporting documentation, including the applicable Special Environmental Concerns Evaluation Procedure Guide Sheets, must be retained and should be included with the NRCS-CPA-52 to relay specific compliance information.

Attach additional sheets or assistance notes if more documentation space is needed beyond the form NRCS-CPA-52, including any state-specific worksheets.

COMPLETING THE NRCS-CPA-52

A. Client Name

B. Conservation Plan ID # (as applicable)

Program Authority (optional): Identifying the program authority (EQIP, WRP, etc.) can help lead the planner to the appropriate NRCS NEPA document the planner may tier to as addressed later in section "R. Rational Supporting the Finding".

C. Identification #: Record any other relevant client identification # (farm, tract, field #, etc.).

D. Client's Objective(s) (purpose): Briefly summarize the client's stated objective(s) [synonymous to "Purpose" under NEPA]. Refer to Step 2 of the NRCS planning process found in the NPPH, Part 600.22 for help, if needed. "Purpose" refers to a goal being pursued in the process of meeting the "Need", such as keeping the operation economically viable or meeting TMDL requirements. Clearly articulated purposes become the decision factors used to decide between the action alternatives.

E. Need for Action: Describe the underlying need being met. Why is the action being proposed? The underlying need will define and shape the alternatives; therefore it is important to accurately articulate the need(s) based on the identified resource concerns and the landowner objectives. The chosen alternative should clearly address the underlying need(s). A "need" is usually the improvement of the condition of a natural resource(s), for example the quality of runoff water from a farm does not meet State standards, or inadequate forage supply and/or grazing strategies are resulting in poor livestock performance. Use information from Step 3 of the Conservation Planning Process (Resource Inventory) to help define the need. Identify here which Resource Concerns need to be addressed in the plan.

F. Resource Concerns and Existing / Benchmark Conditions:

Resource Concerns Analyze and record resource concerns from the current list in your state's eFOTG Section III that have been identified through the Resources Inventory process as a concern that needs to be addressed. The Resource Quality Criteria will also be helpful in considering potential environmental effects and comparing alternatives. Include all resource concerns that apply, adding additional sheets as necessary.

Documenting Existing/Benchmark Conditions Analyze and record the existing (benchmark) conditions for each relevant concern using state-specific tools and protocols available. For example, "the current soil erosion rate = 6T" (or note where this information can be found in the conservation plan). This information will inform the final decision by allowing a comparative effects analysis of all alternatives (including the "no action" alternative). (Note: States often choose to include protocols here to assist the field planner with identification and descriptions of Resource Concerns, as well as other state-specific worksheets.) Optional: If desired, planners can include specific land use designations here.

Human - Economic and Social Considerations Below are some examples for what to consider when addressing the Human - Economic and Social Considerations.

Land use:

- Is the present land use suitable for the proposed alternative?
- Will land use change after practice(s) installation?
- How will a change affect the operation? (e.g., Feed and Forage Balance Sheet)
- Will the action affect resources on which people depend for subsistence, employment or recreation?
- Will land be taken in or out of production?

Capital:

- Does the producer have the funds or ability to obtain the funds needed to implement the proposed alternative?
- What are the impacts of the cost of the initial investment for this alternative?
- What are the impacts of any additional annual costs for Operation and Maintenance?
- What possible impact does implementing this alternative have on the client's future eligibility for farm programs?

Labor:

- Does the client understand the amount and kind of labor needed to implement, operate and maintain the proposed practice(s)?
- Does the client have the skills and time to carry out the conservation practice(s) or will they have to hire someone?

Management level:

- Does the client understand the inputs needed to manage the practice(s) and the client's responsibility in obtaining these inputs?
- Does the client understand their responsibility to maintain practice(s) as planned and implemented?
- Is it necessary for the client to obtain additional education, or hire a technical consultant, to operate and/or maintain the practice(s)?

Profitability:

- Profitability describes the relative benefits and costs of the farm or ranch operation, and is often measured in dollars. An activity is profitable if the benefits are greater than the costs.
- Is the proposed alternative needed and feasible?
- Do the benefits of improving the current operation outweigh the installation and maintenance costs (positive benefit/cost ratio)?
- Is there a reasonable expectation of long-term profitability/benefits for the operation if implemented?
- Will crop, livestock, or wildlife yield increase/decrease?

Risk:

- Adverse risk is the potential for monetary loss, physical injury, or damage to resources or the environment.
- Will the proposed alternative aid/risk client participation in USDA programs?
- What are the possible impacts due to a change in yield?
- Is there flexibility in modifying the conservation plan at a future date?
- What issues are involved with the timing of installation and maintenance?
- What are the cash flow requirements of this alternative?
- What, if any, are the hazards involved?

Public Health and Safety:

- What effect (both positive or negative) will the action have on the client and community with regard to public health and safety?
- What are the off-site effects?

- G. Alternatives: Describe Alternatives** Briefly summarize the practice/system of practices being proposed. The no action and RMS alternatives are required. (NPPH Part 600.41) Alternatives should be formulated to *meet the underlying need*. Note that the no action alternative may not meet the underlying need and is still required to be evaluated and compared to other alternatives (see below). To the extent possible, the alternatives should also prevent additional problems from occurring and take advantage of available opportunities. *If there are unresolved conflicts concerning alternative uses of resources, appropriate alternatives that meet the underlying need must be developed.*

"No Action": Include a brief summary of the activities that would be implemented in the absence of USDA assistance (financial or technical). Unless a change in management direction or intensity will be undertaken, record effects of existing activities. The "No Action" alternative requires the same level of analysis as other alternatives. It should answer the question of what impacts are likely to occur (or what the predicted future condition of the identified resource concerns might be) under the landowner's current and planned management strategies without implementation of a federally assisted action.

"Alternatives 1,2,etc.": List here the practices or system of practices being proposed for each alternative. At least one of the alternatives should contain the practices that NRCS has determined best address all of the identified resource concerns (i.e., RMS alternative). Indicate if the alternative meets RMS criteria based on your State's requirements. One or more other alternatives may be evaluated to aid in the decision-making process or at the request of the client. Use additional sheets if necessary.

Under guidance in the NPPH Part 600.11(f) and the GM 180 Part 409.1(a)(2), at least one alternative that meets RMS criteria should be developed, evaluated, and discussed with the client.

It is important to define the differences between each alternative, including the "No Action" alternative. See "Helpful Tips" in the NECH, Part 610.67 for guidance on narrowing the scope of your analysis when considering alternatives.

H. Effects of Alternatives:

Under "Amount, Status, Description", record the effect of each alternative on the concerns listed, quantifying where possible. *It is important to consider and document both short-term and long-term consequences, as appropriate, for direct, indirect, and cumulative effects (described below)*. If a change to the concern is predicted, then estimate the amount. Professional judgement should be used where Quality Criteria or other tools are not available.

Analyze effects based on the combined effect of all practices on the resource concern. For example, if one proposed practice may impact the water quality of an adjacent stream, but another proposed practice such as a buffer may reduce or eliminate the impact, the overall effect is the one that should be recorded here. As mentioned above, one or more "Other Alternative(s)" may be evaluated to aid in the decision-making process or at the request of the client. Use additional sheets if necessary.

"No Action": Record the impacts that are likely to occur (or what the predicted future condition of the identified resource concerns might be) under the landowner's planned management strategies without implementation of a federally assisted action. Address impacts to each identified resource concern, quantifying where possible. If this information is found elsewhere in the conservation plan, simply provide a summary here.

"Alternatives 1,2, etc.": Record the impacts that are likely to occur under each alternative scenario. Document impacts to each identified resource concern, quantifying where possible. If this information is found elsewhere in the conservation plan, simply provide a summary here. Include both short and long-term consequences in the analysis.

Categories of Effects to Consider- There are three categories of effects that must be considered when predicting short- and long-term effects of an alternative on concerns:

Direct effects are caused by the alternative and occur at the same time and place.

Indirect effects are caused by the alternative and are later in time or farther removed in distance, but are still reasonably foreseeable (e.g., "downstream" effects).

Cumulative effects are those that result from all past, present, and reasonably foreseeable future actions. They can result from individually minor but collectively significant actions taking place over a period of time. Cumulative effects are most appropriately analyzed on a watershed or area-wide level.

Cumulative Impacts ideally consider "...all actions in the area of potential effect, REGARDLESS of what agency (Federal or non-Federal) or person undertakes such other actions." (CEQ 1508.7)

The NECH, Part 610.70, "Effects Analysis," provides important information on describing effects so that an adequate analysis can be made when the proposed alternative has adverse effects.

Resource Concerns Use your state's eFOTG Section III Quality Criteria or other tools where possible which are the established threshold levels for identified resource concerns. Professional judgement should be used where Quality Criteria or other tools are not available. Place a check in the "NOT meet QC" box for each resource concern to indicate when FOTG Section III Quality Criteria will not be met (i.e., where additional measures are needed to meet QC).

I. Special Environmental Concerns

For guidance in addressing special environmental concerns, see NECH Subpart B and the Special Environmental Concern Evaluation Procedure Guide Sheets for specific information applicable to each concern. Where consultation with another federal agency is required (e.g., USFWS or NMFS) to determine potential environmental effects, follow established State protocols or contact the appropriate NRCS State Specialist for guidance. Document any additional State and/or local special environmental concerns in "K. Other Agencies and Broad Public Concerns". Attach additional documentation if needed.

J. Impacts to Special Environmental Concerns: Briefly describe the status and/or description of effects on any of the Special Environmental Concerns, and include other notes as needed. Complete applicable Evaluation Procedure Guide Sheets or other state specific documentation as needed and include them in the client's administrative file. If the Special Environmental Concern is not present in the project area then there is no need to attach the Guide Sheet. Completion of Guide Sheets is not mandatory, but appropriate documentation should be provided. Check your own States' guidance for compliance and planning requirements.

Place a check in the "needs action " box when effects have not been fully determined or when additional procedural action is needed, such as the need for a permit or completing required consultation with regulatory agencies. Practice implementation should not occur until all required consultations and coordination with the appropriate agency have been completed and all necessary permits provided. Planning and practice implementation may continue for practices not involved in required consultation/coordination efforts.

- K. Other Agencies and Broad Public Concerns:** List any necessary easements, permissions, or permits (e.g., Clean Water Act Section 404, Rivers and Harbors Act Section 10, Endangered Species Act Section 10, wetland mitigation easements, state or county permits) required to implement the alternatives. Remember that identifying needed permits for ALL alternatives may be an important decision criteria between alternatives and should be considered during the planning process.

Relay public concerns related to land-use, demographics, landscape characteristics, or other Federal, Tribal, State, and local laws/regulations. Document the impacts of each alternative on these issues. Responses will impact the selection of an alternative as well as issues surrounding "significance." Document contact and communications with USFWS, NOAA-NMFS, COE, EPA, SWCD's, NRCS State Office, state/local environmental agencies, etc., and others consulted, including public participation activities. The NECH, Part 610.68 provides important information on public participation requirements.

Cumulative Effects Refer to NECH Part 610.70. A cumulative impact is defined as "the impact on the environment which results from the incremental impact of the action when added to other past, present and reasonably foreseeable future actions regardless of what agency (federal or non-federal) or person undertakes such other actions. Cumulative impacts can result from individually minor but collectively significant actions taking place over a period of time" (40 CFR 1508.70). Cumulative effects include the direct and indirect effects of a project together with the effects from reasonably foreseeable future actions of others. For a project to be reasonably foreseeable, it must have advanced far enough in the planning process that its implementation is likely. Reasonably foreseeable future actions are not speculative, are likely to occur based on reliable resources and are typically characterized in planning documents. Add additional pages as needed.

- L. Mitigation:** Include here any mitigation measures that are NOT already incorporated in the alternatives that will offset any adverse impacts. Briefly describe or reference all mitigation efforts that may be applied at the time of the decision. Mitigation actions to be applied must be included in the conservation plan.

As referenced in CEQ regulations Section 1508.20 and NECH Part 610.71, Mitigation includes:

- Avoiding the impacts altogether by not taking a certain action or parts of an action.
- Minimizing impacts by limiting the degree of magnitude of the action and its implementation.
- Rectifying the impact by repairing, rehabilitating, or restoring the affected environment.
- Reducing or eliminating impact over time by preservation/maintenance operations during action life.
- Compensating for the impact by replacing or providing substitute resources or environments.

- M. Preferred Alternative:** Record which alternative was agreed upon by the client and agency and why. The decision should clearly address the underlying need(s) as identified in "E". The Objective(s) (Purpose) stated in "D" serves as the decision factors between alternatives.

- N. Context:** Record the context used in the alternatives analysis. Significance varies with the setting of the proposed action. For instance, in the case of a site-specific action, significance would usually depend upon the effects in the locale rather than in the world as a whole. Both short- and long-term effects are relevant.

- O. Determination of Significance or Extraordinary Circumstances:** This section is a very important part of the evaluation process. Many of our actions have been analyzed in one of the National/Regional Programmatic NEPA documents and will only require documentation as detailed in Q-3 below. However, site-specific circumstances (existence of federally listed species, important cultural resources, high degree of controversy, etc.) may be such that a more detailed analysis may be needed to determine, through an EA, that impacts would be non-significant, or through a more detailed EIS if we feel that impacts are likely to significantly or adversely affect the quality of the human environment. The questions in this section list those considerations that, if associated with implementation of the proposed action, may result in a determination of "significance."

Categorical Exclusions: On the other hand, it may be the case that the action we are proposing falls under one of USDA or NRCS' lists of "categorical exclusions." Before documenting the use of one of these categorical exclusions, it is important to read Section 610.46 of the NECH. This section provides a list of all categorical exclusions that apply to actions as well as more detailed considerations and requirements for their use. In order for an action to be categorically excluded, appropriate documentation must be made on the NRCS-CPA-52 indicating that the proposed action does not meet any of the criteria for "significance," as discussed above. These criteria are also known as "extraordinary circumstances" when discussing categorical exclusions. If a proposed plan involves any actions that are NOT on the list of allowable categorical exclusions, the entire action can NOT be categorically excluded from review under NEPA. Also, if actions are interdependent, they can NOT be segmented into smaller component parts to avoid the requisite and appropriate level of environmental review under NEPA.

To complete the determination on the NRCS-CPA-52, check "yes" or "no" for each of the questions. If you are not sure about the answer, contact your State Environmental Liaison for assistance. The NRCS-CPA-52 must provide evidence to conclude that the activity will not result in significant adverse environmental effects or extraordinary circumstances on the quality of the human environment, either individually or cumulatively. If any of the extraordinary circumstances are found to apply to the proposed action, then you should determine whether the proposal can be modified to mitigate the adverse effects and prevent the extraordinary circumstances. If this can be done and the client agrees to any necessary change(s) in the proposed action to avoid significant adverse impacts, then the proposed action is to be modified and implemented. If the proposed action cannot be modified or the proponent refuses to accept a proposed change, then Item 5 in Section "Q" must be checked for the NRCS NEPA Compliance Finding to indicate that additional analysis and documentation is needed.

- P. Signature (planner):** The individual completing Parts A thru P of the CPA-52 must sign and date to indicate they have used the best available information. This may or may not be the same person as the agency RFO. In cases where the planner is not a NRCS employee they will sign the first signature area and then the NRCS will also need to sign to confirm and validate the information as the responsible agency.

Parts "Q" thru "S" must be completed by the Responsible Federal Official (RFO).

For NRCS applications this is the NRCS employee responsible for NEPA compliance at the state or field office level. For NRCS the State Conservationist is the RFO and may delegate that authority to a designated agency representative.

- Q. NEPA Compliance Finding (check one):** This finding will determine the appropriate NEPA action required. Instructions below correspond to the option numbers in Section "Q" of the Form. In Section "R" document the rationale for your Finding.

- 1) Federal actions do NOT include situations in which NRCS (or any other federal agency) provides technical assistance (CTA) only. The agency cannot control what the client ultimately does with that assistance. Non-Federal actions include, but are not limited to:
 - NRCS makes HEL or wetland conservation determinations.
 - NRCS provides technical designs where there is **no** federal financial assistance.
 - NRCS provides planning assistance or other technical assistance and information to individuals, organizations, States, or local governments where there is no federal financial assistance or other control of the decision or action.
- 2) Categorically excluded (CE) actions are a category of actions which do not individually or cumulatively have a significant effect on the human environment, therefore, neither an environmental assessment nor an environmental impact statement is required. First determine whether the proposed action is a categorically excluded action as identified in NRCS or USDA regulations implementing NEPA. Note that there may be overarching or CE-specific side boards that must be met in order to apply a CE. If the proposed action is listed as a CE action, then assess whether there are any applicable extraordinary circumstances which would prevent the action from being eligible as a CE. Check this box only if the action is categorically excluded **AND** there are no EXTRAORDINARY CIRCUMSTANCES involved or affected by the proposed action. USDA and NRCS categorical exclusions are listed in the NECH, Part 610.46.

- 3) Check this box if there is an existing NRCS NEPA document that has sufficiently analyzed the action being proposed. A number of NRCS National Programmatic NEPA documents have analyzed effects of many practices planned under nationwide conservation programs. There may also be Regional, State, or area wide Programmatic NEPA documents that can be referred to. For information about "Tiering" to existing NRCS NEPA documents see the NECH Part 610.81.

Keep in mind that Programmatic EA's and EIS's are not site-specific so they do not attempt to describe every possible type of effect resulting from actions that could be taken. Thus, you must use your knowledge of site-specific conditions to decide if additional analysis is needed. Network diagrams illustrating general effects of conservation practices can be found that are associated with national or state EA's or EIS's. These diagrams may help in analyzing effects of practices.

Authorized planners and RFOs should conduct their own analyses in a similar manner to assess site-specific environmental impacts. Impacts to other resources protected by Executive Orders, laws, and policies (i.e., the Special Environmental Concerns such as cultural resources, endangered species, and riparian areas) must be evaluated separately unless an existing NEPA document analyzes those impacts for the same geographic area and at the same site-specific scale covered by the selected alternative. Potentially significant adverse impacts requiring consultation under other applicable environmental laws and Executive Orders may require preparation of a site-specific EA or EIS. The State Environmental Liaison should be consulted in such cases to assist in determining whether a site-specific EA or EIS is required.

Copies of NRCS national programmatic NEPA documents may be viewed on NRCS' Environmental Compliance web page.

- 4) It is possible to tier to NEPA documents prepared by other Federal agencies if they have undergone a formal "adoption" process by NRCS as outlined in the NECH 610.83 and CEQ regulations 40 CFR-1506.3. NRCS must have prepared and published the agency's own Finding of No Significant Impact (FONSI) for an EA or Record of Decision for an EIS in order for a NEPA document to be "adopted". For information about "Tiering" to NEPA documents see the NECH Section 610.81.
- 5) *If 1), 2), 3), or 4) do not apply, the action may cause a significant effect on the quality of the human environment and an EA or EIS may be required. Additional analysis may be required to comply with NEPA.* Contact the State Environmental Liaison or equivalent for guidance on completing this analysis and provide them with a copy of the NRCS-CPA-52 and supporting documentation.

R. Rationale Supporting the Finding: Explain the reasons for making the "Finding" in "R".

If "Q 1)" was selected, explain why the action is NOT a federal action subject to NRCS regulations implementing NEPA.

If "Q 2)" was selected, document the categorical exclusion that covers the proposed action **and** indicate that there are no extraordinary circumstances.

If "Q 3)" was selected, identify any applicable NRCS NEPA document. Record the citation of the NRCS NEPA document you are tiering to.

If "Q 4)" was selected, identify any applicable NRCS NEPA document that was officially adopted from another agency. Record the citation of the NRCS adopted NEPA document you are tiering to.

If " Q 5)"was selected, document your analysis and provide this information (NRCS-CPA-52 and supporting documents) to your State Environmental Liaison or equivalent.

S. Signature of Responsible Federal Official(RFO): The appropriate agency RFO must sign and date. The RFO should wait to make the finding until all consultations, permits, etc., are finalized. This signature certifies that the proposed action/plan complies with all NRCS policies implementing NEPA and all other applicable Federal, State, and local laws/Executive Orders.

CLEAN AIR ACT
NECH 610.21
Evaluation Procedure Guide Sheet

Check all that apply to this Guide Sheet review: Alternative 1 Alternative 2 Other

Client/Plan Information:

Santaquin City, Utah

Santaquin Storm Drain

WFPO Program 2017 Funding

NOTE: STEPS 1 and 2 help determine whether construction permitting is needed for the planned action or activity. STEP 3 help determines whether the opportunity for emissions reduction credits exist. STEP 4 help determines whether any other permitting, record keeping, reporting, monitoring, or testing requirements are applicable. Each of these steps should be updated with more specific language as needed, since air quality permitting and regulatory requirements are different for each state. In each step, if more information is needed or there is a question as to whether there are air quality requirements that need to be met, the planner or client should contact the appropriate air quality regulatory agency with permitting jurisdiction for the site to determine what air quality regulatory requirement must be met prior to implementing the planned action or activity.

STEP 1.

Is the proposed action or alternative expected to increase the emission rate of any regulated air pollutant?

NOTE: The definition of a “regulated air pollutant” differs depending on the air quality regulations in effect for a given site. For a federal definition of “regulated air pollutant,” please refer to the 40 CFR 70.2. Other definitions for “regulated air pollutant” found in state or local air quality regulations may be different. *States should tailor this question to the State air quality regulations and definitions since those will include any Federal requirements.*

- No If “No,” it is likely that no permitting or authorization is necessary to implement the proposed action or alternative. Document the finding on form NRCS-CPA-52 and advise the client to contact the appropriate air quality regulatory agency with permitting jurisdiction for the site to either verify that no permitting or authorization is necessary or to determine what requirements must be met prior to implementing the planned action or activity. Go to step 3.
- Yes If “Yes,” go to Step 2.

STEP 2.

Can the proposed action or alternative be modified to eliminate or reduce the increase in emission rate of the regulated air pollutant(s)? **NOTE:** This Step is to prompt the planner to review the planned action or activity to see if there is an opportunity to either eliminate the emission rate increase (possibly remove a permitting requirement) or reduce the emission rate increase (possibly move to less stringent permitting).

- No If “No,” it is likely that permitting or authorization from the appropriate air quality regulatory agency will be required prior to implementing the planned action or activity. Document the finding on form NRCS-CPA-52 and advise the client to contact the appropriate air quality regulatory agency with permitting jurisdiction for the site to either verify that no permitting or authorization is necessary or to determine what requirements must be met prior to implementing the proposed action or alternative. Go to Step 3.
- Yes If “Yes,” modify the proposed action or alternative and repeat Step 1.

STEP 3.

Is the proposed action or alternative expected to result in a decrease in the emission rate of any criteria air pollutant for which the area in which the site is located in an EPA designated nonattainment area for that criteria air pollutant? **NOTE:** For an explanation of criteria air pollutants and nonattainment areas, refer to Section 610.81 of the NECH. Further information regarding nonattainment areas can also be found on the U.S. EPA nonattainment area webpage at <http://www.epa.gov/oar/oaqps/greenbk/>.

CLEAN AIR ACT (continued)

- No If "No," go to Step 4.
- Yes If "Yes," the opportunity for obtaining non-attainment pollutant emission credits may exist. Document the finding on form NRCS-CPA-52 and advise the client of that potential opportunity. If the client is interested in registering nonattainment pollutant emission credits, advise him/her to contact the appropriate air quality regulatory agency with permitting jurisdiction for the site to determine if and how credits can be documented and/or registered for potential sale. Go to Step 4.

STEP 4.

Is the site or proposed action or alternative subject to any other federal (i.e., New Source Performance Standards, National Emissions Standards for Hazardous Air Pollutants, etc.), state, or local air quality regulation (including odor, fugitive dust, or outdoor burning)? **NOTE:** Refer to Section 610.81 of the NECH for a further discussion of air quality regulations.

- No If "No," no additional requirements are likely needed prior to implementing the proposed action or alternative. Document finding on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," additional permitting, authorization, or control requirements may be needed prior to implementing the proposed action or alternative. Document the finding on form NRCS-CPA-52, and advise the client to contact the appropriate air quality regulatory agency with permitting jurisdiction for the site to determine what requirements must be met prior to implementing the proposed action or alternative.

Notes:

**CLEAN WATER ACT/WATERS of the U.S.
NECH 610.22
Evaluation Procedure Guide Sheet**

Check all that apply to this Guide Sheet review: Alternative 1
 Alternative 2 Other

Client/Plan Information:

Santaquin City, Utah

Santaquin Storm Drain

WFPO Program 2017 Funding

NOTE: This guide sheet should be tailored to meet the specific needs of individual State and/or local regulatory/permitting requirements. It is important for each state to coordinate with their individual State and Federal regulatory agencies to tailor state-specific protocols in order to prevent significant delays in processing permit applications.

Complete both sections of this guide sheet in order to address Federal as well as State administered regulatory requirements of the Clean Water Act.

SECTION I

Federally Administered Regulatory Program - Section 404 of the CWA

STEP 1.

Will the proposed action or alternative involve or likely result in the discharge of dredged or fill material or other pollutants into "waters of the United States?" *More detailed information regarding "Waters of the U.S.," and federal permitting programs under CWA is found in the NECH 610.82.*

- No If "No," document this on form NRCS-CPA-52 and proceed with Section II below.
- Yes If "Yes," go to Step 2.
- Unknown If "Unknown," refer to your FOTG or contact your NRCS Environmental Liaison for assistance. Inform the client early on that they may need to contact the appropriate U.S. Army Corps of Engineers (COE) office to determine if the proposed action or alternative will require a permit. Repeat Step 1.

STEP 2.

Has the client obtained a Section 404 permit (Individual, Regional, or Nationwide) or a determination of an exemption from the appropriate COE office?

- No If "No," determine if the client has applied for a permit. If a permit has not been applied for, the client will need to do so. If a permit has been applied for, document this, and continue the planning process in consultation with the client and the regulatory agencies. The permit authorization should be reflected in the final plan and documentation. Continue planning, but a permit is required prior to implementation. Complete Section II below.
- Yes If "Yes," document on form NRCS-CPA-52 and complete Section II below. The final plan should not be contrary to the provisions of the permit authorization or exemption. Changes made during the planning process that may impact the applicability of the permit, such as amount or location of fills or discharges of pollutants should be coordinated with the COE.
- Unknown If "Unknown," meaning that you do not know if authorization has been obtained or applied for, consult with the client and repeat Step 2.

Notes:

--

CLEAN WATER ACT/WATERS of the U.S. (continued)**SECTION II****State Administered Regulatory Programs, Sections 303(d) and 402 of CWA****STEP 1**

Is the proposed action or alternative located in proximity to waters listed by the State as “impaired” under Section 303(d) of the CWA?

- No If “No,” document this on form NRCS-CPA-52 and proceed to Step 2.
- Yes If “Yes,” review and comply with any existing TMDLs or associated Watershed Action Plans that have been established by the State for that stream segment. However, even if TMDLs have not been established by the State for that stream segment, ensure that the action will not contribute to further degradation of that stream segment. Proceed to Step 2.
- Unknown If “Unknown,” refer to FOTG for information regarding State designation of “impaired” stream segments, or contact your NRCS Environmental Liaison for assistance. Repeat Step 1.

STEP 2

Will the proposed action or alternative likely result in point-source discharges from developments, construction sites, or other areas of soil disturbance, or sewer discharges (e.g. projects involving stormwater ponds or point-source pollution including CAFOs for which CNMPs are being developed)? *Section 402 of the CWA requires a permit for these activities through the National Pollutant Discharge Elimination System (NPDES) program which the States administer.*

- No If “No,” document this on form CPA-52 and proceed with planning.
- Yes If “Yes,” go to Step 3.
- Unknown If “Unknown,” refer to your FOTG for additional information or contact your NRCS Environmental Liaison for assistance. Inform the client early on that they may need to contact the appropriate State regulatory office to determine if the proposed action or alternative will require a NPDES permit. Repeat Step 2.

STEP 3

Has the client obtained a National Pollutant Discharge Elimination System (NPDES) permit or a determination of an exemption from the appropriate State regulatory office?

- No If “No,” determine if the client has applied for any necessary permits. If a permit has not been applied for, the client will need to do so. If they have applied, document this, and continue the planning process in consultation with the client and the regulatory agency. Continue the planning process in consultation with the client and the regulatory agencies. The permit authorization should be reflected in the final plan and documentation. Continue planning, but a permit is required prior to implementation.
- Yes If “Yes,” document this on form NRCS-CPA-52 and proceed with planning. The final NRCS conservation plan should not be contrary to the provisions of the permit authorization or exemption. Changes made during the planning process that may impact the applicability of the permit should be coordinated with the appropriate State regulatory agency.
- Unknown If “Unknown,” meaning that you do not know if authorization has been obtained or applied for, consult with the client and repeat Step 3.

Notes:

--

COASTAL ZONE MANAGEMENT AREAS
NECH 610.23
Evaluation Procedure Guide Sheet

Client/Plan Information:

Santaquin City, Utah

Santaquin Storm Drain

WFPO Program 2017 Funding

Check all that apply to this Guide Sheet review: Alternative 1
 Alternative 2 Other

STEP 1.

Is the proposed action or alternative in an officially designated "Coastal Zone Management Area"?

- No If "No," additional evaluation is not needed concerning coastal zones. Document the finding on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," go to Step 2.
- Unknown If "Unknown," consult Section II of the FOTG for information regarding Coastal Zone Management Programs in your area and repeat Step 1.

Is the proposed action or alternative "consistent" with the goals and objectives of the State's Coastal Zone Management Program (as required by Section 307 of the Coastal Zone Management Act)?

- No If "No," go to Step 3.
- Yes If "Yes," no additional evaluation is needed concerning coastal zones. Document the finding, including the reasons, on form NRCS-CPA-52 and proceed with planning.
- Unknown If "Unknown," consult with your designated State specialist for CZMA and repeat Step 2.

Is NRCS providing financial assistance or otherwise controlling the action?

- No If "No," go to Step 4.
- Yes If "Yes," the NRCS District Conservationist or an NRCS State Office employee must contact the State's Coastal Zone Program Office before the action is implemented to discuss possible modifications to the proposed action. NRCS shall not provide assistance if the proposed action or alternative would result in a violation of a State's Coastal Zone Management Plan. NRCS shall provide a consistency determination to the State agency no later than 90 days before final approval of the activity. When consultation is complete, document the agreed to items and reference or attach them to the NRCS-CPA-52.

STEP 4.

Will a Federal agency OTHER than NRCS provide funding or otherwise control implementation of the action?

- No If "No," NRCS should provide the landowner with relevant information regarding any local/state compliance requirements and protocols (permitting, etc) in Special Management Areas as appropriate to comply with local Coastal Zone Management Programs. Document on the NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," recommend that the funding or controlling agency consult with the State Coastal Zone Management Office before the action is implemented. Proceed with planning.

Notes:

--

CORAL REEFS
NECH 610.24
Evaluation Procedure Guide Sheet

Client/Plan Information:
Santaquin City, Utah
Santaquin Storm Drain
WFPO Program 2017 Funding

Check all that apply to this Guide Sheet review:	<input checked="" type="checkbox"/> Alternative 1	<input type="checkbox"/> Alternative 2	<input type="checkbox"/> Other
---	---	--	--------------------------------

STEP 1.

Are coral reefs or associated water bodies (e.g. embayment areas) present in or near the planning area?

- No If "No," additional evaluation is not needed concerning coral reefs. Document the finding on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," go to Step 2. **Note:** If there are any endangered or threatened species of coral inhabiting the coral reef ecosystem you must also fill out the Endangered and Threatened Species Guide Sheet.

STEP 2.

Is there a potential for the proposed action or alternative to degrade the conditions of the coral reef ecosystem? (Refer to www.coralreef.gov/ for Local Action Strategies in your area.)

- No If "No," additional evaluation is not needed concerning coral reefs. Document the finding on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," go to Step 3.

STEP 3.

Can the action or alternative be modified to reduce or avoid degradation to the coral reef ecosystem?

- No If "No," identify the component(s) of the system which will cause the potential impacts.
- Yes Document the effects, including the reasons, on form NRCS-CPA-52. Go to Step 4. If "Yes," modify the action or alternative and repeat Step 2.

STEP 4.

Is NRCS providing financial assistance or otherwise controlling the action?

- No If "No," go to Step 5.
- Yes If "Yes," the significance of the impacts must be determined. An Environmental Assessment (EA) or Environmental Impact Statement (EIS) may be required. Contact your State Office for assistance and, if you are the RFO, select option 4) in Section S of the form NRCS-CPA-52.

STEP 5.

Will a Federal agency other than NRCS provide funding or otherwise control implementation of the action?

- No If "No," and degradation of the reefs is unavoidable, provide the client with information regarding the current status of U.S. coral reefs and the documented causes of degradation (including sedimentation and nutrient runoff), and the beneficial aspects of maintaining coral reefs.
- Yes If "Yes," the significance of the impacts must be determined. An Environmental Assessment (EA) or Environmental Impact Statement (EIS) may be required. Document this on the NRCS-CPA-52, with a description of the potential impacts, and provide a copy of the form to the Federal agency providing funding or controlling the action. Inform the client and proceed with planning.

Notes:

--

**CULTURAL RESOURCES / HISTORIC
PROPERTIES NECH 610.25
Evaluation Procedure Guide Sheet**

Check all that apply to this Guide Sheet review: Alternative 1 Alternative 2 Other

Client/Plan Information:

Santaquin City, Utah
Santaquin Storm Drain
WFPO Program 2017 Funding

NOTE: This guidesheet provides general guidance to field planners and managers. States may need to tailor this Evaluation Procedure Guide Sheet to reflect State Level Agreements (SLA's) with SHPOs or Tribal consultation protocols or operating procedures pertinent to your state, and/or other state specific protocols that reflect the terms of the current National Programmatic Agreement among NRCS, the Advisory Council on Historic Preservation, and the National Conference of SHPOs. For additional information regarding compliance with Section 106 of the NHPA and NRCS cultural resource policy refer to the General Manual Title 420 Part 401 Cultural Resources; for current operating procedures see Title 190 Part 601, the National Cultural Resource Procedures Handbook (NCRPH).

NOTE regarding consultations: When dealing with undertakings with the potential to affect cultural resources/historic properties, it is important to follow NRCS's policy and the regulations that implement Section 106 and complete consultation with mandatory (SHPOs, THPOs, federally recognized tribes) and identified consulting parties during the course of planning. This consultation is not documented on this guidesheet but would occur with Steps 2, 3, 4, and 6 and these must be conducted in accordance with NRCS State Office operating procedures to ensure appropriate oversight by Cultural Resources Specialists who meet the Secretary of Interior's Qualification Standards.

STEP 1.

Is the proposed action or alternative funded in whole or part or under the control of NRCS? To make this determination, answer the following:

- Is technical assistance carried out by or on behalf of NRCS? No Yes Unknown
- Is it carried out with NRCS financial assistance? No Yes Unknown
- Does it require Federal approval with NRCS as the lead federal agency (permit, license, approval, etc.)? No Yes Unknown
- Is it a joint project with another Federal, State, or local entity with NRCS functioning as lead federal agency? No Yes Unknown

- If all of your responses are "No," document decision on the NRCS-CPA-52 and proceed with planning.
- If any responses are "Yes," go to Step 2.
- If "Unknown," consult with your State Cultural Resources Coordinator or Specialist (CRC/CRS) to determine if this is an action/undertaking that requires review and then complete Step 1.

STEP 2.

Is the proposed action(s) or alternative(s) identified as an "undertaking" (as defined in the NCRPH and GM) with the potential to cause effects to cultural resources/historic properties?

- No If "No," document this finding on the NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," go to Step 3.

STEP 3.

Has the undertaking's Area of Potential Effect (APE) been determined? **NOTE:** Include all areas to be altered or affected, directly or indirectly: access and haul roads, equipment lots, borrow areas, surface grading areas, locations for disposition of sediment, streambank stabilization areas, building removal and relocation sites, disposition of removed concrete, as well as the area of the actual conservation practice. Consultation is essential during determination of the APE so that all historic properties (buildings, structures, sites, landscapes, objects, and properties of cultural or religious importance to American Indian tribal governments and native Hawaiians) are included.

- No If "No," or "Unknown," consult with your state specific protocols or the CRC/CRS to determine the APE.
- Unknown
- Yes If "Yes," go to Step 4.

CULTURAL RESOURCES (continued)**STEP 4.**

Have the appropriate Records (National, State and local registers and lists) been checked and/or interviews conducted to determine whether any known cultural or historic resources are within or in close proximity to the proposed APE/project area? **Note:** This record checking does not substitute for mandatory consultation with SHPO, THPO, tribes and other identified consulting parties.

- | | | | |
|---|-----------------------------|---|----------------------------------|
| National Register of Historic Places? | <input type="checkbox"/> No | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> Unknown |
| State Register of Historic Places? | <input type="checkbox"/> No | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> Unknown |
| The SHPO's statewide inventory/data base? | <input type="checkbox"/> No | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> Unknown |
| Local/county historical society and/or commission lists? | <input type="checkbox"/> No | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> Unknown |
| Client knowledge of existing artifacts, historic structures or cultural features? | <input type="checkbox"/> No | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> Unknown |

- If any responses are "No" or "Unknown," work with your CRC/CRS to be sure these files are checked (sometimes the SHPO will let only the CRS or CRC review the files). Follow all other operating procedures as required by NRCS policy and procedures, State Level Agreement (SLA), and Tribal consultation protocols or operating procedures, as appropriate.
- If all responses are "Yes," and **NRCS providing technical assistance only**, then use any known information, notify the landowner of any potential affects, and provide recommendations for consideration. Document this on the NRCS-CPA-52 and proceed with planning. If NRCS is providing more than technical assistance go to Step 5.

STEP 5.

Did STEP 4 reveal the existence of any known or potential cultural resources in the APE, and/or were any cultural resource indicators observed during the field inspection of the APE? **NOTE:** Field inspections or cultural resource survey will need to be conducted by qualified personnel in your state. Check with you State Cultural Resource Specialist to determine qualification criteria.

- No If "No," document this finding on the NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," contact the CRC/CRS. Do NOT proceed with finalizing project design or project implementation until the final CRS response is received. Go to Step 6.

STEP 6.

Can the proposed action(s) or alternative(s) be modified to avoid effects on the known cultural resources?

- No If "No," go to Step 7.
- Yes If "Yes," modify the planned action(s) or activity(ies) and proceed according to CRS guidance and document this on the NRCS-CPA-52 and continue with planning.

STEP 7.

Has consultation with appropriate and interested parties been completed and documented? **NOTE:** The field planner completing the NRCS-CPA-52 generally does not do the consultation unless it is the CRS or CRC. Refer to the appropriate specialist for the documentation information.

- No If "No" refer to State CRC or CRS for further consultation and recommendations to the State Conservationist.
- Yes If "Yes," and all necessary historic preservation activities of identification, evaluation, and treatment have been completed, document any consultation and proceed with planning.

Notes:

**ENDANGERED AND THREATENED SPECIES,
NECH 610.26
Evaluation Procedure Guide Sheet**

Check all that apply to this Guide Sheet review:	<input type="checkbox"/> Alternative 1	<input type="checkbox"/> Alternative 2	<input type="checkbox"/> Other
---	--	--	--------------------------------

Client/Plan Information:
Santaquin City, Utah
Santaquin Storm Drain
WFPO Program 2017 Funding

If species listing/status changes prior to implementation, go back and analyze the affects in the appropriate section as dictated in Step 1.

Note Regarding Candidate Species: As per GM Title 190, Part 410.22, NRCS shall contact the Services, State agencies, and Tribal governments to identify Federal candidate, State and Tribal designated species, and NRCS actions which have the greatest potential to affect those species and their habitats. NRCS shall determine which candidate species and species of concern are to be considered during planning and implementation of NRCS actions. When NRCS concludes that a proposed action "may adversely affect" Federal candidate species, NRCS will recommend only alternative conservation treatments that will avoid adverse effects, and to the extent practicable, provide long-term benefit to the species. If the species becomes

STEP 1.

Are there any endangered or threatened species, designated critical habitat(s), proposed species/habitats, or sState/Tribal species of concern protected by law or regulation present, or potentially present, in the area of potential effect?

- No If "No," additional evaluation is not needed. Document the finding on form NRCS-CPA-52 and proceed with planning.
- Unknown If "Unknown," consult Section II of the FOTG for a listing of threatened and endangered species and associated critical habitats, and State species of concern, then repeat Step 1. If you are still uncertain about the status of threatened, endangered, proposed, or species of concern in the planning area, ask your State Biologist or contact the FWS/NMFS Fisheries, as appropriate.
- Yes **If "Yes," then proceed to the applicable section(s) listed below:**
- Federally listed **endangered or threatened** species/habitats. **Go to Step 2.**
 - Federally listed **proposed** species/habitats. **Go to Step 5.**
 - **State/Tribal species of concern** protected by law or regulation. **Go to Step 9.**

Federally endangered or threatened species/habitats

STEP 2.

What are the short and long-term impacts of the proposed action or alternative on endangered or threatened species or their designated critical habitat? If more than one may apply, then differentiate in the "Notes" section below.

- No effect If "No effect," additional evaluation is not needed concerning endangered and threatened species or designated critical habitat. Document the finding, including the reasons for your determination on form NRCS-CPA-52 and proceed with planning.
- May Affect but not likely to adversely affect (e.g. beneficial affect) If "May affect but not likely to adversely affect," document the finding, including the reasons, on form NRCS-CPA-52. This determination may require concurrence from FWS/NMFS Fisheries. Go to Step 3.

Federally endangered or threatened species/habitats (continued)

- May adversely affect If "May adversely affect," modify the action if possible to avoid adverse effects. If the action can be modified, repeat Step 2. If the action can not be modified, go to Step 3.
- Effects are unknown If "Effects are unknown," contact the NRCS State Biologist for assistance and repeat Step 2.

STEP 3.

Will a Federal agency other than NRCS provide funding or otherwise control implementation of the action?

- No If "No," go to Step 4.
- Yes If "Yes," ensure that potential adverse effects are avoided to the extent feasible, document and describe the effects on form NRCS-CPA-52. Include both short-term and long-term effects. Document the need for the lead Federal agency to consult (if listed species or habitat may be affected beneficially or adversely) with the FWS/NMFS Fisheries, as appropriate. Inform the client and continue planning. However, make the client aware that the action can not be implemented without first attaining the appropriate concurrence.

STEP 4.

Is NRCS providing financial assistance or otherwise controlling the action?

- No **If "No," and your answer in Step 2 was, "May affect but not likely to adversely affect"** and there is no possibility of any short-term or long-term adverse effects then continue with planning but ensure the client is aware of the effects.
- No **If "No," and your answer in Step 2 was, "May adversely affect,"** then inform the client of NRCS's policy concerning endangered and threatened species and the need to use alternative conservation treatments to avoid adverse effects on these species or their habitat. Further NRCS assistance will be provided only if one of the conservation alternatives is selected that avoids adverse effects (then repeat from Step 2) or the landowner obtains a "take" permit from the FWS/NMFS Fisheries, as appropriate. Refer the client to USFWS/NMFS Fisheries to address their responsibilities under Sections 9 & 10 of the ESA, for Federally listed species.
- Yes **If "Yes," and your answer in Step 2 was either, "May affect but not likely to adversely affect", or, "May adversely affect,"** then inform client that the NRCS must consult on listed species with FWS/NMFS Fisheries, as appropriate. The action will only be implemented according to the terms of the consultation. When consultation is complete, reference or attach the consultation documents to NRCS-CPA-52 and proceed with planning.

Notes for Federally endangered or threatened species/habitats:

Federally proposed species/habitats

For proposed species and their proposed critical habitats the action agency (NRCS) has the responsibility of determining that "activities will not jeopardize the continued existence of or destroy or adversely modify designated or proposed critical habitat for listed or proposed species" [190 GM Part 410.22(f)(5)(i)(B)]. Also see Chapter 6 in the ESA Section 7 Consultation Handbook for more information.

STEP 5.

What are the short and long-term impacts of the proposed action or alternative on proposed species or their proposed critical habitat? If more than one may apply, then differentiate in the "Notes" section below.

- No adverse effect If "No adverse effect," additional evaluation is not needed concerning proposed species or proposed critical habitat. Document finding, including the reasons for your determination on form NRCS-CPA-52 and proceed with planning.
- Potential adverse effect If "Potential adverse effect," go to Step 6.
- Effects unknown If "Effects unknown," contact the NRCS State Biologist for assistance and then repeat Step 5.

STEP 6.

Will a Federal agency other than NRCS provide funding or otherwise control implementation of the action?

- No If "No," go to Step 7.
- Yes If "Yes," ensure that potential adverse effects that are likely to jeopardize the continued existence of the proposed species or destroy or adversely modify proposed critical habitat are avoided. Coordinate with the lead Federal agency and provide any assistance needed for them to make the required "jeopardy" determination. Document on form NRCS-CPA-52 the potential need for the lead Federal agency to conference with the FWS/NMFS Fisheries, as appropriate. Inform the client and continue planning. However, make the client aware that the action can not be implemented without first attaining the appropriate concurrence.

STEP 7.

Is NRCS providing financial assistance or otherwise controlling the action?

- No If "No," inform client of NRCS policy for proposed species and the need to use alternative conservation treatments to avoid adverse effects that are likely to jeopardize the continued existence of the proposed species or destroy or adversely modify proposed critical habitat. **Contact NRCS State Biologist to make the affects determination** then go to Step 8.
- Yes If "Yes," then inform the client that the NRCS must conference on proposed species with FWS/NMFS Fisheries, as appropriate. The action will only be implemented according to the terms of the conference. When conference is complete, reference or attach the conference documents to form NRCS-CPA-52 and proceed with planning.

STEP 8.

Upon guidance from NRCS State Biologist, has it been determined that the proposed action or alternative is likely to jeopardize the proposed species or destroy or adversely modify proposed critical habitat?

- No If "No," document the finding on the NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," further NRCS assistance will be provided only if one of the conservation alternatives is selected that avoids that level of adverse effects (then repeat from Step 5). If the client is unwilling to modify the action, NRCS assistance must be discontinued. Although a "take" permit is not required for proposed species, there may be cases where the proposed species/habitats becomes formally listed as endangered/threatened or critical habitat is designated prior to project implementation. In this case, advise the client that a "take" permit from the USFWS/NMFS Fisheries would be needed prior to project implementation if it is determined that the action may have an adverse affect on the listed species/habitat.

Notes for Federally proposed species/habitats:

--

State / Tribal species of concern protected by law or regulation

STEPS 9-11 ADDRESS "STATE/Tribal SPECIES OF CONCERN" ONLY. Consult Section II of your State's FOTG for a listing of State/Tribal Species of Concern that are protected by law or regulation that may need to be evaluated, or ask your State Biologist for assistance.

STEP 9.

What are the short and long-term impacts of the proposed action or alternative on the State/Tribal Species of Concern? If more than one may apply, then differentiate in the "Notes" section below.

- | | |
|---|--|
| <input type="checkbox"/> No adverse effect | If "No adverse effect," additional evaluation is not needed concerning State species of concern, unless otherwise specified by State procedures or the State Biologist. Document the finding, including the reasons for your determination, on form NRCS-CPA-52 and proceed with planning. |
| <input type="checkbox"/> May adversely affect | If "May adversely affect," modify the action if possible to avoid adverse effects. If the action can be modified, repeat Step 9. If the action can not be modified, go to Step 10. |
| <input type="checkbox"/> Effects are unknown | If "Effects are unknown," contact the NRCS State Biologist for assistance and repeat Step 9. |

STEP 10.

Will a Federal agency other than NRCS provide funding or otherwise control implementation of the action?

- | | |
|------------------------------|--|
| <input type="checkbox"/> No | If "No," go to Step 11. |
| <input type="checkbox"/> Yes | If "Yes," ensure that potential adverse effects are avoided to the extent possible, document and describe the effects on form NRCS-CPA-52. Include both short-term and long-term effects. Document on form NRCS-CPA-52 the need for the lead Federal agency to address State/Tribal species of concern as appropriate under State land Tribal laws and regulations. Inform the client and continue planning. |

STEP 11.

Is NRCS providing financial assistance or otherwise controlling the action?

- | | |
|------------------------------|---|
| <input type="checkbox"/> No | If "No," and your answer in Step 9 was, "May adversely affect", inform the client of NRCS's policy regarding State and Tribal species of concern and the need to use alternative conservation treatments to avoid adverse effects on species. Provide alternative measures to client for consideration. Advise the client to contact the appropriate State or tribal resource agency for additional guidance to avoid any penalties applicable under State or Tribal law, and continue planning. |
| <input type="checkbox"/> Yes | If "Yes," and your answer in Step 9 was, "May adversely affect," inform the client of NRCS's policy concerning State species of concern and the need to use alternative conservation treatments to avoid adverse effects on species. Follow policy and procedures in your state for addressing State and Tribal species of concern. Consultation with the appropriate State wildlife resource agency may be needed. |

Notes for State species of concern:

--

ENVIRONMENTAL JUSTICE
NECH 610.27
Evaluation Procedure Guide Sheet

Client/Plan Information:
Santaquin City, Utah
Santaquin Storm Drain
WFPO Program 2017 Funding

Check all that apply to this Guide Sheet review:	<input type="checkbox"/> Alternative 1	<input type="checkbox"/> Alternative 2	<input type="checkbox"/> Other
---	--	--	--------------------------------

STEP 1.

In the area affected by the NRCS action, are there low-income populations, minority populations, Indian tribes, or other specified populations that would be adversely impacted by environmental effects resulting from the proposed action or alternative?

- No If "No," additional evaluation is not needed concerning environmental justice. Document the finding on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," go to Step 2.
- Unknown If "Unknown," consult your State Environmental Specialist, or equivalent, and/or Tribal Liaison for additional guidance. NOTE: The USDA Departmental Regulations on Environmental Justice (DR 5600-002) provides detailed "determination procedures" for NEPA as well as non-NEPA activities and suggests social and economic effects for considerations.

STEP 2.

Is the proposed action or alternative the type that might have a disproportionately adverse environmental or human health effect on any population?

- No If "No," additional evaluation is not needed concerning environmental justice. Document the finding on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," initiate community outreach or Tribal consultation to affected and interested parties that are categorized as low-income, minority, or as Indian Tribes. The purpose is to encourage participation and input on the proposed program or activity and any alternatives or mitigating options. Participation of these populations may require adaptive or innovative approaches to overcome linguistic, institutional, cultural, economic, historic, or other potential barriers to effective participation. If assistance is needed with this process, contact your State Public Affairs Specialist or Tribal Liaison. Go to Step 3.

STEP 3.

Considering the results of the outreach initiative together with other information gathered for the decision-making process, will the proposed action or alternative have a disproportionately high and adverse effect on the human health or the environment of the minority, low-income, or Indian populations?

- No If "No," notify interested and affected parties of agency decision.
- Yes If "Yes," consider the feasibility and appropriateness of the proposed alternatives and their effects and the possibility of developing additional alternatives or a mitigation alternative and repeat Step 4. Document results of these early scoping sessions on the NRCS-CPA-52. If it is felt that there remains a potentially high and/or adverse effect on human health or the environment, or the project/action carries a high degree of controversy, check "Q 5)" in Q of the NRCS-CPA-52 and refer the action to the State Environmental Liaison for further analysis. An EA may be required to determine if the action is "significant." If it is known that the "action will have significant effects on the quality of the human environment," and EIS will be required (NECH 610.44 and 610.45).

Notes:

--

ESSENTIAL FISH HABITAT
NECH 610.28
Evaluation Procedure Guide Sheet

Client/Plan Information:
Santaquin City, Utah
Santaquin Storm Drain
WFPO Program 2017 Funding

Check all that apply to this Guide Sheet review:	<input type="checkbox"/> Alternative 1	<input type="checkbox"/> Alternative 2	<input type="checkbox"/> Other
---	--	--	--------------------------------

STEP 1.

Is the proposed action or alternative in an area designated as Essential Fish Habitat (EFH) or in an area where effects could indirectly or cumulatively affect EFH?

- No If "No," additional evaluation is not needed concerning EFH. Document the finding on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," go to Step 2.
- Unknown If "Unknown," consult Section II of the FOTG for a list or the location of EFH areas and repeat Step 1. **Note:** Additional information regarding EFH Descriptions and Identifications can be found on NOAA's web site, <http://www.nmfs.noaa.gov/habitat/habitatprotection/efh/index.htm>

STEP 2.

Will the proposed action or alternative result in short-term or long-term disruptions or alterations that may result in an "adverse effect" to EFH? [16 U.S.C. 1855(b)(2); MSA Section 305(b)(2)]

- No If "No," consultation with NOAA Fisheries and further evaluation is not needed concerning EFH unless otherwise specified by the State Biologist. Document the finding on form NRCS-CPA-52 or equivalent and proceed with planning.
- Yes If "Yes," GO TO Step 3.
- Unknown If "Unknown," consult with your State Biologist and repeat Step 2.

STEP 3.

Can the proposed action or alternative be modified to avoid the potential adverse effect?

- No If "No," document the effects, including the reasons, on form NRCS-CPA-52. Go to Step 4.
- Yes If "Yes," modify the action or activity and repeat Step 2.

STEP 4.

Is NRCS providing assistance that would result in the funding, authorization, or undertaking of the proposed action or alternative? [MSA Section 305(b)]

- No If "No," go to Step 5.
- Yes If "Yes," inform the client that the NRCS District Conservationist or NRCS State Biologist must consult with NOAA Fisheries before further action or activity can proceed [MSA, Section 305(b)(2)]. **Note:** For specific information regarding consultation for EFH, see NOAA's "Essential Fish Habitat Consultation Guidance," April 2004, available at <http://www.nmfs.noaa.gov/habitat/habitatprotection/efh/index.htm>

ESSENTIAL FISH HABITAT (continued)

STEP 5.

Is a Federal agency other than NRCS providing assistance that would result in the funding, authorization, or undertaking of the proposed action or alternative?

- No If "No," an alternative conservation system that avoids the adverse effect must be identified as the proposed action or NRCS must discontinue assistance. If assistance is terminated, indicate the circumstances in the Remarks section of the NRCS-CPA-52 or contact the NRCS State Office for assistance. (GM 190, Part 410.3)
- Yes If "Yes," document on the NRCS-CPA-52 that the lead Federal agency should consult with NOAA Fisheries before the action is implemented. Inform the client and proceed with planning.

Notes:

--

FLOODPLAIN MANAGEMENT
NECH 610.29
Evaluation Procedure Guide Sheet

Client/Plan Information:
Santaquin City, Utah
Santaquin Storm Drain
WFPO Program 2017 Funding

Check all that apply to this Guide Sheet review:	<input type="checkbox"/> Alternative 1	<input type="checkbox"/> Alternative 2	<input type="checkbox"/> Other
---	--	--	--------------------------------

NOTE: This Guide Sheet is intended for evaluation of non-project technical and financial assistance only (individual projects). For project assistance criteria (those assisting local sponsoring organizations), consult GM-190, Part 410.25.

STEP 1.

Is the project area in or near a 100-year floodplain?

- No If "No," additional evaluation is not needed. Record "N/A" on NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," go to Step 2.
- Unknown If "Unknown", review the HUD/FEMA flood insurance maps and/or other available data. If still "Unknown", contact the appropriate field or hydraulic engineer. Repeat Step 1.

STEP 2.

Is the planning area in the floodplain an agricultural area that has been used to produce food, fiber, feed, forage or oilseed for at least 3 of the last 5 years before the request for assistance?

- No If "No," go to Step 4.
- If "Yes," document the agricultural use history and go to Step 3.

STEP 3.

Is the floodplain's agricultural production in accordance with official state or designated area water quality plans?

- No If "No," advise the client of conservation practices or other measures that will bring the land into accordance with water quality plans and incorporate these into the conservation plan. Go to Step 4.
- Yes If "Yes," document and go to Step 4.

STEP 4.

Over the short or long term, will this proposed action or alternative likely result in an increased flood hazard, incompatible development, or other adverse effect to the existing natural and beneficial values of the floodplain or lands adjacent or downstream from the floodplain?

- No If "No," document your finding on the NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," modify the action if possible to avoid adverse effects. Inform landuser of the hazards of locating actions in the floodplain and discuss alternative methods of achieving the objective and/or alternative locations outside the 100-year floodplain. If the action can be modified, describe the modification on the NRCS-CPA-52 and repeat Step 4. If the action can not be modified to eliminate adverse effects, go to Step 5.

FLOODPLAIN MANAGEMENT (continued)

STEP 5.

Is one or more of the alternative methods or locations practical?

No If "No," the District Conservationist will carefully evaluate and document the potential extent of the adverse effects and any increased flood risk before making a determination of whether to continue providing assistance. Go to Step 6.

Yes If your answer is "Yes, **and client agrees** to implement the alternative methods or locations outside the floodplain, document the agreed upon actions, including the reasons, on form NRCS-CPA-52 or equivalent and proceed with planning.

If your answer is "Yes," **and client does not agree** to implement the alternative methods or locations, advise the client that NRCS may not continue to provide technical and/or financial assistance where there are practicable alternatives. Go to Step 6.

STEP 6.

Will assistance continue to be provided?

No If "No," provide written notification of the decision to terminate assistance to the client and the local conservation district, if one exists. Document the decision, including the reasons, on NRCS-CPA-52 and proceed with planning.

Yes If "Yes," the District Conservationist should design or modify the proposed action or alternative to minimize the adverse effects to the extent possible. Circulate a written public notice locally explaining why the action is proposed to be located in the 100-year floodplain. Document the decision, including the reasons, on form NRCS-CPA-52 and proceed with planning.

Notes:

--

INVASIVE SPECIES
NECH 610.30
Evaluation Procedure Guide Sheet

Client/Plan Information:
Santaquin City, Utah
Santaquin Storm Drain
WFPO Program 2017 Funding

Check all that apply to this Guide Sheet review:	<input type="checkbox"/> Alternative 1	<input type="checkbox"/> Alternative 2	<input type="checkbox"/> Other
---	--	--	--------------------------------

NOTE: The GM 190, Part 414 states that "NRCS shall not authorize, fund, or carry out actions that it believes are likely to cause or promote the introduction and spread of invasive species in the U.S. or elsewhere."

STEP 1.

Is the proposed action or alternative in an area where invasive species are known to occur or where risk of an invasion exists? **NOTE:** Executive Order 13112 (1999) directs Federal agencies to "prevent the introduction of invasive species, provide for their control, and to minimize the economic, ecological, and human health impacts that invasive species cause."

- No If "No," additional evaluation is not needed concerning invasive species. Document the finding on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," go to Step 2.
- Unknown If "Unknown", consult Section II of the FOTG for a listing of invasive species in the area and/or the appropriate technical specialist to determine the potential for introduction of new invasive species into the area.

STEP 2.

Conduct an inventory of the invasive species and identify areas at risk for future invasions (GM 190, Part 414.30). Delineate these areas on the conservation plan map and document management considerations in the plan or assistance notes. Have all appropriate tools, techniques, management strategies, and risks for invasive species prevention, control, and management been considered in the planning process?

- No If "No," you must consider and include all appropriate factors relating to the existing and potential invasive species for the planning area and repeat Step 2.
- Yes If "Yes," describe strategies, techniques, and reasons on NRCS-CPA-52 and go to Step 3.

STEP 3.

Is the proposed action or alternative consistent with the E.O. 13112, the National Invasive Species Management Plan (<http://www.invasivespeciesinfo.gov/laws/execorder.shtml>), and/or an applicable State or local Invasive Species Management Plan?

- No If "No," modify the action and repeat Step 3. If the client is unwilling to modify the proposed action, NRCS must discontinue assistance. Document the circumstances on the NRCS-CPA-52 and in the case file.
- Yes If "Yes," describe strategies, techniques, and reasons, on the NRCS-CPA-52 and proceed with planning.

Notes:

--

**MIGRATORY BIRDS, BALD AND GOLDEN
EAGLE PROTECTION ACT, NECH 610.31
Evaluation Procedure Guide Sheet**

Check all that apply to this Guide Sheet review: Alternative 1 Alternative 2 Other

Client/Plan Information:

Santaquin City, Utah

Santaquin Storm Drain

WFPO Program 2017 Funding

NOTE: This guide sheet includes evaluation guidance for compliance with both the Migratory Birds Treaty Act, Executive Order 13186 (2001), and the Bald and Golden Eagle Protection Act. Both sections must be completed if eagles are identified within the area of potential effect.

MIGRATORY BIRDS TREATY ACT

In the lower 48 states, all species except the house sparrow, rock pigeon, common starling, and non-migratory game birds like pheasants, gray partridge, and sage grouse, are protected.

STEP 1.

Could the proposed action or alternative result in a "take" (intentionally or unintentionally) to any migratory bird, nest or egg? **"Take"** means to pursue, hunt, shoot, wound, kill, trap, capture, or collect, or attempt to pursue, hunt, shoot, wound, kill, trap, capture, or collect (50 CFR 10.12). **NOTE:** The MBTA does not contain any prohibition that applies to the destruction of a migratory bird nest alone (without birds or eggs) provided that no possession occurs during the destruction (USFWS, Migratory Bird Memorandum, MBPM-2, April 2003).

- No If "No," additional evaluation is not needed concerning migratory birds. Document the finding, including the reasons, on form CPA-52 and proceed with planning.
- Yes If "Yes," go to Step 2.

STEP 2.

Is it the purpose of the proposed action or alternative to intentionally "take" a migratory bird or any part, nest or egg (such as, but not limited to: controlling depredation by a migratory bird, or removal of occupied nests of nuisance migratory birds)? **NOTE:** Take of migratory game birds is exempt, as provided for under state and Federal hunting regulations.

- No If "No," go to Step 3.
- Yes If "Yes," document the effects, including the reasons, on form NRCS-CPA-52. Inform the client that they must obtain a permit from USFWS and any required state permit before the action is implemented.

STEP 3.

Have adverse effects on migratory birds been mitigated (avoided, reduced, or minimized) to the maximum practicable extent?

- No If "No," modify the alternative and repeat Step 1. If client is unwilling to modify the action then NRCS must discontinue assistance until issue has been resolved with USFWS.
- Yes If "Yes," document mitigation measures and go to Step 4.

MIGRATORY BIRDS TREATY ACT / BALD AND GOLDEN EAGLE PROTECTION ACT (continued)**STEP 4.**

Will unintentional take of migratory birds, either individually or cumulatively, result in a measurable negative effect on a migratory birds population?

- No If "No," additional evaluation is not needed concerning migratory birds. Document the finding, including the reasons, on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," additional principles, standards and practices shall be developed in coordination with USFWS to further lessen the amount of unintentional take (EO 13186(3)(e)(9)). Repeat Step 1 or indicate which of the following options is pursued by the client:
- The client will obtain a permit from USFWS before the action is implemented; OR
 - NRCS may need to terminate assistance. Contact the NRCS State Environmental Specialist or Wildlife Biologist.

Notes:**BALD & GOLDEN EAGLE PROTECTION ACT****STEP 1.**

Will the proposed action or alternative result in the take, possession, sale, purchase, barter, or offer to sell, purchase, or barter, export or import "of any bald or golden eagle, alive or dead, including any part, nest, or egg, unless allowed by permit?" **"Take"** is defined as "pursue, shoot, shoot at, poison, wound, kill, capture, trap, collect, molest or disturb" a bald or golden eagle. The term "disturb" under this Act means to agitate or bother a bald or golden eagle to a degree that causes, or is likely to cause, based on the best scientific information available; 1) injury to an eagle; 2) a decrease in its productivity, by substantially interfering with normal breeding, feeding, or sheltering behavior, or; 3) nest abandonment, by substantially interfering with normal breeding, feeding, or sheltering behavior.

- No If "No," additional evaluation is not needed. Document the finding, including the reasons, on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," go to Step 2.

STEP 2.

Can the proposed action or alternative be modified to avoid the adverse effect?

- No If "No," document the finding, including the reasons, on form NRCS-CPA-52. Contact the NRCS State Biologist or appropriate NRCS official about working with the client and USFWS to permit the action or finding another alternative action to avoid adverse effects prior to providing final designs or implementing the proposed action or alternative. No permit authorizes the sale, purchase, barter, trade, importation, or exportation of eagles, or their parts or feathers. The regulations governing eagle permits can be found in 50 CFR Part 22 (Eagle Permits).
- Yes If "Yes," modify the alternative and repeat Step 1.

Notes:

PRIME AND UNIQUE FARMLANDS
NECH 610.32
Evaluation Procedure Guide Sheet

Client/Plan Information:
Santaquin City, Utah
Santaquin Storm Drain
WFPO Program 2017 Funding

Check all that apply to this Guide Sheet review:	<input type="checkbox"/> Alternative 1	<input type="checkbox"/> Alternative 2	<input type="checkbox"/> Other
---	--	--	--------------------------------

STEP 1.

Using the criteria found in the FPPA Rule (7 CFR Part 658.5), does the proposed action or alternative convert farmland to a nonagricultural use? NOTE: Conversion does not include construction of on-farm structures necessary for farm operations. Also, form AD-1006 entitled "Farmland Conversion Impact Rating" and form NRCS-CPA-106 entitled "Farmland Conversion Impact Rating for Corridor Type Projects" are used to document effects of proposed projects that may convert farmland.

- No If "No," additional evaluation is not needed concerning prime and unique farmland. Document the finding on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," go to Step 2.
- Unknown If "Unknown," consult Section II of the FOTG and FPPA Rule and repeat Step 1. If you are still uncertain about the effects of prime and unique farmlands in your planning area, consult your State Soil Scientist.

STEP 2.

Are prime or unique farmlands or farmlands of statewide or local importance present in or near the area that will be affected by the proposed action or alternative?

- No If "No," additional evaluation is not needed concerning prime and unique farmland. Document the finding on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," go to Step 3.

STEP 3.

Can the proposed action or alternative be modified to avoid adverse effects or conversion?

- No If "No," document the adverse effects on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," modify and repeat Step 2 or contact the State Soil Scientist for further assistance.

Notes:

--

RIPARIAN AREA
NECH 610.33
Evaluation Procedure Guide Sheet

Client/Plan Information:
Santaquin City, Utah
Santaquin Storm Drain
WFPO Program 2017 Funding

Check all that apply to this Guide Sheet review:	<input type="checkbox"/> Alternative 1	<input type="checkbox"/> Alternative 2	<input type="checkbox"/> Other
---	--	--	--------------------------------

STEP 1.

Is a riparian area present in or near the planning area? (Definition can be found in the GM 190, Part 411.)

- No If "No," additional evaluation is not needed concerning riparian areas. Document the finding on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," go to Step 2.

STEP 2.

Does the proposed action or alternative conflict with the conservation values/functions of the riparian area?

- No If "No," go to Step 3.
- Yes If "Yes," explain the values/functions of riparian areas to the client, including their contribution to floodplain function, streambank stability and integrity, nutrient cycling, pollutant filtering, sediment retention, biological diversity, and present alternatives that will resolve the conflict (GM 190, Part 411.03). Then, go to Step 3.
- Unknown If "Unknown," refer to your state specific protocols to determine the current status of ecological function of the riparian area and project future conditions if the practice is implemented. If further assistance is required, contact your State Biologist.

STEP 3.

Does the proposed action or alternative maintain or improve water quality and quantity benefits provided by the riparian area?

- No If "No," alternatives must be developed which maintain or improve water quality and quantity benefits (GM 190, Part 411.03). When alternatives have been developed and discussed with the client, go to Step 4.
- Yes If "Yes," no additional evaluation is needed concerning Riparian Areas. Document the finding on form NRCS-CPA-52 and proceed with planning.

STEP 4.

Is the client willing to modify the proposed action or alternative so that water quality and quantity benefits provided by the riparian area are maintained or improved?

- No If "No," inform the client that NRCS policy requires that the conservation plan must maintain or improve water quality and quantity benefits of riparian areas where they exist (GM 190, Part 411.03). If the client remains unwilling to modify the proposed action, NRCS must discontinue assistance on those portions of the plan impacting riparian areas. If assistance is terminated, indicate the circumstances in the Remarks section of the NRCS-CPA-52. Be sure to also document in the case file that the values of riparian areas were explained to the client and alternatives were provided, but the client declined to modify the proposed action.
- Yes If "Yes," no additional evaluation is needed concerning Riparian Areas. Document the finding along with any mitigation actions or modifications on the NRCS-CPA-52 and proceed with planning.

Notes:

--

WETLANDS
NECH 610.34
Evaluation Procedure Guide Sheet

Client/Plan Information:
Santaquin City, Utah
Santaquin Storm Drain
WFPO Program 2017 Funding

Check all that apply to this Guide Sheet review:	<input type="checkbox"/> Alternative 1	<input type="checkbox"/> Alternative 2	<input type="checkbox"/> Other
---	--	--	--------------------------------

This guide sheet addresses policy relative to the Food Security Act of 1985, GM 190, Part 410.26, E.O. 11990 "Protection of Wetlands," and the NRCS Wetland Technical Assistance Policy 7 CFR Part 650.26. Use the Clean Water Act guide sheet for addressing wetland concerns relating to the Clean Water Act.

STEP 1.

Are wetlands present in or near the planning area? **NOTE:** This includes ALL wetlands except those artificial wetlands created by irrigation water. Thus, areas determined as Prior Converted (PC) per the 1985 Food Security Act and non-irrigation induced artificial wetlands (AW), which retain wetland characteristics, are wetlands as they relate to the Wetland Protection Policy.

- No If "No," document this on the NRCS-CPA-52. (If the area could qualify as an "other water of the U.S." such as lakes, streams, channels, or other impoundment or conveyances, a Clean Water Act Section 404 or River and Harbors Act Section 10 permit may be required from the Corps of Engineers. Refer to the Clean Water Act Guide sheet.)
- Yes If "Yes," document and go to Step 2.

STEP 2.

Will the proposed action or alternative impact any wetland areas (this includes changing wetland types when considering wetland restoration projects)?

- No If "No," document this on the form NRCS-CPA-52, along with any additional supporting evidence, and proceed with planning.
- Yes If "Yes," describe (on the NRCS-CPA-52) the effects of the proposed activity on the wetland area. Proceed to Step 3.

STEP 3.

Do practicable actions or alternatives exist which either enhance wetland functions and values, or avoid or minimize harm to wetlands?

- No If "No," a "minimal effects determination" will need to be conducted. (For State-specific protocols, consult with your State Wetland Specialist.) If it is determined that impacts to wetlands are likely to be minimal, proceed with planning. **If it is determined that the action will likely exceed minimal effects, NRCS can provide assistance only if an adequate compensatory mitigation plan is provided.** NRCS can assist with the development of a compensatory mitigation plan for the functions and values that were lost. Prior to or concurrent with NRCS, the client should obtain all necessary permits or approvals related to work in the wetland. Document on NRCS_CPA-52 and proceed with planning.
- Yes If "Yes," inform the client and advise them of the available option(s). (If there is a practicable action or alternative that will avoid impacts, the client MUST choose the alternative. HOWEVER, under Swampbuster, if the participant wants to convert a wetland the statute affords the mitigation exemptions without question.) Proceed to Step 4.

WETLANDS (continued)

STEP 4.

Does the client wish to pursue an identified practicable action or alternative that will enhance wetland functions and values, or avoid/minimize harm to wetlands?

- No If "No," advise the client regarding eligibility criteria under the FSA as amended, and that the NRCS may assist with the development of acceptable associated mitigation plan for swampbuster, but can not offer further technical or financial assistance for the wetland conversion activity itself. Prior to or concurrent with NRCS assistance, the client should obtain all necessary permits or approvals related to work in wetlands. Document on the NRCS-CPA-52.
- Yes If "Yes," continue with planning and technical assistance for the activity, and, if applicable, the development of an associated mitigation plan. Prior to or concurrent with NRCS assistance, the client should obtain all necessary permits or approvals related to work in wetlands (including those required under the Clean Water Act). Document effects on the NRCS-CPA-52.

Notes:

WILD AND SCENIC RIVERS
NECH 610.35
Evaluation Procedure Guide Sheet

Client/Plan Information:
Santaquin City, Utah
Santaquin Storm Drain
WFPO Program 2017 Funding

Check all that apply to this Guide Sheet review:	<input type="checkbox"/> Alternative 1	<input type="checkbox"/> Alternative 2	<input type="checkbox"/> Other
---	--	--	--------------------------------

STEP 1.

Could the proposed action or alternative have an effect on the natural, cultural and recreational values of any nearby river(s)?

- No If "No," additional evaluation is not needed concerning Wild and Scenic Rivers. Document the finding on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," analyze the potential effects and develop alternatives, as necessary, that would mitigate potential adverse effects, then go to Step 2.

STEP 2.

Is there a Federal or State designated Wild, Scenic, or Recreational River segment or a river listed in the National River Inventory in or near the planning area?

- No If "No," additional evaluation is not needed concerning Wild and Scenic Rivers. Document the finding on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," and there is still potential for effect consult your State Environmental Liaison to assist with determining significance. Go to Step 3. **Note:** The State Office may request the National Park Service to assist you in developing appropriate avoidance/mitigation measures. (Remember that if an action/activity has not been sufficiently analyzed to determine if it may be significant (either beneficial or adverse), an EA or EIS may be required)
- Unknown If "Unknown," consult Section II of the FOTG for a list or the location of Wild, Scenic, or Recreational Rivers of river segments (or see the NPS list of Wild and Scenic Rivers and the "Nationwide Rivers Inventory") and repeat Step 2.

STEP 3.

Upon further analysis, could the proposed action or alternative have an **adverse effect or have the effects been found to be significant** on the natural, cultural and recreational values of the Wild, Scenic, or Recreational River segment?

- No If "No," document the finding, including the reasons, on form NRCS-CPA-52 and proceed with planning.
- Yes If "Yes," go to Step 4.

STEP 4.

Is NRCS providing financial assistance or otherwise controlling the proposed action or alternative?

- No If "No," go to Step 5.
- Yes If "Yes," an environmental assessment (EA) or, if the effects are significant, an environmental impact statement (EIS) must be prepared. Check "Q 5)" on the NRCS-CPA-52 and provide documentation regarding the action/activity to you State Environmental Liaison for further analysis.

WILD AND SCENIC RIVERS (continued)

STEP 5.

Will a Federal agency other than NRCS provide funding or otherwise control implementation of the action?

- No If "No," inform the client that a permit may be required for their activities and they should consult with the NPS. The permit authorization should be reflected in the final plan and documentation.
- Yes If "Yes," indicate on the NRCS-CPA-52, that the lead agency should consult with the NPS.

Notes:

RESOURCE CONSIDERATIONS (Optional)

Field Inventory Guide Sheet

Client/Plan Information:

Santaquin City, Utah
 Santaquin Storm Drain
 WFPO Program 2017 Funding

Identify the resource concern(s) that need to be addressed and the assessment tool(s) used for the evaluation.

SOIL	<p>Erosion</p> <input type="checkbox"/> Sheet and Rill <input type="checkbox"/> Wind <input type="checkbox"/> Ephemeral Gully	<input type="checkbox"/> Classic Gully <input type="checkbox"/> Streambank <input type="checkbox"/> Shoreline	<input type="checkbox"/> Irrigation Induced <input type="checkbox"/> Mass Movement <input type="checkbox"/> Road, Road Sides & Construction Sites	<input type="checkbox"/> Other: _____ <input type="checkbox"/> Other: _____	
	<p>Condition</p> <input type="checkbox"/> Organic Matter Depletion <input type="checkbox"/> Rangeland Site Stability <input type="checkbox"/> Compaction	<input type="checkbox"/> Subsidence <input type="checkbox"/> Contaminants-Salts & Other Chemicals <input type="checkbox"/> Contaminants-Animal Waste & Other Organics <input type="checkbox"/> Contaminants-Commercial Fertilizer	<input type="checkbox"/> Contaminants-Residual Pesticides <input type="checkbox"/> Damage from Soil Deposition		
<p>Assessment tools, Problems & Notes:</p>					
WATER	<p>Quantity</p> <input type="checkbox"/> Excessive Seepage <input type="checkbox"/> Excessive Runoff, Flooding, or Ponding <input type="checkbox"/> Excessive Subsurface Water <input type="checkbox"/> Drifted Snow <input type="checkbox"/> Inadequate Outlets <input type="checkbox"/> Inefficient Water Use on Irrigated Land <input type="checkbox"/> Inefficient Water Use on Non-irrigated Land <input type="checkbox"/> Reduced Capacity of Conveyances by Sediment Deposition <input type="checkbox"/> Reduced Storage of Water Bodies by Sediment Accumulation <input type="checkbox"/> Aquifer Overdraft <input type="checkbox"/> Insufficient Flows in Water Courses <input type="checkbox"/> Rangeland Hydrologic Cycle <input type="checkbox"/> Other:	<p>Quality</p> <input type="checkbox"/> Harmful Levels of Pesticides in Groundwater <input type="checkbox"/> Excessive Nutrients and Organics in Groundwater <input type="checkbox"/> Excessive Salinity in Groundwater <input type="checkbox"/> Harmful Levels of Heavy Metals in Groundwater <input type="checkbox"/> Harmful Levels of Pathogens in Groundwater <input type="checkbox"/> Harmful Levels of Petroleum in Groundwater <input type="checkbox"/> Harmful Levels of Pesticides in Surface Water <input type="checkbox"/> Excessive Nutrients and Organics in Surface Water <input type="checkbox"/> Excessive Suspended Sediment & Turbidity in Surface Water <input type="checkbox"/> Excessive Salinity in Surface Water <input type="checkbox"/> Harmful Levels of Heavy Metals in Surface Water <input type="checkbox"/> Harmful Temperatures of Surface Water <input type="checkbox"/> Harmful Levels of Pathogens in Surface Water <input type="checkbox"/> Harmful Levels of Petroleum in Surface Water			
	<p>Assessment tools, Problems & Notes:</p>				
AIR	<p>Quality</p> <input type="checkbox"/> Particulate matter less than 10 micrometers in diameter <input type="checkbox"/> Particulate matter less than 2.5 micrometers in diameter <input type="checkbox"/> Excessive Ozone <input type="checkbox"/> Excessive Greenhouse Gas - CO2 <input type="checkbox"/> Excessive Greenhouse Gas - N2O <input type="checkbox"/> Excessive Greenhouse Gas - CH4	<input type="checkbox"/> Ammonia (NH3) <input type="checkbox"/> Chemical Drift <input type="checkbox"/> Objectionable Odors <input type="checkbox"/> Reduced Visibility <input type="checkbox"/> Undesirable Air Movement <input type="checkbox"/> Adverse Air Temperature			<input type="checkbox"/> Other: _____ <input type="checkbox"/> Other: _____
	<p>Assessment tools, Problems & Notes:</p>				
PLANTS	<input type="checkbox"/> Plants are not adapted or suited	<input type="checkbox"/> Declining Species, Species of Concern <input type="checkbox"/> Productivity, Health and Vigor <input type="checkbox"/> Noxious and Invasive Plants			<input type="checkbox"/> Wildfire Hazard <input type="checkbox"/> Other:
	<p>Condition</p> <input type="checkbox"/> Impaired Forage Quality and Palatability <input type="checkbox"/> Threatened or Endangered Species	<p>Assessment tools, Problems & Notes:</p>			
ANIMALS	<p>Fish and Wildlife</p> <input type="checkbox"/> Inadequate Food <input type="checkbox"/> Inadequate Cover/Shelter <input type="checkbox"/> Inadequate Space <input type="checkbox"/> Plant Community Fragmentation <input type="checkbox"/> Imbalance Among and Within Populations <input type="checkbox"/> Threatened and Endangered Species <input type="checkbox"/> Declining Species, Species of Concern	<input type="checkbox"/> Inadequate Water	<p>Domestic Animals</p> <input type="checkbox"/> Inadequate Quantities and Quality of Feed & Forage <input type="checkbox"/> Inadequate Shelter <input type="checkbox"/> Inadequate Stock Water <input type="checkbox"/> Stress and Mortality		
	<p>Assessment tools, Problems & Notes:</p>				

ADDENDUM 1
INDIVIDUAL DEBRIS BASIN BENEFIT ANALYSIS

This addendum is included in response to the following request made during the Final EA review:

Input the benefits per structure as part of incremental analysis for the aggregated NED. This incremental analysis should be add on Appendix D. Individual benefits shall be known in the unlikely event that all the debris basins are not constructed. If the state cannot add the incremental analysis then a justification shall be submit to NHQ of why the request cannot be done.

The Santaquin Watershed Project in Utah calls for five debris basins to control flooding. The original plan did not rank the basins on cfs control or average annual benefits. The table below displays this information. The total estimated average annual benefits are \$478,600. Flow rates from each watershed are shown without and with the basin to demonstrate the amount of flow rate captured by each proposed debris basin and to estimate a corresponding benefit.

The ranking is provided so that if total funding is not available all at once, prioritization can occur. Some local opinion may differ on the ranking of basin six, as it is the northernmost basin and controls primarily agricultural land, however it does provide a great deal of control as opposed to ranks 4 and 5. Note that while other storm events were analyzed, the basins control analysis is only for the storms listed in the table.

Table 1. Rank of Funding for Basins

Watershed	100-yr			200-yr			500-yr			Total Control	Pct. Of Total	Estimated Average Annual Benefits	Rank
	Existing Flow	Plan Flow	Control	Existing Flow	Plan Flow	Control	Existing Flow	Plan Flow	Control				
1	301	17	284	404	95	309	570	344	226	819	0.27	\$ 127,174	1
2&3	77	4	73	105	22	83	152	80	72	228	0.07	\$ 35,313	5
4	292	17	275	396	107	289	564	361	202	767	0.25	\$ 118,979	2
5	210	15	195	296	96	200	438	305	133	528	0.17	\$ 82,020	4
6	263	13	250	353	78	275	502	286	217	742	0.24	\$ 115,114	3
										3083	1.00	\$ 478,600	

APPENDIX E

SUPPORTING INFORMATION



**Supplemental Watershed Plan No. 1 and Environmental
Assessment for Santaquin Flood Prevention**

Santaquin Watershed
Utah County, Utah

October 2019



SANTAQUIN CITY CORPORATION

45 West 100 South
Santaquin, UT 84655
(801) 754-3211
(801) 754-3526 fax

MEMO

TO: City Council

FROM: City Manager's Office-Shannon Hoffman

DATE: October 29, 2002

RE: Flood / Mudslide numbers

Since the flood/mudslides that occurred September 12-16, city staff has kept very detailed records of volunteer hours, equipment used, infrastructure damage, etc. from the clean-up of the East Side Subdivision. These numbers will be used to determine whether or not the residents impacted by this disaster would be eligible for Federal Emergency Funds and/or Small Business Administration (SBA) assistance. Each of these agencies have a minimum criteria that must be met before any sort of assistance would be available to the residents affected. SBA was contacted and was on site on September 19th to inspect the damages (see attached report). Unfortunately, the identified damage was not sufficient enough to meet their minimum criteria of at least 25 homes and/or businesses, each of which has sustained 40% or more uninsured loss. FEMA has a minimum criteria of \$2,000,000 in uninsured damages before they will offer any kind of assistance. Listed below is the information that has been collected, calculated dollar amounts, and out of pocket dollars that have been paid by the City. Also, attached is a spreadsheet with the same information.

- **Volunteer Hours.**

Public. The time spent by volunteers was kept track of each day as they would arrive and leave the disaster site. The rate per hour for each volunteer was given to us by FEMA and is \$12.00 per hour. The total number of volunteer hours was 7,688 hours, which came to \$90,672.00. We are still tracking these hours as they come in.

Fire Department. The Fire Department spent 1,096 hours from 9-12 to 9-16

with disaster related functions such as traffic control, transportation of residents to the site, checking flood areas, manning the command post, etc. They will be compensated for these hours on their yearly check. The total compensation for the hours spent performing disaster related tasks is \$9,123.78.

City Employees. The hours spent by our city employees were turned in and paid at an overtime rate. The total number of hours spent by our city employees were 590 hours. The total amount calculated for time spent by city employees was \$20,064.01, with only \$11,292.61 actually being paid out.

- **Equipment.**

Public. Any equipment that was used for the clean-up of the mudslide was logged in when the equipment arrived and logged out as they finished. There was a variety of equipment each having its own FEMA cost per hour depending on the type and size of the equipment. A lot of the equipment and the cost of the operator were donated by the cities and companies who worked to clean up the site, the FEMA rates were used for these donated services. The total amount of donated equipment was \$23,665.29. The operator cost for the donated services were \$8,337.00. There have been several requests for payment submitted by equipment owners. As of this date we have paid out \$10,676.63 for use of equipment and operator compensation. We do expect to receive additional invoices, which will increase the amount paid out of pocket by the city. A breakdown of these item can be found on the attached spreadsheet.

Fire. Each fire vehicle that was used for any disaster task was logged in and out as it was needed for traffic control, transportation, checking flood area, etc. The total number of hours for the fire equipment was 314.5 hours. The FEMA rates for fire vehicles was used for calculation of this total, which came to \$10,362.40.

City. All city equipment was used during the duration of the clean-up. The total number of hours calculated was 160 hours. Using the FEMA rates for equipment the total was \$2,496.00. The cost of the operator for the equipment is included in the city overtime hours.

- **Infrastructure Damages**

A breakdown of damages to the infrastructure in the East Side Subdivision can be found on the attached spreadsheet. These damages are estimated to be \$194,752.00. If there are any question regarding these totals, you can contact Mark Stevenson at the office.

Santiquin City Flood/Mudslide

Volunteer Hours	Total Hours	Per Hour	Cost	Out of Pocket Pd
Public	7688	\$12.00	\$92,256.00	\$0.00
Fire	1096	Varies	\$9,123.78	\$9,123.78
City	590	Overtime	\$20,064.01	\$11,292.61

Equipment

Public (Equipment Only)	822	Varies	\$34,341.92	\$10,676.63
Public (Equipment Operator)	694.75	\$12.00	\$8,337.00	\$0.00
Fire	314.50	Varies	\$10,362.40	\$0.00
City	160	Varies	\$2,496.00	\$0.00

Infrastructure Damage

See Attachment for Breakdown			\$194,752.00	
------------------------------	--	--	--------------	--

Misc.

Fuel	2729.60 gal		\$3,490.61	\$3,490.61
Delivery Time	10 hours	\$55.00	\$550.00	\$550.00

TOTAL

\$375,773.72

\$35,133.63

* EXPECTING MORE INVOICES TO BE TURNED IN FOR PAYMENT

- **Miscellaneous Items**

The miscellaneous items include fuel for equipment and delivery time. Springlake totals for equipment, volunteer hours, damages, etc. will also be listed as they are available.

Conclusion

Springlake and the Dry Mountain mudslide costs can be combined in an effort to reach the \$2,000,000 threshold. As of this date, the total for Santaquin is \$375,773.72. We do not have all the totals from Springlake, but as you can tell, reaching the 2,000,000 mark will be probably not occur. We did, however, want the residents effected by this disaster to feel like the City has done its best to help them receive any assistance. Since it appears that it is unlikely that federal funds will be received, costs associated with the damage and repair of the Dry Mountain mudslides/floods will be wholly born by the local residents and the city. If you have any questions or would like to review any of the records, please don't hesitate to call me.

EASTSIDE SUBDIVISION FLOOD DAMAGE ESTAMATES TO INFRASTRUCTURE

	ITEM DESCRIPTION	QUANTITY	UNITS	DEMO ESTIMATE	REPLACEMENT COSTS	TOTALS
1	SIDEWALKS	2158	LIN FT	\$ 17,264.00	\$ 25,896.00	\$ 107,840.00
2	CURB & GUTTER	3234	LIN FT	\$ 25,872.00	\$ 38,808.00	\$ 64,680.00
3	CROSS GUTTERS	66	LIN FT	\$ 1,782.00	\$ 1,650.00	\$ 3,432.00
4	CURB BOXES FOR STORM DRAIN	16	EACH	\$ 250.00		\$ 4,000.00
5	SUMPS FOR STORM DRAINS	6	EACH	\$ 250.00		\$ 1,500.00
6	SEWER MANHOLES	10	EACH	\$ 250.00		\$ 2,500.00
7	ROAD DAMAGE	300	LIN FT	\$ 14.00		\$ 4,200.00
8	GAS METERS	4	EACH	\$ 250.00		\$ 1,000.00
9	WATER METERS	10	EACH	\$ 110.00		\$ 1,100.00
10	STORM RETENTION BASIN	1	EACH	\$ 4,500.00		\$ 4,500.00

\$ 194,752.00

U.S. SMALL BUSINESS ADMINISTRATION

Damage Assessment Report

Director for Area Office: **Area 3, Ft. Worth, Texas**

State Utah	Name of Governor or Authorized Representative Michael Leavitt	Date of Request September 17, 2002
----------------------	---	--

Type and Cause of Disaster Heavy Rain - Run-off and Mudslide	Date(s) of Occurrence 9/12/02	Date(s) of Survey September 19, 2002
--	---	--

County or Political Subdivision Utah County Seat: Provo County population 360000	SBA Survey Team Member (s) State: Jerryann Kolby - 801-209-7513 - John Rokich - 801-538-3400 City: Tom Hodgson, Dave Bennet, Mark Stevenson - 801-754-3211 - SBA: Joe Pavlas - 817-684-5600
---	---


DAMAGE SUMMARY

	Estimated Properties Affected				Majors Damage Qualifying for SBA Purposes		
	Homes		Businesses			Number	\$ Amount
	Number	\$ Amount	Number	\$ Amount	Homes		
Majors	5	\$197,000	2	\$40,500	Business	2	\$40,500
Minor	27	\$268,000	0	\$0	Nonprofit	0	\$0
TOTALS	32	\$465,000	2	\$40,500	TOTALS	7	\$237,500

Comments:

Run-off and Mud slide destroyed homes, filled basements to 5 ft deep. Mud rocks and debris covered streets. American Red Cross report was not available
 Insurance coverage for the affected area is approximately 0 % for this type of damage
 Average income levels of the affected area(s) are approximately 40% low 50 % middle 10 % high
 There are 0 Manufactured houses in the damaged totals.
 1 renters with damage are included in the totals
 N.F.I.P. status for the affected area is Participating
 Historical structures were not reported as affected
 Temporary office space may be obtained from Santaquin City - Roger Carter - 801-754-3211 ext. 17
 Temporary lodging may be obtained in Provo (20 miles) and Payton (10 miles)

Area Office Recommendation Approve Disapprove

Area Director Signature  Date 9-23-02

PLEASE NOTE: The estimated burden for completing this form is 5 minutes per response. You are not required to respond to any collection of information unless it displays a current valid OMB approval number. Comments on the burden should be sent to U.S. Small Business Administration, Chief, AIB, 409 3rd St., SW, Washington, DC 20503. OMB Approval (3245-0136). PLEASE DO NOT SEND FORMS TO OMB.
 SBA Form 387 (2-01)



U.S. SMALL BUSINESS ADMINISTRATION
WASHINGTON, D.C. 20416

SEP 30 2002

Honorable Michael O. Leavitt
Governor of Utah
Salt Lake City, Utah 84114

Dear Governor Leavitt:

This responds to your request of September 17, 2002 for a disaster declaration by the Small Business Administration (SBA) for Utah County as a result of damages caused by severe thunderstorms, flash flooding that occurred on September 12.

As you may know, a survey to determine the extent of the damages was conducted by SBA personnel, accompanied by State and local officials, on September 19. Unfortunately, the identified damage was not sufficient to meet our minimum criteria of at least 25 homes and/or businesses, each of which has sustained 40 percent or more uninsured loss. Therefore, on September 30, 2002, Administrator Hector V. Barreto determined that an SBA disaster declaration would not be approved for Utah County.

I regret that we are unable to be of assistance in this matter.

Sincerely,

Herbert L. Mitchell
Associate Administrator
for Disaster Assistance

SBA IS AN EQUAL OPPORTUNITY EMPLOYER AND PROVIDER

Prepared

By: Nathan Clarke, Environmental Specialist

Date: August 30, 2018

Memorandum

Subject: Aquatic Resources Inventory
Santaquin Debris Basins

Introduction

The United States Department of Agriculture Natural Resources Conservation Service (USDA-NRCS), in cooperation with Santaquin City as the project sponsor, is considering proposed improvements within the Santaquin east bench watersheds. The proposed improvements include the construction of up to six (6) stormwater debris basins and associated facilities along the eastern foothills in Santaquin. Improvements under consideration may be partially funded through the Watershed Protection and Flood Prevention Act of 1954 (PL83-566) and will address flood prevention and control, water conservation, and public safety risks while supporting existing agricultural and municipal land use.

The proposed project is located in Utah County along the east bench of Santaquin. The National Environmental Policy Act (NEPA) and the Council on Environmental Quality's regulations at 40 CFR Parts 1500-1508 require an evaluation of potential environmental impacts associated with federal projects and actions with input from the public.

This memo summarizes the findings from the work done by Horrocks Engineers and addresses potential project impacts to wetlands and others waters of the U.S. (WoUS).

Methodology

The inventory fieldwork was conducted by Nathan Clarke on June 20, 2018. Prior to visiting the project location, National Wetlands Inventory (NWI) maps were studied to help identify potential waters. The project study area was visited and potential WoUS were identified and mapped based on visual characteristics, surface hydrology, and vegetation. An aquatic resources delineation was not conducted and a jurisdiction determination from the U.S. Army Corp of Engineers (USACE) was not obtained.

Results

One canal (Strawberry Highline Canal) and one potential wetland were located within the study area. National Wetland Inventory (NWI) maps identified four intermittent streams coming from the major canyons to the east. Each of these areas were surveyed during the field visit and characteristics of an Ordinary High Water Mark (OHWM) were not observed in these features, namely, break in the bank slope, drift deposits, and change in vegetation cover. They do not meet the USACE's definition of a WoUS, thus are not considered jurisdictional.

The area was predominantly covered by a mix of native and introduced grasses, shrubs, and upland vegetation found within the Foothill plant community.

Potential Wetlands

One potential wetland was identified within the study area adjacent to outfall location #3 (see map 1 and Figure 7 and 8). The area was dominated by *Salix exigua* and *Schoenoplectus pungens*. The water source for this wetland is a small spring on the east side of the wetland. The water flows west until it reaches a man-made berm, where the wetland ends. It appears the wetland is isolated and does not have any connection to a navigable waters of the U.S.

Waters of the U.S.

The Strawberry Highline Canal is an irrigation canal that flows from the mouth of Spanish Fork Canyon through Santaquin and toward Utah Lake. The canal is concrete-lined and flows through the northern most part of the study area (see map 3 and Figure 3 and 4).

Conclusion

The proposed project will be designed with the intent to avoid impacts to the potential wetlands and other WoUS that were identified during the survey. If impacts to these waters can be avoided, no Department of the Army permit will be required.

Below are photographs of what was observed during the field visit.



Figure 1- Depression near outflow location 6



Figure 1- Depression near outflow location 6



Figure 3- Strawberry Highline Canal looking northeast



Figure 4- Strawberry Highline Canal looking southeast



Figure 5- Depression near outflow location 5



Figure 6- Depression near outflow location 4



Figure 7- Potential wetland near outflow location 3



Figure 8- Potential wetland near outflow location 3




Figure 9- Depression near outflow location 2 and 3



Figure 10- Depression near outflow location 1




Appendix A: Maps




C:\12018\UT-1024-1801_Santaquin Debris Basin Plan EAP\Project Data\GIS\Horrocks\Map\Project Location Map.mxd, 6/20/2018 5:03:10 PM, nashans

- * Outflow Locations
- Study Area



Santaquin Debris Basin Plan
Project Location Map

O:\2018\UT-1024-1801-Santaquin-Debris-Basin-Plan-EA\Project-Data\GIS\Horrocks\Mxd\Wetland-Inventory.mxd, 6/21/2018 4:52:17 PM, nathanc



- Legend**
- Study Area
 - Canal
 - Potential Wetland Area

✱ Outflow Locations





**Santaquin Debris Basin Plan
Aquatic Resources Inventory Map**

1 inch = 500 feet





0 500 1,000
Feet

Map 1 of 3

O:\2018\UT-1024-1801-Santaquin-Debris-Basin-Plan-EA\Project-Data\GIS\Horrocks\Mxd\Welland-Inventory.mxd, 6/21/2018 4:52:19 PM, nathanc




Legend

-  Study Area
-  Canal
-  Potential Wetland Area
-  Outflow Locations




**Santaquin Debris Basin Plan
Aquatic Resources Inventory Map**

1 inch = 500 feet




O:\2018\UT-1024-1801-Santaquin-Debris-Basin-Plan-EA\Project-Data\GIS\Horrocks\Mxd\Wetland-Inventory.mxd, 6/21/2018 4:52:21 PM, nathanc






Strawberry Highline Canal

Santaquin

6




Legend

-  Study Area
-  Canal
-  Potential Wetland Area

 Outflow Locations



1 inch = 500 feet



**Santaquin Debris Basin Plan
Aquatic Resources Inventory Map**



To: Project File
From: Craig Bown, Environmental Specialist
Date: August 22, 2018
Subject: Threatened and Endangered Species; Wildlife
Santaquin Debris Basins

Memorandum

Background

The United States Department of Agriculture Natural Resources Conservation Service (USDA-NRCS), in cooperation with Santaquin City, is evaluating proposed improvements within the Santaquin east bench watersheds. The proposed improvements could include solutions that would control and prevent flood debris flow impacts within the eastern foothills in Santaquin. Improvements under consideration may be partially funded through the Watershed Protection and Flood Prevention Act of 1954 (PL83-566) to address flood prevention and control, water conservation, and public safety risks while supporting existing agricultural and municipal land use.

Methods

The study area (see attached study area map) has been evaluated for federally listed species and their designated critical habitat protected under the Endangered Species Act (ESA) utilizing information obtained from U.S. Fish and Wildlife Service's (USFWS) Online Information, Planning, and Conservation system (IPaC) (see attached IPaC results). Known location data was also reviewed for federally listed species using data obtained from the Utah Division of Wildlife Resources (UDWR) Natural Heritage Program. Furthermore, a site visit was conducted to determine habitat suitability for federally listed species, potential nesting habitat for migratory birds, and other general wildlife. No official species surveys were conducted.

Affected Environment

Habitat

The study area is east of Santiquinn, Utah within the western foothills of Dry Mountain. Approximate elevations of the study area are between 5000 - 5800 feet. The associated vegetation community is a foothill woodland. General vegetation species within the study are include Gambel oak, Cliffrose, juniper spp., sagebrush spp., rabbit brush, and other native shrubs and grasses. The majority of the study area is undeveloped, however, regular use from off-highway vehicles is apparent. Other uses within the study area consist of fruit-tree orchards and unofficial camp sites. Immediately west of the study area are residential sub-divisions.

Threatened and Endangered Species

Threatened and Endangered species identified within the IPaC results are further evaluated in **Table 1** for the potential to occur within the study area.

Table 1: Study Area T&E Species Habitat Assessment

Species	Status	Habitat Synopsis ^{1,2,3}	Potential to occur within Study Area?
Mammals			
Canada lynx (<i>Lynx canadensis</i>)	Threatened	Prefers moist, cool coniferous forest that support snowshoe hare populations.	IPaC results did not identify any critical habitat within the study area. Additionally, the vegetation community within the study area does not meet the classification of a coniferous forest. It is not likely that Canada lynx is found within or near the study area.
Birds			
Yellow-billed Cuckoo (<i>Coccyzus americanus</i>)	Threatened	Riparian obligate and usually found in large tracts of cottonwood/willow habitats with dense sub-canopies.	IPaC results did not identify any critical habitat within the study area. Additionally, there is no suitable riparian habitat identified within 0.5 miles of the study area, as required by USFWS <i>Guidelines for the Identification of Suitable Habitat for WYBCU in Utah</i> . It is not likely that yellow-billed cuckoo is found within or near the study area.
Fishes			
June Sucker (<i>Chasmistes liorus</i>)	Endangered	Endemic to Utah Lake and the Provo River.	IPaC results did not identify any critical habitat within the study area. Additionally, these fish are found only within Utah Lake and spawn only in the connecting Provo River. Although Strawberry Highline Canal has a connection to Utah Lake, it is uncharacteristic habitat for June sucker utilization. It is not likely that June suckers would be found within or near the study area.


Species	Status	Habitat Synopsis ^{1,2,3}	Potential to occur within Study Area?
Flowering Plants			
Jones Cycladenia (<i>Cycladenia humilis</i> <i>var. jonesii</i>)	Threatened	Grows in gypsiferous soils that are shallow, fine textured, and intermixed with rock fragments. The species can be found in Eriogonum-Ephedra, mixed desert shrub, and scattered pinyon-juniper communities, at elevations ranging from 4000 to 6800 feet.	IPaC results did not identify any critical habitat within the study area. Additionally, the study area does not contain soil types required to support this species. It is not likely that Jones Cycladenia would be found within or near the study area.
Ute Ladies'-tresses (<i>Spiranthes diluvialis</i>)	Threatened	Found in wet meadows, along streams, in abandoned stream meanders, and near springs, seeps, and lake shores in sandy or loamy soils with mixed gravel.	IPaC results did not identify any critical habitat within the study area. However, the Strawberry Highline Canal and one potential wetland were identified as potential habitat areas within the study area (see attached maps). Field observations did not identify appropriate soils for this species along the canal as it is lined in concrete. Additionally, habitat conditions observed at the potential wetland area are not typical of conditions with known populations. Additionally, based on data obtained from UDWR Natural Heritage Program, there are no known instances of Ute ladies'-tresses occurring within one mile of the study area. It is not likely that Ute ladies'-tresses would be found within or near the study area.
¹ UDWR - Utah Conservation Data Center (https://dwrcdc.nr.utah.gov/ucdc/) ² USFWS Species Fact Sheets ³ USDA NRCS Plant Guides			

Wildlife


Sufficient habitat exist within the study area to support big game species, other common small mammals, and migratory birds. One mule deer (*Odocoileus hemionus*) and several bird species were observed during the site visit including black-capped chickadee (*Poecile atricapillus*), western kingbird (*Tyrannus verticalis*), American robin, (*Turdus migratorius*), broad-tailed hummingbird (*Selasphorus platycercus*), lazuli bunting, (*Passerina amoena*), lark sparrow, (*Chondestes grammacus*), Eurasian Collared-dove (*Streptopelia decaoctoringered*), black-billed magpie, (*Pica hudsonia*), American kestrel (*Falco sparverius*), turkey vulture (*Cathartes aura*), and prairie falcon, (*Falco mexicanus*).


Conclusion

Habitat within the study area would be impacted by the development of potential flood prevention solutions. However, from a regional perspective of available habitat, effects would be considered insignificant. The study area does not contain suitable habitat for any of the identified Threatened and Endangered species. Therefore, a potential project in this area would likely have no effect on federally-listed threatened and endangered species or their designated critical habitat. It is not expected that implementation of project would have a long-lasting negative affect on big game species and other common mammals found within the study area. Removal of vegetation during the spring and early summer months has potential to effect nesting migratory birds and would need to be avoided to remain complaint with the Migratory Bird Treaty Act.



1 inch = 500 feet

 Study Area




Santaquin Debris Basin Plan Study Area Map




1 inch = 500 feet

Study Area



Santaquin Debris Basin Plan Study Area Map




Strawberry Highline Canal


198


Santaquin

Strawberry Highline Canal



1 inch = 500 feet

 Study Area




Santaquin Debris Basin Plan Study Area Map

Pilot WS

WATERSHED PROTECTION

711 Cost Est.

WORK PLAN SANTAQUIN CANYON WATERSHED PROTECTION PROJECT UTAH



PREPARED BY
SOIL CONSERVATION SERVICE
UNITED STATES DEPARTMENT OF AGRICULTURE
SALT LAKE CITY, UTAH
1954

USDA - SC5 - ALBUQUERQUE, N. MEX. 1954
M-535

658.542

WORK PLAN
SANTAQUIN CANYON WATERSHED PROTECTION PROJECT
UTAH COUNTY, UTAH

PARTICIPATING AGENCIES

Nebo Soil Conservation District	Santaquin Livestock Association
Utah Power and Light Company	Extension Service, Utah County
Utah County	Utah State Fish & Game Commission
Genola Town	Agricultural Conservation Program USDA
Santaquin Town	Forest Service, U.S.D.A.
Summit Creek Irrigation Company	Soil Conservation Service U.S.D.A.
Nebo Stock Grazers Association	Bureau of Land Mgt. Dept. of Interior
Santaquin Canyon Watershed Committee	

Prepared by
United States
Department of Agriculture

Payson, Utah
September 22, 1954

Mr. Bradford Hatch
Work Unit Conservationist
Soil Conservation Service
Payson, Utah


Dear Mr. Hatch:

The Supervisors of our Soil Conservation District have reviewed carefully the work plan primarily for flood prevention and sediment reduction for the Santaquin Canyon Watershed.

We believe that the development of this watershed work plan by joint efforts of the participating agencies and land owners has resulted in a plan which we all thoroughly subscribe to and are willing to push through to completion according to the terms of cooperation and the schedule shown.

The work plan for the Santaquin Canyon watershed has been incorporated with and made a part of the Nebo Soil Conservation District work plans. A Supplemental Memorandum of Understanding and the watershed amendment have been entered into between the United States Soil Conservation Service and our District covering the general terms of cooperation and assumption of responsibilities in the execution of this kind of work.

Very truly yours,



Chairman,
Nebo Soil Conservation District

Mr. Ralph H. Felker
Area Conservationist
Soil Conservation Service
Provo, Utah

Santaquin, Utah
September 27, 1954

Dear Mr. Felker:

The Santaquin Canyon Watershed Protection Committee and the Nebo Soil Conservation District governing body have actively participated in the preparation of the attached work plan prepared primarily for flood prevention and sediment control for the Santaquin Canyon watershed.

This plan represents a common understanding and agreement on the kinds and amounts of measures needed to be applied in the Santaquin Canyon Watershed to achieve soil and water conservation on all of the lands in the watershed so as to bring about the greatest reduction in flood and sediment damages feasible at this time. Our common objective is to place the land in condition so that by practicing grass and browse management, it may be used for optimum sustained livestock use, water yield consistent with other related uses that it is capable. We believe the carrying out of the works of improvement outlined in the attached plan will accomplish the above objective.

The Santaquin Canyon Watershed Protection Committee consists of a member from each of the contributing non-federal organizations. These are Santaquin and Genola Cities, Utah Power & Light Co., Summit Creek Irrigation Company, Santaquin Livestock Association and Utah County. The civic clubs and Nebo Soil Conservation District are represented by a non-voting member.

Very truly yours,

Arthur F Wickman
Santaquin Canyon Watershed Protection Committee

9/27/54
Date

D. Lynn Crook
Santaquin City

9/27/54
Date

Burt J. Draper
Genola City

9/27/54
Date

Arthur F Wickman
Summit Creek Irrigation Company

9/27/54
Date

Theodore Ablin
Santaquin Livestock Association

9/27/54
Date

Stevling D. Jones
Utah County

9/27/54
Date

Lynn Clark
Santaquin Civic Clubs

Sept. 27, 1954
Date

Carroll H. Davis
Nebo Soil Conservation District

9-27-54
Date

CONTENTS

	Page
<u>Introduction</u>	1
Authority	1
Purpose and Scope of the Plan	1
<u>Summary of Plan</u>	1-2
Distribution of Costs	2
Responsibility for Operation and Maintenance of Works of Improvement	2
Comparison of Benefit and Costs	2
<u>Description of Watershed</u>	2-9
Location and Size	2-3
Physical Characteristics	3-4
Climate	4-5
Land Capability Classes	5-6
Land Use	6-8
Economy of the Watershed	8-9
<u>Flood and Erosion Problems and Damages</u>	9-12
Floodwater and Sedimentation Damages	9-10
Critical Areas	10-11
Sedimentation Rate	12
<u>Existing or Proposed Water Management Projects</u>	12-16
Flood Prevention Works of Improvement	13-15
Measures for Conservation of Water and Watershed Lands	15-16
Other Needed Conservation Measures	16
<u>Effect of Flood Prevention Measures on Damages and Benefits</u>	16-18
Evaluating the Effects of the Program	17
Comparison of Benefits and Costs	17-18
<u>Accomplishing the Plan</u>	18-20
<u>Provisions for Maintenance</u>	21-22
Table 1. Estimated Installation Costs - Total Needed Program	
Table 1. Supplement "C" Measures	
Table 2. Status of Conservation Job in Santaquin Canyon Watershed	
Table 2A. Cost Sharing Arrangement	
Table 3. Annual Costs	
Table 4. Summary of Average Annual Monetary Floodwater and Sediment Damage and Flood Prevention Benefit from the Plan.	

CONTENTS -- Continued

Table 5. Distribution of Costs and Benefits by Measures and Groups of Measures

Table 6. Floodwater Retarding Structure Data

Table 7. Summary of Program Data

Table 8. Summary of Physical Data

Figure 1. Generalized Use Capability, Range Site and Condition Map.

Figure 2. Land Ownership Status Map

Figure 3. Work Plan

Figure 4. Damage Area and Treatment Map

Appendix

Evaluation Program
Cooperative Agreement

11-01

11-02

11-03

11-04

11-05

11-06

11-07

11-08

11-09

11-10

11-11

11-12

11-13

11-14

11-15

11-16

11-17

11-18

11-19

11-20

11-21

11-22

11-23

11-24

11-25

11-26

11-27

11-28

11-29

11-30

11-31

11-32

11-33

11-34

11-35

11-36

11-37

11-38

11-39

11-40

11-41

11-42

11-43

11-44

11-45

11-46

11-47

11-48

11-49

11-50

11-51

11-52

11-53

11-54

11-55

11-56

11-57

11-58

11-59

11-60

11-61

11-62

11-63

11-64

11-65

11-66

11-67

11-68

11-69

11-70

11-71

11-72

11-73

11-74

11-75

11-76

11-77

11-78

11-79

11-80

11-81

11-82

11-83

11-84

11-85

11-86

11-87

11-88

11-89

11-90

11-91

11-92

11-93

11-94

11-95

11-96

11-97

11-98

11-99

11-100

Santaquin, Utah - September 27, 1954

INTRODUCTION

Authority

The Federal participation outlined in this work plan is expected to be performed under the authority of the Soil Conservation Act of 1935 (Public Law No. 46, 74th Congress) and other authorities of the National program of concerned agencies.

Purpose and Scope of Plan

The purpose of this plan is to state specifically the required and feasible practices and measures and how they will be carried out to achieve the maximum practicable reduction of erosion, floodwater and sediment damages. Application of this mutually developed plan will provide the protection to and improvement of land and water resources which it has been agreed can be undertaken at this time with the combined facilities of local interests and State and Federal agencies. Upon completion and continued maintenance of the measures set forth in this plan a material contribution will be made to sustaining agricultural production at a level corresponding to the capability of the land, with adequate conservation treatment and the welfare of the landowners and operators, the community, the State and the Nation promoted thereby. This watershed is in Utah County, Utah, and tributary to Utah Lake. It contains 27,153 acres or 42 square miles.

SUMMARY OF PLAN

This plan is a combination of land treatment practices and measures used for the conservation of water and watershed lands which contribute directly

to flood prevention, and of measures primarily for flood prevention. The measures are designed to effect a substantial reduction of floodwater and sediment damage by reducing rates of surface runoff, erosion and sediment production to the maximum practical extent.

Distribution of Cost

The improvement work as listed in Table 1 is planned to be installed during a five-year period at an estimated total cost of \$114,299. This cost is to be shared -- \$16,440 by farmers and ranchers; \$12,020 by non-Federal public agencies; and \$85,839 by the Federal Government.

Responsibility for Operation and Maintenance of Works of Improvement

The Nebo Soil Conservation District, hereafter referred to as the District will assume overall responsibility for future operation and maintenance of this project. The Santaquin Watershed Committee and other local interests will cooperate with the District in maintaining the flood-prevention works installed primarily for the benefit of non-Federal land and property.

Where measures are installed primarily for the benefit of Federal lands, maintenance will be a Federal responsibility. The land owners and operators will be responsible for maintaining the land treatment measures installed on their properties where benefit is for their lands.

Comparison of Benefits and Costs

When the works of improvement are applied and operating at full effectiveness the ratio of the estimated average annual benefit (\$6,620) to the estimated average annual value of the costs (\$4,960) is 1.33 to 1 based on current price levels for costs and long term prices for benefits.

DESCRIPTION OF THE WATERSHED

Location and Size

The Santaquin Canyon Watershed is located in Central Utah within the

Nebo Soil Conservation District in the south part of Utah County; the town of Santaquin is situated on the alluvial fan at the mouth of the canyon just below the junction of Pole Canyon and Summit Creek. The community of Genola is at the mouth of Summit Creek near Utah Lake. Santaquin Canyon is a local name for the canyon through which Summit Creek, a live stream, flows. Pole Canyon is an adjacent watercourse which flows only during snow melt or after heavy rains. This project is designated the "Santaquin Canyon Watershed" because locally that is the best known name.

The flood source area consists of the drainage area of Summit Creek, 12,323 acres, and that of Pole Canyon, 2,603 acres, a total of 14,926 acres. The watershed is roughly 3 miles wide and 15 miles long extending northwest-ernly from its headwaters to Utah Lake.

Physical Characteristics

The watershed varies from an elevation of 4,500 feet at Utah Lake and 5,000 feet at Santaquin to 10,913 feet at the top of Bald Mountain. The divide at the head of the watershed has an average elevation of about 9,000 feet. Most tributary streams have very steep gradients. The higher watershed is characterized by extremely steep slopes and in some cases vertical cliffs. Relatively small areas with flatter slopes are found at or near the top of the watershed. Side canyons have extremely narrow bottoms and steep sides. Talus slides are numerous.

The faulted Wasatch front is upthrown and very steep on the west face. Streams cut into this face are short, very high gradient, and trenched into deep canyons. Stream eroded materials, supplemented by talus and glacial debris have deposited in a large fan where the canyon emerges into the Bonneville Basin. Part of the fan was deposited during existence of ancient Lake Bonneville, and the old shore line extended up into the present canyon.

The stream is now dissecting the upper part of the fan developed in Bonneville time. The towns of Santaquin and Genola lie on the outer flanks of the fan. Soils developed on the lower part of the fan are very productive and have been cultivated since 1856.

1. Climate

The average annual precipitation ranges from about 15 inches in the lower portion of the watershed to about 35 inches in the higher portion, a major portion being in the form of snow.

Winter storms are mainly of the cyclonic type, broad in aerial extent and with lower intensities and longer duration than summer storms. The precipitation (snow) accumulates in the mountainous areas during the months of October to May. When these storms build up heavy snow packs in the high elevations along with heavy snow accumulation at lower elevation, and accompanied with retarded spring weather, above normal snow melt floods usually occur. The high elevation snow pack provides the greater part of the perennial stream flow. Considerable movement of sediment in channels occurs during normal spring runoff. The snow-melt floods usually carry downstream the sediment which is washed into the main channel by the summer storms.

There are two principal types of summer storms in the watershed: (1) convective, or local thunderstorms which produce high precipitation intensities over small areas for short periods of time, and (2) general storms which cover extensive areas and produce relatively large amounts of precipitation with comparatively low intensities of longer duration. The convective type storms are more frequent and are the principal cause of summer floods. Most of these storms occur during the months of July and August.

The frost free season averages 150 days at lower elevations and 80 days at higher elevations in the watershed. Normal valley temperatures range from

100 degrees F. to a few degrees below zero. Extremes of 108 and -40 degrees have been recorded.

2. Land Capability Classes

Land Capability Classes have been mapped for all watershed lands on the basis of their physical characteristics, conservation needs and suitability for various land use. (See Figure 1)

Land Capability Class I (37 Acres). This land consists of deep loam soils located on the flat lake terrace. It is suitable for cultivation without special conservation practices. These irrigated soils are highly productive when good soil and water management practices are applied.

Land Capability Class II (4,562 Acres). This class of land includes both irrigated and dryland and is well suited for cultivation. The irrigated land (2,685 acres) is moderately deep to deep loam soils and requires the application of simple conservation practices to prevent erosion. Slopes generally range from two to three per cent and are difficult to irrigate because of the irregular surface. Leveling, improved water application and management are needed. The dry farmland (1,877 acres) consists of deep loam soils on slopes varying from two to six per cent. Contour strip cropping and stubble mulching are needed on these soils.

Land Capability Class III (986 acres). Land in this class is all irrigated and suitable for cultivation with intensive conservation practices. These soils are either gravelly or have heavy silty sub-soils and/or slopes ranging from four to seven per cent. The soils with heavy sub-soils on steep slopes are subject to considerable erosion and require extremely careful soil and water management to prevent erosion. Because of this, it is not adapted to row crops except on the flatter slopes. Leveling is needed on most of this land.

Land Capability Class IV (622 acres). Land in this class is not suitable for continuous cultivation. The irrigated land (547 acres) consists of very heavy surface and sub-soil or is very shallow on steep slopes. The best use for these soils is permanent pasture, cultivated only when necessary to re-establish the permanent cover. The dry farmland (75 acres) has shallow soils on slopes up to 10 per cent. This land should be permanently retired from cultivation and planted to adapted grasses.

Land Capability Class VII (15,850 acres). This class is all in range use and occupies much of the flood source area. Careful grass and forage management is required to maintain vigor and cover so that floodwater runoff and erosion are held to a minimum. Some structural conservation measures and seeding are feasible where physical conditions permit. Some small areas of Class VI land occur within the area mapped as Class VII but this does not significantly affect the type of conservation practices required.

Class VIII (4,496 acres). This class consists of extremely steep canyon slopes and rock ledges with large areas of exposed rock. This land is suitable principally for water production. Some recreational and wildlife use is also made of it.

3. Land Use

A. Range Land: 20,968 acres.

The plant cover of the non-cultivated area is the typical high mountain, foothill and valley type prevailing along most of the Wasatch front.

It is divided into five range sites: (1) high mountain, (2) intermediate mountain, (3) foothills, (4) shallow stony hills, and (5) salt meadow.

(1) The high mountain site generally has an aspen cover with weed, brush and grass growing under the aspen. The major portion of the understory is dominated by brush and undesirable weeds. In most places the vegetal

cover has been depleted by overgrazing and can be materially improved in the amount of growth, type of vegetation, and forage value. Many of the north facing steep slopes are covered with a thick stand of conifers.

(2) The intermediate mountain site is dominated by brush such as big sagebrush, oak and maple. In some cases almost pure stands of maple with little or no vegetative understory exist. The vigor of the understory is poor.

(3) Foothill site. The low hills and rolling slopes are generally quite droughty. The present cover is dominated by big sagebrush. Some oak clumps and other browse plants are present. In some places a fairly good stand of grass exist in the understory. The most prevalent grasses are wheatgrasses, bluegrass and Indian rice grass. Annuals, such as cheat grass are prevalent over much of this area.

(4) Intermingled in the foothill site are a few areas having very shallow soil over bed rock. These areas were classified as shallow stony hills. They resemble the foothill area in present vegetative cover except that service-berry and mountain mahogany are found in place of the oak. Although the potential of this area is somewhat limited because of the droughty conditions present, it is not now growing nearly as much vegetation as it is capable of doing.

(5) Between the cultivated land surrounding Genola and Utah Lake is a comparatively flat area. Generally, the area is saline, has a high water table and a heavy textured, highly dispersed, poorly drained soil. The vegetative cover is principally a thick stand of salt grass, wire grass and sedges. Some remnants of sacaton and alkali grass are occasionally found.

Each of the above sites was examined with respect to present condition as compared to the best condition the site could reach. Areas in various condition classes were shown on the range site and land capability map. Areas

shown in "good" condition were considered as being between 50% and 75%, "fair" condition 25% to 50%, and "poor" condition less than 25% of their optimum condition.

B. Dryland: 1,952 acres.

The dryland is fallowed after each crop of wheat. The yield is around 17 bushels per acre which is about state average. Most of these farmers also have irrigated lands. The 75 acres of class IV dry farm land should be planted to permanent grass.

C. Irrigated Land: 4,255 acres.

Irrigation water for the Genola community is furnished from the Strawberry Highline Canal. The land around Santaquin is watered from Summit Creek and there is usually a shortage for late summer irrigation. Alfalfa and small grain are the main crops grown along with sugar beets in the Genola area. Just south and east of Santaquin there are several orchards.

All irrigated land needs good management practices such as fertilizing, weed control, irrigation water management, crop rotation when row crops are used. Special conservation practices are also needed as indicated in "other needed conservation practices." (Table 1 "C" Measures)

Economy of the Watershed

The population of the watershed is estimated at about 1,800 people. Farming, which has an annual value of about \$400,000 is the most important industry. The area is adequately served by a network of county roads, U. S. Highways 91, 50 and 6, and branch lines of the Denver and Rio Grande Western and Union Pacific railroads.

Most of the upper watershed is in the Uinta National Forest and is managed by the Forest Service. Most of the lower watershed is owned and managed by private operators.

The use of Santaquin Canyon watershed is varied. The higher lands produce forage for domestic livestock and big game. Most of the accessible timber has been removed and no logging is being done at present. Recreational use, hunting, fishing and picnicking, is important. A few mining claims have been filed, but there is very little mining activity. Stream flow from Summit Creek provides a portion of irrigation water for 4,255 acres of farmland. It also furnishes power for the operation of a small hydro-electric plant owned by the Utah Power and Light Company. Springs in the Summit Creek channel bottom furnish culinary water for Santaquin and Genola.

FLOOD AND EROSION PROBLEMS AND DAMAGES

Floodwater and Sedimentation Damages

The town of Santaquin has been subject to flood-water and sediment damage and water control problems since shortly after settlement in 1856. Damaging floods from Santaquin Canyon are reported to have occurred in 1880, 1910, 1920, 1925, 1930 and 1952. However, there is little recorded information on magnitude of discharge or resulting monetary damages caused by these floods.

The largest flood in recent years occurred in August, 1920. This flood is reported to have washed out the culinary water supply pipeline, a major portion of Santaquin Canyon road and a section of U.S. Highway 91. Three homes were severely damaged and a section of the residential area of Santaquin and adjacent farm lands were inundated.

In 1952, the spring snow melt flood caused considerable damage to the irrigation system and to the road from Santaquin to Santaquin Reservoir owned by the irrigation company. Emergency levees constructed by local townspeople were successful in preventing flooding of the town and in preventing damage to the springs, collection works and main pipeline of the culinary water system.

The power plant and intake were also threatened by the flood. After the flood, the Utah Power and Light Company constructed additional levees and jetties to protect their plant.

Local residents report that the large quantity of heavy sediment, mostly gravel, carried by the stream during floods and during normal spring flows has been the principal cause of past damages. Shortly after the town of Santaquin was settled an irrigation system was constructed and the entire flow of the stream was diverted through the system. Subsequent economic development has obliterated the original stream channel in and below Santaquin.

Prior to 1914 sediment carried by spring flows was diverted with the water into the irrigation canals where much of it was deposited. Subsequent loss of canal capacity frequently resulted in the canals overflowing and flooding sections of the town and cultivated fields. Large amounts of coarse sediment (gravel) were deposited in the inundated area. The larger floods completely disrupted the system by filling the canals with sediment and washing out sections of canal banks.

Critical Areas

Approximately 5,900 acres in the upper portion of the drainage basin have been depleted of the better kinds of vegetation and subjected to erosion varying from slight to severe. About 1,600 acres of the above are considered a critical source of floodwater and sediment. Here the original vegetative cover has largely disappeared. The present plant cover consists largely of weeds and other indicators of a deteriorated range which afford very little protection to the soil and have poor forage value. Studies in 1951 showed infiltration rates on badly depleted range lands to be, on the average, only about one-fourth of that in aspen stands where the rates are three inches or

more per hour - sufficient to control high intensity rainstorms. This low infiltration rate prevents the penetration of moisture into the soil in sufficient quantities for normal plant growth and causes abnormally rapid runoff from these depleted watershed lands. The related phenomena of plant depletion, soils disturbance, surface runoff and accelerated erosion once initiated sets in motion an upward spiral of range productivity losses and downstream flood water and sediment damages.

Total flood water and sediment damages are \$4,920 annually. Spring and summer floods cause an estimated damage of \$3,470 based on present watershed conditions. An additional \$1,450 damage occurs annually from sediment carried by normal stream flow. Flood water and sediment damages have not been separated because of their very close inter-relationship. However, sediment movement accounts for a large part, probably a major part of the flood problem as indicated above.

Eroded material from the stream channels increases the volume of the flood and materially contributes to downstream flood water and sediment damages. Approximately three miles of the main channel above the power plant is a major source of the damaging sediment. Serious channel erosion has been in progress in this section for many years.

Past damages from snow melt floods have been caused primarily by the large quantities of sediment carried in the stream. Summer cloudburst type storms occur on the upper watershed and frequently result in floods on individual tributaries. Only occasionally are these upstream floods of sufficient magnitude to cause a damaging flood on the lower reach of the main stream. However, these small summer floods damage roads and deposit large quantities of sediment in the main streams to be transported subsequently downstream by spring flows.

Sedimentation Rate

The estimated average sediment rate at the present debris basin is 5 acre feet annually. About 70 per cent of the sediment consists of bed-load sand, gravels and cobbles and the remainder consists of silt, clay and fine sand. The existing debris basin, while it was effective, trapped most of the bed-load and about one-third of the suspended load. The remainder passed through the basin to be deposited in irrigation systems, on farm land or in Utah Lake.

EXISTING OR PROPOSED WATER MANAGEMENT PROJECTS

The local citizens have done much toward reducing damages from flood runoff and sediment condition.

In 1914 local people in cooperation with Utah State Experiment Station constructed a debris basin just above the town of Santaquin. This functioned satisfactorily for a number of years, but sediment filled it to the point where flood flows overtopped the embankment. A second debris basin about 1/3 mile below the power plant and above the first basin was constructed in 1934. This structure was raised in 1937, 1939, 1948, 1949 and 1952. The Nebo Soil Conservation District assisted in raising the debris basin dam in 1948 and 1949.

When U.S. Highway 91 was relocated to bypass Santaquin, it crossed near the lower debris basin. Sediment material from the basin was used for the road fill near the channel crossing. The State Highway Department constructed a small dike creating some storage for debris.

Some contour trenching was done at the head of Santaquin Canyon in 1938 and 1939. In 1942 slender wheatgrass and tall meadow oat grass were sown in the upper reaches. In 1944 about 200 acres at Santaquin Meadows were reseeded and fenced the following June.

Utah Power and Light Company has periodically excavated the stream channel past their plant and has constructed levees and jetties to protect their plant from inundation.

In 1952 through an agreement with Santaquin Livestock Association 4,200 acres of aspen and brush covered areas on the National Forest in upper Santaquin Canyon were broadcast seeded by airplane. Starting in 1953 the Santaquin Livestock Association which included 19 permittees took three year non-use of the range watershed for 574 cattle to allow establishment and improvement of vegetation.

The Mona cattle allotment includes approximately 500 acres in the head of Santaquin Canyon. The Nebo Stock Graziers Association, who run cattle on this allotment, agreed in the fall of 1953 to permit this area to be fenced and to hold their cattle off this area for a three year period beginning in 1955. This area has provided approximately 125 cow months feed annually.

Flood Prevention Works of Improvement to be Installed ("A" Measures)

The measures primarily for flood prevention to provide flood protection for flood plain lands, highways, and urban improvements are listed with estimated costs in Table I. The major works are shown on figure 3.

1. Stabilizing and Sediment Control Measures

One desilting basin of about 84 acre-feet capacity will be constructed on Summit Creek at the approximate location of the present upper basin. A small detention structure, holding about 3 acre-feet, will be constructed on Pole Canyon near its mouth. A channel 800 feet long will be constructed from the spillway of the larger desilting basin to the smaller structure on Pole Canyon. The normal spring runoff in Summit Creek will be discharged from the larger desilting basin into the main canal of the Summit Creek

Irrigation Company, which will be enlarged to carry the maximum expected flow of 180 c.f.s. Larger floods in Summit Creek resulting from summer storms will cause water to flow over the spillway of the larger desilting basin, through the spillway channel and into the small basin on Pole Canyon. From the smaller basin, flood waters will be dissipated on waste land by means of a spreader system. These basins will catch and store sediment and also reduce flood peaks downstream. Sufficient capacity is provided for 40 years of sedimentation with the improved watershed conditions expected from the application of this program.

The sediment basin dam and spillway including side slopes will be seeded to grass after construction work is completed. Seeding recommendations are included in appendix.

2. Stream Channel Improvement

Streambank revetment of large rock rip rap and/or planting with woody plants will be installed to reduce bank cutting and sediment production. This work will extend intermittently from the power plant to a point about three miles upstream. Two rock stabilizers will be constructed to maintain channel gradient and to protect city water supply. Russian olive and black willow will be planted on appropriate locations along the stream bank. This will follow rock revetment work.

3. Diversion Ditches and Dikes

A short dike is planned to protect the power plant from debris and flood damage. The dike will be constructed of earth and rock.

4. Enlargement of Irrigation Canal to Carry Flood Waters

Canal enlargement is planned to carry 180 c.f.s. which is maximum expected during spring runoff from this watershed. This will be accomplished by using the present distribution system and providing earthen embankments or other suitable means on each side of the existing lined canal.

5. Stabilization of Critical Areas

It is planned to seed 800 acres in the National Forest to grass. Four hundred acres will be broadcast seeded and 100 acres of barren areas will be plowed and drilled. Three hundred acres will be seeded in conjunction with contour trenching. Grazing use by domestic stock will be withheld for a period of three years beginning in 1953 on the Santaquin allotment and 1955 on the Mona cattle allotment to allow establishment of the reseeded grasses.

Six miles of fence will be installed along the watershed boundary to control livestock use and protect the reseeded area.

There are 300 acres of barren, actively eroding areas in the National Forest that require large contour trenches to prevent surface runoff until vegetation can be established. These trenches are designed to contain 1.0" of runoff. The trenched area will be seeded to grass to accelerate vegetative recovery.

Measures for Conservation of Water and Watershed Lands ("B" Measures)

Reseeding of 440 acres, 320 by drilling and 120 acres by broadcasting before leaf fall, is needed to establish perennial vegetation where there are now many weeds and bare spots. A large part of the area to be drill-seeded will need clearing.

Approximately 1 3/4 miles of fencing will be installed to control livestock and protect new seeding of grass. Deferred grazing on the new seeding is planned until it has had an opportunity to become established.

On all watershed range lands, the improvement of the plant vigor and cover, both in kind and amount is of paramount importance both to an effective watershed program and to the range user. The use pattern and the effectiveness of grass and browse management govern the kind, amount and vigor

of range forage, which is of interest to the rancher. People in the downstream damage area are interested in the fact that a watershed in the best practical range and woodland condition will absorb a good deal of rain and reduce the rate of surface runoff. It will also hold the soil in place and prevent it moving downstream where it must be cleaned out of canals and structures at great expense.

Private owners have stated their interest in cooperating with the Nebo Soil Conservation District and the Forest Service in applying a sound grass management program on all of their lands.

Other Needed Conservation Measures

The land capability survey indicates that the valley land not in the flood contributing portion of the watershed needs numerous conservation measures so as to round out a complete conservation program. The following conservation practices along with estimated needs are:

<u>Practice</u>	<u>Needs</u>	<u>Practice</u>	<u>Needs</u>
<u>DRY CROPLAND</u>		<u>RANGELAND</u>	
Contour farming	Ent. Ac.	Deferred grazing	5,000 ac.
Stubble mulching	Ent. Ac.	Proper use	Ent. ac.
<u>IRRIGATED CROPLAND</u>		Range seeding	500 ac.
Crop residue management	Ent. Ac.	Rotation grazing	6,000 ac.
Ditch lining or impr.	15,000 L.F.	Stockwater developments	2 ea.
Farm drainage	300 ac.	<u>ONE OR MORE LAND USES</u>	
Farm irrig. system impr.	All farms	Fish pond development	5 ea.
Irrig. water management	Ent. Ac.	Land clearing	500 ac.
Land leveling	3,000 ac.	Marsh improvement	100 ac.
Pond construction	10 ea.	Tree planting	10 ac.
Pasture seeding	1,400 ac.	Wildlife area improvement	100 ac.
Structures, small	1,200 ea.	Windbreak planting, field	20 ac.
Structures, large	8 ea.		

EFFECT OF FLOOD PREVENTION MEASURES ON DAMAGES AND BENEFITS

The combined program of land treatment and flood prevention measures described above will provide a high degree of protection from Santaquin Canyon floods.

The debris basin, which will effectively detain flood flows for the first few years, is expected to become filled with sediment at the end of 40 years. However, sufficient spillway capacity will be provided at the lower debris basin, with a channel to carry the spill safely around the town of Santaquin and valley irrigated lands, to prevent overflow damage from storms which might occur in the watershed up to 100 year frequency.

The estimated average annual floodwater and sediment damages resulting from flood flows will be reduced from \$3,470 to \$170. Normal flows in Summit Creek also carry considerable sediment into irrigation systems and the lower channel and onto farm lands. These damages from normal stream flows will be reduced from \$1,450 to \$450 annually. The total annual flood damage reduction is estimated at \$4,300.

It is estimated that the average annual conservation benefits to landowners and operators in the watershed which will accrue from the application of the total program is \$2,320. The expected benefits were determined by estimating the increased net income which will result from the application of the needed practices and measures.

Evaluating the Effects of the Program

The hydrologic, economic and other effects of this program will be measured in the future. A plan for the installations and procedures required to evaluate these effects has been developed in cooperation with other fact-finding agencies. This plan is attached as an appendix to the work plan.

Comparison of Benefits and Costs

The ratio of the average annual benefits from measures primarily for flood prevention, \$5,360, to the average annual cost of the measures, \$4,570, is 1.17 to 1.

The ratio of the average annual benefit, \$1,260, from the land treatment measures and practices (B measures) to their average annual cost, \$390, is 3.23 to 1.

The ratio of the total average benefits, \$6,620, to the total average annual value of the cost \$4,960, is 1.33 to 1, see table 5.

In addition to the monetary benefits, there are other substantial values which are attributable to the program. Sheet, gully and channel erosion is slowly undermining the productive base of watershed lands. This will be largely mitigated by the program. Recreational opportunity will be increased through conservation and protection of fish and wildlife and their habitat.

The communities of Santaquin and Genola are dependent upon the watershed for irrigation and culinary water supplies. Protection of these water supplies by sound management and use of the soil and plant resources in the watershed is important to the continued well being of the communities.

ACCOMPLISHING THE PLAN

The Nebo Soil Conservation District, which sponsors this project, and the Soil Conservation Service have mutually agreed to the sharing of costs set forth in Table 1. Each party agrees to schedule its contributions to the project so they will promote the efficient prosecution of the work. The Santaquin Watershed Protection Committee is assisting the district, through a cooperative agreement, in the development and carrying out of this watershed program.

Specifically, the Nebo Soil Conservation District, hereafter called the District, will:

1. With help from the Santaquin Watershed Committee and Extension Service disseminate information about this project, through community meetings,

tours, radio and press releases, to local landowners and citizens to promote a common understanding and acceptance of the project and facilitate the carrying out of this work plan.

2. With help from the Extension Service, in community meetings and by personal contacts, encourage land owners and operators within this watershed to adopt and carry out soil and water conservation plans on their farms and ranches as rapidly as practicable.
3. Arrange for all lands, easements, and rights-of-way needed for the sediment basin and other structures primarily for the protection of non-Federal lands.
4. Arrange for the contribution in services, equipment use and other forms by individual land owners, Utah County, Utah Power and Light Company, Summit Creek Irrigation Company, and the Towns of Santaquin and Genola, and by other non-Federal agencies and individuals interested in this project.
5. Provide for maintenance of the measures in a satisfactory manner.

The Soil Conservation Service, hereafter called the Service, will:

1. Assign additional technicians to assist the district in the overall planning of the project and in the design and installation of flood prevention measures.
2. Contract for the installation of flood prevention works which the district and the Service agree should be installed by contract. For these works the Service will develop construction plans and specifications, let contracts and supervise the construction.
3. Provide technical assistance to the district in future maintenance operations.

The Forest Service will carry out this plan as it applies to the protection and improvement of National Forest lands. They will continue an effective fire protection program and will carry out a timber management program, on Federal lands. Fire protection and prevention on private lands is being provided in accordance with Utah State Fire Laws.

The Santaquin Canyon Watershed Committee, a voluntary organization of non-Federal interests in this area, will assist the district in local dealings related to adoption of the plan, financing, rights-of-way, and maintenance.

The Santaquin Livestock Association will assist the district and the Forest Service to improve watershed conditions by voluntary deferment of livestock grazing where necessary and by application of conservation practices and sound grass management.

The Agricultural Conservation Program will assist the district and the farmers by offering incentive payment as funds permit to encourage the establishments of "D" and "C" conservation measures.

The Bureau of Land Management will continue to manage the lands under their jurisdiction. Special treatment of E.L.M. lands was not deemed necessary for this watershed protection program.

The Utah State Fish and Game Commission will cooperate in making browse condition studies, in making special big game counts and in recommending adjustments when needed by providing special hunting privileges.

Tables #1 and #2 and Figure #1 indicate the schedule of operations which has been agreed upon for the most efficient development of this project in view of financial and other considerations. This schedule will be periodically adjusted by mutual agreement to comply with current conditions.

PROVISIONS FOR MAINTENANCE

Estimated annual maintenance costs after the land treatment measures and flood prevention measures have been installed are shown in Table 3.

The Federal agencies involved will operate and maintain measures installed primarily for benefit of Federal lands under their jurisdiction.

The Nebo Soil Conservation District will assume overall responsibility for operation and maintenance of this project. Land owners and operators will maintain the land treatment measures installed on their lands under terms of their cooperative agreements with the District.

The floodwater retarding and sediment control works, primarily for the protection of private lands, will be maintained by the District through a cooperative group agreement with the Santaquin Canyon Watershed Protection Committee. More specifically, the Summit Creek Irrigation Company will be responsible for operation and maintenance on the sediment basin including emergency spillway and canal flood-way to Santaquin reservoir. Towns of Santaquin and Genola will be responsible for operation and maintenance of channel stabilization works from point 1/4 mile above Utah Power and Light sub-station to a point 300 feet above the upper city spring.

All major flood prevention and sediment control works installed primarily for the protection of private lands will be inspected periodically, at least annually, by representatives of the District, the Service, the Santaquin Watershed Committee and of any local agency or group which has responsibility for maintenance under agreement with the District. All conditions of damage or deterioration in these structures will be noted and satisfactory repairs will be made by the responsible group as soon as practical after the need for repair is determined.

Provisions and funds for maintenance will be established by each local group responsible for maintenance of specific structures and these funds will be maintained by annual levies for this purpose, and will be part of their annual plan of operations.

Measures	Unit	No. to be Applied	Estimated Cost			
			Federal	Non-Federal Public	Private	Total
A-Measures Primarily for Flood Prevention						
Soil Conservation Service						
(2) Stabilizing & sediment control measures b. Desilting Basin (incl. right-of-way)	Number	1.0	23,374.	5,353.		28,727.
SCS-Subtotal			23,374.	5,353.		28,727.
Forest Service						
(7) Stabilization of critical runoff & sediment producing areas						
a. Roadside erosion control	Miles	0.8	681.			681.
b. Revegetation of critical areas						
1. Grasses and legumes	Acres	412.0	1,806.			1,806.
c. Special purpose terraces	Acres	250.0	12,500.			12,500.
d. Gully stabilization (small)	Miles	3.0	3,370.			3,370.
h. Fences	Miles	1.0	566.			566.
i. Deferred grazing	Acres	13,000.0		3,160.		3,160.
FS-Subtotal			18,923.		3,160.	22,083.
Total A-Measures			42,297.	5,353.	3,160.	50,810.
B-Measures - for conservation of watershed lands that contribute directly to flood prevention						
Soil Conservation Service						
Forest Service						
SCS-Subtotal						
Forest Service						
FS-Subtotal						
Total B-Measures						
Total A and B Measures						
Facilitating Measures						
Program Evaluation SCS						
Work Plan Development SCS						
Work Plan Development FS						
Summary						
Total Watershed Protection Program SCS						
Total Watershed Protection Program FS						
Grand Total (Watershed Protection Funds)						
Going Program (SCS)						
Going Program (FS)						

Measures	Unit	No. to be Applied	Estimated Cost			
			Federal	Non-Federal Public	Private	Total
A-Measures Primarily for Flood Prevention						
Soil Conservation Service						
(2) Stabilizing & sediment control measures b. Desilting Basin (incl. right-of-way)				200.		200.
(4) Stream channel improvement a. Channel stabilization (above UP&L plant)	Mile	1.2	4,042.	1,705.		5,747.
SCS-Subtotal			4,042.	1,905.		5,947.
Forest Service						
(4) Stream channel improvement a. Channel stabilization (above UP&L plant)	Mile	1.0	1,577.	606.		2,183.
(7) Stabilization of critical runoff & sediment producing areas a. Roadside erosion control	Mile	2.0	1,600.			1,600.
b. Revegetation of critical areas 2. Woody plantings (channel)	Mile	3.0	1,140.			1,140.
c. Special purpose terraces	Acre	25.0	1,300.		3,160.	1,300.
i. Deferred grazing						3,160.
FS-Subtotal			5,617.	606.	3,160.	9,383.
Total A-Measures			9,659.	2,511.	3,160.	15,330.
B-Measures - for conservation of watershed lands that contribute directly to flood prevention						
Soil Conservation Service						
Range Reseeding	Acres	200.0			2,405.	2,405.
Fencing	Miles	1.75			1,400.	1,400.
SCS-Subtotal					3,805.	3,805.
Forest Service						
FS-Subtotal						
Total B-Measures					3,805.	3,805.
Total A and B Measures			9,659.	2,511.	6,965.	19,135.
Facilitating Measures						
Program Evaluation SCS			300.			300.
Work Plan Development SCS						
Work Plan Development FS						
Summary						
Total Watershed Protection Program SCS			4,342.	1,905.	3,805.	10,135
Total Watershed Protection Program FS			5,617.	606.	3,160.	
Grand Total (Watershed Protection Funds)			9,959.	2,511.	6,965.	19,435.
Going Program (SCS)			300.			300.
Going Program (FS)			910.			910.

1/ Includes \$500. ACP
2/ Includes \$220. ACP

Measures	Unit	No. to be Applied	Estimated Cost			
			Federal	Non-Federal Public	Private	Total
A-Measures Primarily for Flood Prevention						
Soil Conservation Service						
(4) Stream channel improvement a. Channel stabilisation above UP&L plant	Mile	0.3	224.	2,106.		2,330.
SCS-Subtotal			224.	2,106.		2,330.
Forest Service						
FS-Subtotal						
Total A-Measures			224.	2,106.		2,330.
B-Measures - for conservation of watershed lands that contribute directly to flood prevention						
Soil Conservation Service						
Deferred grazing	Acre	400			1,000.	1,000.
Range reseeding	Acre	120			1,435.	1,435.
Range reseeding (broadcast)	Acre	120			720.	720.
SCS-Subtotal					3,155.	3,155.
Forest Service						
FS-Subtotal						
Total B-Measures					3,155.	3,155.
Total A and B Measures			224.	2,106.	3,155.	5,485.
Facilitating Measures						
Program Evaluation SCS			300.			300.
Work Plan Development SCS						
Work Plan Development FS						
Summary						
Total Watershed Protection Program SCS			524.	2,106.	3,155.	5,785.
Total Watershed Protection Program FS						
Grand Total (Watershed Protection Funds)			524.	2,106.	3,155.	5,785.
Going Program (SCS)			200.			200.
Going Program (FS)						

1/ Includes \$270. ACP
2/ Includes \$110 ACP

Project: Santaquin Canyon WatershedTABLE I
INSTALLATION COSTState: UtahFOR 1958Date September 30, 1954

Measures	Unit	No. to be Applied	Estimated Cost			
			Federal	Non-Federal Public	Private	Total
A-Measures Primarily for Flood Prevention						
Soil Conservation Service						
(6) Flood ways	Miles	1.0				
a. Channel enlargement			4,020.	1,980.		6,000.
(7) Stabilisation of critical runoff & sediment producing areas						
a. Roadside erosion control (Pole Canyon)			170.	70.		240.
SCS- Subtotal			4,190.	2,050.		6,240.
Forest Service						
FS-Subtotal						
Total A-Measures			4,190.	2,050.		6,240.
B-Measures - for conservation of watershed lands that contribute directly to flood prevention						
Soil Conservation Service						
SCS-Subtotal						
Forest Service						
FS-Subtotal						
Total B-Measures						
Total A and B Measures			4,190.	2,050.		6,240.
Facilitating Measures						
Program Evaluation SCS			200.			200.
Work Plan Development SCS						
Work Plan Development FS						
Summary						
Total Watershed Protection Program SCS			4,390.	2,050.		6,440.
Total Watershed Protection Program FS						
Grand Total (Watershed Protection Funds)			4,390.	2,050.		6,440.
Going Program (SCS)			100.			100.
Going Program (FS)						

Project: Santaquin Canyon Watershed

TABLE I
INSTALLATION COST

State: Utah

FOR Summary 1954 - 1958

Date September 30, 1954

Measures	Unit	No. to be Applied	Estimated Cost			
			Federal	Non-Federal Public	Private	Total
A-Measures Primarily for Flood Prevention						
Soil Conservation Service						
(2) Stabilizing & sediment control measures						
b. Desilting Basin (incl. right-of-way)	Number	1.0	24,947.	5,553.		30,500.
(4) Stream channel improvement						
a. Channel stabilization above UP&L Plant	Mile	1.2	4,042.	1,705.		5,747.
(5) Diversion ditches & dikes						
Dike above UP&L Co. Plant	Mile	0.3	224.	2,106.		2,330.
(6) Flood ways						
a. Channel enlargement	Mile	1.0	4,020.	1,980.		6,000.
(7) Stabilization of critical runoff & sediment producing areas.						
a. Roadside erosion control (Pole Canyon)			170.	70.		240.
SCS- Subtotal			37,803.	11,414.		44,817.
Forest Service						
(4) Stream channel improvement						
a. Channel stabilization (above UP&L Plant)	Mile	1.0	1,577.	606.		2,183.
(7) Stabilization of critical runoff & sediment producing areas.						
a. Roadside erosion control	Mile	3.0	2,499.			2,499.
b. Revegetation of critical areas						
1. Grasses & legumes	Acre	500.0	3,980.			3,980.
2. Woody plantings (channel)	Miles	3.0	1,140.			1,140.
c. Special purpose terraces	Acre	301.0	22,204.			22,204.
d. Gully stabilization (small)	Mile	3.0	3,370.			3,370.
e. Fences (includes 4 cattle guards)	Mile	6.0	3,849.			3,849.
i. Deferred grazing	Acre	13,000.0			9,480.	9,480.
FS-Subtotal			38,609.	606.	9,480.	48,695.
Total A-Measures			72,110.	12,020.	9,480.	93,510.
B-Measures - for conservation of watershed lands that contribute directly to flood prevention						
Soil Conservation Service						
Deferred grazing	Acre	400.0			1,000.	1,000.
Range reseeding	Acre	320.0			3,840.	3,840.
Range reseeding (broadcast)	Acre	120.0			720.	720.
Fencing	Mile	1.75			1,400.	1,400.
SCS-Subtotal					6,960.	6,960.
Forest Service						
FS-Subtotal						
Total B-Measures					6,960.	6,960.
Total A and B Measures			72,110.	12,020.	16,440.	100,470.
Facilitating Measures						
Program Evaluation SCS			2,425.			2,425.
Work Plan Development SCS			6,801.			6,801.
Work Plan Development FS			4,603.			4,603.
Summary						
Total Watershed Protection Program SCS			42,629.	11,414.	6,960.	51,777.
Total Watershed Protection Program FS			43,212.	606.	9,480.	48,695.
Grand Total (Watershed Protection Funds)			85,839.	12,020.	16,440.	114,299.
Going Program (SCS)			1,000.			1,000.
Going Program (FS)			2,730.			2,730.

1/ Includes \$1,100. ACP

9/30/54

TABLE I SUPPLEMENT
SANTAQUIN CANYON PROTECTION PROJECT

"C" MEASURES

<u>Practice</u>	<u>Needs</u>
<u>DRY CROPLAND</u>	
Contour farming	Ent. Ac.
Stubble mulching	Ent. Ac.
<u>IRRIGATED CROPLAND</u>	
Crop residue management	Ent. Ac.
Ditch lining or improvement	15,000 l. f.
Farm drainage	300 acres
Farm irrig. system improvement	All farms
Irrigation water management	Ent. Ac.
Land leveling	3,000 acres
Pond construction	10 each
Pasture seeding	1,400 acres
Structures, small	1,200 each
Structures, large	8 each
<u>RANGELAND</u>	
Deferred grazing	5,000 acres
Proper use	Ent. Ac.
Range seeding	500 acres
Rotation grazing	6,000 acres
Stockwater developments	2 each
<u>ONE OR MORE LAND USES</u>	
Fish pond development	5 each
Land clearing	500 acres
Marsh improvement	100 acres
Tree planting	10 acres
Wildlife area improvement	100 acres
Windbreak planting, field	20 acres

TABLE 2
STATUS OF CONSERVATION JOB IN SANTAQUIN CANYON WATERSHED

	Unit	Total Conservation Job		Applied To Date	Estimated Cost to Date			Remaining To Be Applied (See Table 1)
		Number	Total Cost (Dollars)		Federal (Dollars)	Non-Federal Public (Dollars)	Private (Dollars)	
"A" MEASURES - Non-Federal Land								
(2) Stabilizing and Sediment Control Measures								
b. Desilting basin (incl. right of way)	No.	3	\$ 36,500	2	\$	\$ 6,000	\$	1
(4) Stream Channel Improvement								
a. Channel stabilization	Miles	1.2	5,747					1.2
(5) Diversion Ditches and Dikes								
Dike above U.P. & L. plant	Miles	0.3	2,830			500		0.3
(6) Flood Ways								
a. Channel enlargement	Miles	2.0	8,720	1	20	2,700		1
(7) Stabilization of Critical Runoff and Sediment Producing Areas								
a. Roadside erosion control (Pole Canyon)	Miles	1	240					1
Sub-Total			\$ 54,037		\$ 20	\$ 9,200		
"A" MEASURES - Federal Land								
(4) Stream Channel Improvement								
a. Channel stabilization	Miles	1	2,183					1
(7) Stabilization of Critical Runoff and Sediment Producing Areas								
a. Road and trail stabilization	Miles	3	2,499					3
b. Revegetation of critical areas								
1. Grasses and legumes	Acres	500	3,980					500
2. Woody plantings	Miles	3	1,140					3
c. Special purpose terraces	Acres	301	2,220					301
d. Gully stabilization	Miles	3	3,370					3
f. Fences	Miles	6	3,840					6
i. Deferred grazing - Federal land	Acres	13,000	15,810		810		2,790	
Sub-Total			\$ 55,023		\$ 810		\$ 2,790	
TOTAL "A" MEASURES			\$109,060		\$ 830	\$ 9,200	\$ 2,790	
"B" MEASURES								
Deferred Grazing - Non-Federal Land	Acres	400	1,000					400
Range Reseeding	Acres	320	3,840					320
Range Reseeding (broadcast)	Acres	120	720					120
Fencing (net wire)	Miles	1.75	1,400					1.75
Gully Stabilization	Miles	0.3	450	0.3			450	
Farm and ranch Planning			1,000					
TOTAL "B" MEASURES			\$ 8,410				\$ 450	
TOTAL "A" AND "B" MEASURES			\$117,470		\$ 830	\$ 9,200	\$ 3,240	
Facilitating Measures								
Program Evaluation (SCS)			2,425					
Work Plan Development (SCS)			6,801					
Work Plan Development (FS)			4,603					
Grand Total			\$131,299					

9/30/54

TABLE 2 A

COST SHARING ARRANGEMENT IN SANTAQUIN CANYON WATERSHED

	ESTIMATED COST TO DATE		
	FEDERAL (Dollars)	PUBLIC (Dollars)	PRIVATE (Dollars)
Total Estimated Cost			131,299.
Total Fed., Exp. prior to designation of Watershed		830.	
Total Est. Fed. Expense non-W.P. Funds -- ACP	1,100.		
Loss of revenue	2,730.		
Farm and ranch planning	1,000.	4,830.	
Total Est. Fed. Exp. W.P. funds on Fed. Land		43,180.	
Total Est. Fed. Exp. W.P. funds on Program Evaluation		<u>2,425.</u>	51,265.
Difference			80,034.
50% of difference		40,017.	
Non-Fed. expenditures prior to designation of watershed		12,440.	
Amount of Non-Fed. contribution to meet 50% cost sharing		27,577.	

9/30/54

TABLE 3
Annual Costs
SANTAQUIN CANYON WATERSHED

	Amortization of Installation Costs				Operation and Maintenance			Grand Total
	Federal	Non-Federal	Private	Total	Federal	Non-Federal	Private	
"A" MEASURES								
(2) Desilting Basin	1,050.	200.		1,250.		200.		1,450.
(4) Channel stabilization above U.P.&L. Plant	170.	60.		230.		80.		310.
(5) Dike above U.P.&L. Plant	10.	80.		90.		10.		100.
(6) Channel Enlargement	160.	80.		240.		20.		260.
(7) Stabilization of critical areas	10.			10.				10.
Sub-Total Non-Federal Land	1,400.	420.		1,820.		310.		2,130.
(4) Channel Stabilization above U.P.&L. Plant	60.	20.		80.		60.		140.
(7) Stabilization of Critical Areas	1,560.		440.	2,000.	300.			2,300.
Sub-Total Federal Land	1,620.	20.	440.	2,080.	300.	60.		2,440.
Sub-Total "A" Measures	3,020.	440.	440.	3,900.	300.	370.		4,570.
"B" MEASURES	70.		270.	340.			50.	390.
TOTAL A and B Measures	3,090.	440.	710.	4,240.	300.	370.	50.	4,960.

9/30/54

TABLE 4

Summary of Average Annual Monetary Floodwater and Sediment
Damage and Flood Prevention Benefit from the Plan
SANTAQUIN WATERSHED, UTAH

Long-term Prices

DAMAGES	AVERAGE	ANNUAL	DAMAGES	AVERAGE	ANNUAL	BENEFITS
	Under Present Condi- tions	B Meas- ures Only	With A & B Meas.	From B Meas. Only	From A Meas. Only	Total Flood Prevent- ion Ben- efit from A & B
Floodwater & Sediment Damages (flood flows)						
Agriculture	\$ 430.	\$ 410.	\$	\$ 20.	\$ 410.	\$ 430.
Irrigation systems	170.	170.			170.	170.
Municipal	450.	450.	40.		410.	410.
Residential	600.	600.			600.	600.
Utilities	1,000.	1,000.	40.		960.	960.
Roads & bridges	500.	500.	70.		430.	430.
Sub-total	3,150.	3,130.	150.	20.	2,980.	3,000.
Sediment Damages (Normal flows)						
Irrigation systems	550.	540.	50.	10.	490.	500.
Channel & farm land	900.	900.	400.		500.	500.
Sub-total	1,450.	1,440.	450.	10.	990.	1,000.
Indirect Damages (flood flows)	320.	320.	20		300.	300.
Total Average Annual Damage	\$ 4,920.	\$ 4,890.	\$620.			
Benefit from reduction of damage				\$ 30.	\$ 4,270.	\$4,300.
Benefit from more intensive use of flood plain				-		
Total Flood Prevention Benefit				\$ 30.	\$ 4,270.	\$4,300.

9/30/54

TABLE 5

Distribution of Costs and Benefits by Measures
and Groups of Measures
SANTAQUIN WATERSHED, UTAH

Item	Average Annual					
	Total Cost	Average Annual Cost	Floodwater & Sediment Benefit	Conser- vation Benefit	Total Bene- fits	Benefit Cost Ratio
<u>"A" Measures</u>	\$	\$	\$	\$	\$	\$
Channel Improvements in- cluding desilting basin	53,761.	2,260.	2,770.		2,770.	1.23 to 1
Stabilization of criti- cal runoff and sediment producing areas	53,883.	2,310.	1,500.	1,090.	2,590.	1.12 to 1
Subtotal "A" Measures	107,644.	4,570.	4,270.	1,090.	5,360.	1.17 to 1
<u>"B" Measures</u>	7,960.	390.	30.	1,230.	1,260.	3.23 to 1
TOTAL	115,604 ^{1/}	4,960.	4,300	2,320.	6,620.	1.33 to 1

^{1/} Does not include the cost of program evaluation (\$2,425.)

TABLE 6

9/30/54

Desilting Basin Structure Data
SANTAQUIN CANYON WATERSHED

No.	Sq. Mile	Storage Capacity				Inches of Runoff	Surface Area		Ht.	Flood Plain Area		Volume	Draw	Type	Estimated		
		Pool	Pool	Total	Pool		Pool	Total		Pool	Pool					Feet	Pool
1	23.3	125 ¹ / ₄	84 ² / ₂	125 ³ / ₂	0.08 ⁴ / ₄	-	0.08	10.0	8.33	36	10.0	8.33	10.0	68,490	5/ ₅	Veg.	30,500

- 1/ Includes estimated deposition above spillway level - 40 A.F.
 2/ Capacity of pool for water at spillway level. This capacity is reduced by sediment which accumulates each year.
 3/ All storage is for sediment.
 4/ Spillway level capacity will serve as detention until water storage capacity is depleted by sediment deposit.
 5/ Structure not designed primarily as a detention structure. Outlets are provided to permit complete draining of the reservoir and to pass low peak, high volume spring snow melt flows.

9/30/54

TABLE 7

Summary of Program Data
Santaquin Canyon Watershed

ITFM	UNIT	QUANTITY
Years to complete program	Year	5
Total installation cost	Dollar	114,299
Federal	Dollar	85,839
Non-Federal	Dollar	28,460 <u>1/</u>
Annual O&M cost		
Federal	Dollar	300
Non-Federal	Dollar	420
Annual benefits	Dollar	6,620
Sediment Basin structures	Each	1
Area inundated by structures		
Floodplain	Acre	11.5
Upland	Acre	6
Watershed area above structures	Acre	14,926
Reduction of floodwater sediment damage (flood flows)		
"A" Measures	Percent	94.6
"B" Measures	Percent	.6
Reduction of sediment damage (Normal flow)		
"A" Measures	Percent	68.0
"B" Measures	Percent	.7
Other Benefits		
"A" Measures	Dollar	1,090
"B" Measures	Dollar	1,230

1/ Includes \$1,100 ACP

9/30/54

TABLE 8

Summary of Physical Data
SANTAQUIN CANYON WATERSHED

ITEM	UNIT	QUANTITY	
		Without Program	With Program
Watershed area	Sq. Mi.	42	42
Watershed area	Ac.	27,153	27,153
Area of Cropland	Ac.	6,207	6,132
Area of Grassland	Ac.	15,946	16,021
Area of Woodland	Ac.	5,000	5,000
Floodplain area subject to damage by design storm	Ac.	5,755	-
Annual rate of erosion			
Sheet	Tons/yr.	816	490
Gully	Tons/yr.	523	348
Streambank	Tons/yr.	5,749	3,484
Scour	Tons/yr.		
Area damaged annually by:			
Sediment	Ac.	2,400	-
Floodplain scour	Ac.	$\frac{1}{1}$	
Swamping	Ac.	$\frac{1}{1}$	
Streambank erosion	Ac.	$\frac{1}{1}$	
Sheet erosion	Ac.	$\frac{1}{1}$	
Sediment Production	Tons/Ac/Yr	9,339	5,718
Sediment Accumulation in reservoirs	Ac/Ft/Yr	4.9	3.0
Frequency of flooding	Events/Yr	0.1	0.012/
Average annual rainfall (9000' \pm)	Inches	35	35
Average annual runoff (5000' \pm)	Inches	15	15
Average annual runoff	Inches	12	12

1/ Not evaluated

2/ Summer flooding


LAND OWNERSHIP STATUS SANTAQUIN CANYON WATERSHED UTAH

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
SALT LAKE CITY, UTAH



Scale in Miles

JUNE 1954



LEGEND

- | | |
|-----------------------------|--|
| SEMI OR HARD SURFACED ROADS | |
| ALL OTHER ROADS | |
| TRAILS | |
| RAILROAD | |
| TOWN OR CITY | |
| SCHOOL | |
| CHURCH | |
| SPRING OR SEEP | |
| DRAINAGE | |
| IRRIGATION LATERAL | |
| WATERSHED BOUNDARY | |
| COUNTY LINE | |
| NAT. FOREST BOUNDARY | |

LAND OWNERSHIP STATUS

- | | |
|--|---------------------------|
| | NATIONAL FOREST |
| | BUREAU OF LAND MANAGEMENT |
| | MINING CLAIM |
| | PRIVATELY OWNED LAND |

BASE 6-5-13779

USA-904-ALBUQUERQUE, N. MEX. 904 M-532

Figure 2


**WORK PLAN
SANTAQUIN CANYON WATERSHED
UTAH**

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
SALT LAKE CITY, UTAH



Scale in Miles

JUNE 1954



LEGEND

- SEMI OR HARD SURFACED ROADS
- ALL OTHER ROADS
- TRAILS
- RAILROAD
- TOWN OR CITY
- SCHOOL
- CHURCH
- SPRING OR SEEP
- DRAINAGE
- IRRIGATION LATERAL
- WATERSHED BOUNDARY
- COUNTY LINE
- NAT. FOREST BOUNDARY
- STREAMBANK PROTECTION
- PROTECTION DIKE
- DEBRIS BASIN
- GULLY STABILIZATION STRUCTURE (SMALL)
- ROADSIDE EROSION CONTROL STRUCTURES
- CHANNEL ENLARGEMENT

BASE: 6-5-13779

1954-SC1-ALBUQUERQUE, N. MEX. 1054 M-533

Figure 3

9/30/54

COOPERATIVE AGREEMENT

Nebo Soil Conservation District

State of Utah

THIS AGREEMENT is entered into by the Nebo Soil Conservation District, hereafter referred to as the "District" and Santaquin Canyon Watershed Protection Committee hereafter referred to as the "Committee".

Object: The object of this agreement is to coordinate the activities and efficient use of the resources of the two parties in carrying out and maintaining watershed protection needed on watershed lands and the installation of such measures in the Santaquin Canyon Watershed, which is a part of the Nebo Soil Conservation District. Measures as described in the watershed projects work plan are planned for the purpose of reducing flood water and sediment damages to land owners and operators as well as other property owners within this watershed.

THE DISTRICT AGREES TO:

1. Sponsor Santaquin Canyon Watershed as one of the 62 pilot small watersheds projects of which there are two proposed in Utah.
2. Furnish technical assistance in the preparation of a cooperative work plan for the Santaquin Canyon Watershed.
3. Sign Trust Fund agreement with Soil Conservation Service covering non-federal cash payments agreed upon in work plan and by committee.
4. Furnish representative to annually inspect and observe watershed project for operation and need for maintenance. This may be made in company with Department of Agriculture representatives.
5. Give special emphasis to planning and application of Farmer-District conservation farm and ranch plans so far as assistance will permit.

THE COMMITTEE AGREES TO:

1. Arrange with local interests to raise at least 50 per cent of the cost of the project excluding funds spent for protection of Federal lands as indicated in work plan. Estimated cost break-down: Non-Federal expenditures prior to designation of watershed \$12,440; cost of "B" measures to be installed \$5,860; cost of deferred grazing on federal lands \$9,470. and cash or material and labor \$12,020. making a total of \$39,790.
2. Arrange for collection of contributions authorized and agreed to in meeting of committee on November 30, 1953. These are: Santaquin City, \$4,207.; Genola City, \$1,500; Utah County, \$1,442; Summit Creek Irrigation Company, \$1,923; Utah Power and Light Company, \$2,948.
3. Pay to Nebo Soil Conservation District the agreed to annual local contributions (cash, materials or labor) along with itemized statement of materials and labor expended toward completion of project.

9/30/54

4. Assume responsibility of annual operation and maintenance as follows: Summit Creek Irrigation Company will be responsible for operation and maintenance on the sediment basin including emergency spillway and canal floodway to Santaquin reservoir. Towns of Santaquin and Genola will be responsible for operation and maintenance of channel stabilization works from point 1/4 mile above Utah Power and Light substation to point 300' above upper city spring.

5. Furnish one or more representatives to accompany district representatives to annually inspect and evaluate operation and need for maintenance of project installation. USDA representatives may accompany this group on occasions.

6. Furnish the District with easements and rights-of-way as well as ingress and egress freedom for the planning and carrying out of this cooperative project work plan.

IT IS FURTHER UNDERSTOOD AND AGREED:

1. Both the district and committee will encourage the development as rapidly as feasible, a basic conservation plan with each farmer and rancher within watershed. These conservation plans will be pointed to using the land within its capabilities and treating it according to its needs for protection and improvement.

2. The District agrees to continue to furnish technical assistance to the extent available to advise and assist committee and local people to carry out this project according to the work plan.

3. The district will be held free from all claims for damages that may arise from the installation or operation of work installed in accordance with project work plan.

4. All amendments to the accepted project work plan will be mutually discussed and agreed upon by parties concerned before becoming effective.

5. Both parties will publicize project and assist in acceptance of watershed project by local and other interested people.

6. Progress of the Santaquin Watershed Project will be a part of the annual District reports to the State Soil Conservation Committee.

This agreement has been verbally in effect since committee was organized and is now set down in writing for future guidance of parties involved. It will continue in effect for a period of five years, and it will automatically be renewed from year to year thereafter. This agreement may be amended by mutual agreement.

Approved:

Santaquin Canyon Watershed Protection Committee

By /s/ Arthur F. Wickman Chairman Date: 9/27/54

By /s/ Lorenzo Clark Secretary Date: 9/27/54

9/30/54

Nebo Soil Conservation District

By /s/ Bernell Hansen Chairman Date: 9/30/54

By /s/ Roy Lyman Secretary Date: 9/30/54

Approval of this agreement given during meeting of Santaquin Watershed
Committee on 9/27/54 and Nebo Soil Conservation District on
9/22/54.